Growing Out before Out Growing

Flexible Housing for New Zealand

Liam Playle

Growing Out before Out Growing

Flexible Housing for New Zealand

Liam Playle

A 120 point thesis submitted to Victoria University of Wellington in partial fulfilment of the requirements for the degree of Master of Architecture [Professional]

Victoria University of Wellington

2020

Figure 1: 1:1 M8RX prototype cladding installation

AMPD Mission Statement:

The following thesis is part of the Advanced Manufacturing and Prototyping for Design Research Lab. AMPD aims to investigate and define innovative techniques and methods of modern construction applicable to the architecture and construction sector through the use of advanced tools of design, fabrication and manufacturing. The fourth industrial revolution is core to our research, exploring methods of improving information flow from design to fabrication, across the digital continuum, to design architecture that builds wellbeing for people and the planet. We can't keep doing what we have always done. Our research questions the status quo by designing and constructing prototypes. You should consider the thesis within the larger body of research that AMPD Research Lab undertakes. Each thesis has focused on an aspect of AMPD's aim.

Funded from the
Building Research Levy

Figure 2: Fastmount clip installation

Abstract

Housing in New Zealand often makes its way into the headlines, with issues such as demand, shortfall and affordability dominating the news. There is, however, one issue that is prevalent but is barely addressed. This is the issue of suitability. Many New Zealanders are living in houses that are inappropriate for their needs. This problem exists along a spectrum and affects everyone. The truth is, at some stage in our lives, we may find ourselves living in a house that is either too big or too small.

The purpose of this research is to investigate whether flexible housing is a feasible solution to address the problem of suitability. This is achieved through the design of a modular prefabricated construction system and the design of a connection which facilitates this flexibility. This system consists of a prefabricated modular panel system and a designed connection, which allows the physical fabric of the house to be altered, so it can increase or decrease in size to suit its occupants'.

The feasibility of this system has been evaluated through the construction of a full-scale prototype and the design of a house to test its flexible abilities. Fundamentally, this research should hopefully change the way we think about constructing homes in New Zealand. An inversion of the current process and will see home construction suited to the occupant at the very beginning, middle and end of their lifespan instead of just a potentially small period. This solution could also bring about change in the way we finance our homes allowing for incremental change and incremental investment over the lifetime of the building.

Supported By:

Acknowledgements

There are many people I would like to thank and acknowledge for their support in helping this research develop over the past year. It has been a difficult year with all that has been going on in the world, but those obstacles have made the desire for success even greater.

A special thanks to my supervisors Jae Warrander and Guy Marriage whose support and knowledge has been exceptional. These two individuals span two different generations of the same industry and I couldn't have asked for two better people to lead me along the journey. Without your assistance, support and the occasional push in the right direction, none of this would have been possible.

Secondly, I would like to thank all the amazing people who have assisted me at some stage along this journey.

- BRANZ and the AMPD committee for awarding me with the BRANZ Future Design Thinking for Construction Scholarship. Without your funding all of the prototyping, materials and tools purchased in relation to this project would not have been possible.
- Phil and Josh from the workshop for helping with all the CNC machining seen in this thesis. The knowledge and trust that you have passed onto me to operate the CNC machine is a much-appreciated skill and one that can be added to the CV for sure.
- Mitchell Holden from First Light Studio and Sarah Cox from the University of Auckland Architecture Archives for sharing the access to very rare documents on the IBS building system.
- Chris and Craig at City Timber for supplying Plywood and Cladding.

A huge thanks to my friends back in Auckland and my flatmates Rebecca, Ella, and Sophie. All of you created the best environment to get away from university and made my year so rewarding.

Finally, I would like to thank my family for helping me and supporting me when I needed it the most. Mum and Dad; thank you for all your support through my 5 years of university. You were always there when ever I felt alone or overwhelmed and needed someone to talk to. Hopefully someday I can repay you and design that dream home for retirement. To my girlfriend Sophie, you joined me halfway through this journey and I am so grateful to have shared it with you. You have seen me cry more times than you should, but have always been there to pick me back up on my bad days and encourage me to keep going and finish.

Because of all of you, I have completed my Masters of Architecture (Professional). Now.... Time to find a job.

Contents

Ampd Mission Statement	iii
Abstract	v
Acknowledgements	vi
1 Introduction	1
1.0 Introduction	3
1.1 Aims and Objectives	4
1.2 Scope	4
1.3 Research Approach	5
1.4 Design Research Methodology	6
2 Background	9
2.0 The Issue	11
2.1 Housing and Maori and Pacific People	13
2.2 Housing and the Aging Population	15
2.3 Key Learnings	17
3 The Build Method	19
3.0 Traditional Construction Method	21
3.1 The Builder	23
3.2 Traditional Construction Method Analysis	23
3.3 Conclusion	30
4 Prefab, Modular & Digital Fabrication	31
4.0 Preface	33
4.1 Prefabrication Background	34
4.2 Prebrication as a Solution	34
4.3 The Role of the Joint/Connection	35
4.4 Modular Construction	37
5 Prefab & Flexibility	39
5.0 Preface	41
5.1 Industrialised Building System	44
5.2 Packaged House & General Panel Company	50
5.3 Critical Reflection	55

6 Concept Design	57
6.0 Preface	59
6.1 Methodology	60
6.2 Modernising IBS	61
6.3 Analysing IBS	61
6.4 Panel Design	65
6.5 Detailed Panel Connection	67
6.6 Module Form Testing	69
6.7 Module Layout	75
6.8 Foundations and Floor	85
6.9 Revisiting the Modle Arrangement	93
6.10 Critical Reflection	95
7 Developed Design	97
7.0 Preface	99
7.1 Panel Design	100
7.2 Roof Design	103
7.3 Window Integration	105
7.4 Linear Expansion	109
7.5 Lateral Expansion	109
7.6 Critical Reflection	109
8 M8RX System	111
8.0 Preface	113
8.1 Introduction to the M8RX Building System	115
8.2 Components	115
8.3 Panels and Cassettes	116
8.4 Floor	135
8.5 Roof	137
8.6 Fabrication and Assembly Process	139
8.7 Integration of Services	139
8.8 Transport and Onsite Assembly	139
8.9 Panel to Panel Joint	143
8.10 Panel to Floor Joint	143
8.11 Panel to Roof Joint	143
8.12 Critical Reflection	143

9 Fabrication and Assembly	145
9.0 Preface	147
9.1 The Prototype	148
9.2 Fabrication	150
9.3 Fabrication Issues	152
9.4 Panel Component Assembly	156
9.5 Panel Component Assembly Issues	162
9.6 Critical Reflection	163
10 M8RX House	165
10.0 Preface	167
10.1 Client Selection	168
10.2 The Client	169
10.3 The Build	170
10.4 Linear Expansion	172
10.5 Lateral Expansion	174
10.6 Critical Reflection	176
11 Critical Reflection	177
11.0 Preface	179
11.1 Process Reflection	180
11.2 Research Limitations	180
11.3 M8RX System Improvements	180
11.4 Future Directions	181
12 Final Remarks	183
12.0 Final Remarks	185
13 Bibliography	187
14 Illustration Sources	191

No material within this thesis may be used
without permission of the copyright owner

*"Any house is a continuous process of growth and
change"*

- Tony Watkins, 'The Human House'

Dedicated to Nana

Introduction

- 1.0 Introduction
- 1.1 Aims and Objectives
- 1.2 Scope
- 1.3 Research Approach
- 1.4 Design Methodology

1.0 Introduction

New Zealand has a big problem when it comes to the unsuitability of housing. Urban developments and new subdivisions insist on the continued and replicated use of the 3-bedroom model of standard mass-produced housing, yet the consensus among many New Zealanders is that this prominent model of housing doesn't fit the needs of the population (Stats NZ, 2020b, p. 20). Of those surveyed in the 2018 census who declared their homes as unsuitable, 54% stated that size of their homes, being either too large or too small was a contributing factor (Stats NZ, 2020b, p. 96). Houses are a static entity and a population consisting of many different people, each with their own unique family dynamics, are forced to live out their lives inside the confines of a house that is designed for only a select group of people. Over time, the constructs of these families and individuals change and yet their homes remain the same, fixed in the state they were in when they were built or bought. With house prices continuing to rise in New Zealand, simply moving to a house that could be defined as 'more suitable' becomes an increasingly difficult task on its own, and one that is not an adequate solution (Gibson, 2021).

New Zealand is also facing a demographic shift in the coming years towards a country with an aging population. As the compositions of households change in the coming years, the way we build is also going to need to change to follow suit. This means that simply building more houses is not the answer to fix the country's significant shortfall. Instead, a tailored approach is required where housing can be constructed, and modified according to the occupants' needs, thus making them more affordable and suitable. This research looks towards a modular system which can facilitate change to the physical fabric of the house. As the needs of the occupants change the house can change with them allowing it to remain suitable for their needs, whatever they may be. Therefore, this research can be categorised by the following question:

"How can a designed connection in combination with a modular building system be applied to the construction of houses in New Zealand to create flexible homes which can change with the occupant?"

1.1 Aims and Objectives

In response to the question, this research aims to develop modular flexible building system and a designed connection with the intention of using this system to construct flexible houses. The outcome of this research is to explore whether flexible housing and a prefabricated system has the potential to address some of New Zealand's critical issues surrounding housing.

The following research objectives are:

- To analyse and evaluate the current build method and establish the issues which prevent flexible housing from being constructed using this method.
- To design and prototype a modular flexible building system and designed connection and evaluate its ability to change and adapt to a wide range of situations.
- To design an organisational module on which this system could be applied to produce flexible houses.
- To produce a full-scale prototype panel and connection assembly to demonstrate the build potential and evaluate the systems feasibility.
- To produce a concept 'Flexible House' and evaluate the systems performance against a client and their changing needs.

1.2 Scope

"Flexible Housing" by nature is a deliberately broad term and encompasses many varied types of housing with the ability to change and adapt to a variety of conditions all over the world. For clarity, this thesis aims to focus on the growth and change of the house over an extended period of time, specifically relating to the lifetime of a house. Ultimately the goal will be to create flexible housing that in Steven Groak's words is "capable of different physical arrangements" (Groak, 1992, p. 17). This will show that flexibility is able to be achieved through changes that alter the physical fabric of the house, specifically external and internal changes that are permanent

1.3 Research Approach

The approach to design led research in this thesis has been deliberately practical. From the beginning, the aim was to develop a designed, prefabricated solution that could be easily used and constructed in the New Zealand context. As a result, structural research, materials analysis and scale assembly tests have all been used as a means to iteratively develop an alternative solution to the way that we construct houses. This is a solution that is no longer static but purposely designed and built with change in mind. The thesis is split into three main parts.

Section one: This section addresses the issues with the way that homes are constructed in New Zealand today. It provides insight into the issues facing the housing industry such as the shortage, unsuitability, unaffordability, and poor construction. This section goes on to discuss proposed solutions for flexible housing and their relationship to the New Zealand context. The ideas of prefabrication and digital fabrication as an answer to these problems are discussed in this section as well as an evaluation of prefabricated and flexible systems which could be used.

Section two: This section begins the conceptual design research process based on research undertaken in section one. It is here where the authors own solutions to a flexible, prefabricated system are designed, tested and refined. The central problem is defined around flexibility and this is used as a basis on which to critique the designed solutions. The evaluation of historical precedents undertaken in section one will create a starting point at which to begin designing.

Section three: Introduces the designed solution to the real world and tests its flexibility and ability to change in a series of real-world scenarios. These scenarios are modelled off the requirements established by a client. The versatility of the system is against a brief to observe its performance.

1.4 Design Research Methodology

In order to reflect on the practical intentions of the research objectives, a design led methodology was created based upon extensive use of detailed scale and prototype modelling. These models are both physically and digitally explored to investigate a wide range of possible solutions as well as the issues associated with designing with flexibility in mind. A process of design, build, test and evaluate was carried out using digital sketch modelling and physical fabrication using both CNC (Computer Numerically Controlled) and laser cut models which allowed for unrestrained conceptual experimentation.

During the design led research phase a macro to micro approach is used. Initial design research looks at all the larger parts of a house that restrict change and narrows in on these areas. These areas such as wall to wall connections, roof to wall connections and floor to wall connections become the focus of the research. The findings of this design led research is then presented through a proof of concept in the form of a full-scale prototype and conceptual house in the hopes that the findings will lead to change in the construction and housing industry to further explore the potential of flexible housing.

"How can a designed connection in combination with a modular building system be applied to the construction of houses in New Zealand to create flexible homes which can change with the occupant?"

Problem

1

Background

2

The Build Method

3

Prefab & Modular

4

Case Studies

5

Concept Design

6

Developed Design

7

M8RX System

8

Fabrication & Assembly

9

M8RX House

10

Critical Reflection

11

Conclusion

12

Background

- 2.0 The Issue
- 2.1 Housing and Maori and Pacific People
- 2.2 Housing and the Ageing Population
- 2.3 Key Learnings

2.0 The Issue

New Zealanders face a shortage of dwellings of just about every description, while paying far more for those we do have (Bassett et al., 2013, p. 2). It is estimated that current shortfall of houses in Auckland exceeds 28,000 while nationally, that number outstrips 45,000 (Johnson et al., 2018, p. 23). If current trends continue the way they are, Prefab NZ estimates that New Zealand could have a shortage of 100,000 houses by 2030 (Prefab NZ, 2015, p. 1). In direct contrast to our housing shortage is our booming construction industry. The construction sector shows no signs of slowing down, with a record number of 38,000 new homes being consented in 2020. This is the highest number since 1974 (Stats NZ, 2020a).

This image has not been reproduced due to Copyright

Figure 6: New suburb development in Milldale

Despite our increasing build numbers, the shortage of houses continues to rise, and the unsuitability of available and future housing stock becomes a significant issue. At present, the Labour Government have pledged to build more than 18,000 public houses by 2024 (Arder, 2020) on top of those built privately or by development firms in expansive new subdivisions. While new houses are much needed, the issue around how they are built and their composition is problematic and calls for change. Housing on a mass-produced scale provides very little in the way of variation between houses. Developers want the best return on their investment and in turn, minimal variation between designs reduces the overall cost to produce these houses. Aside from a different exterior material, colour or interior layout, mass produced housing lives up to its designation. As a result, these houses are problematic for the people who are going to occupy them, as standard and similar designs are expected to accommodate families and individuals with varying needs. The 'one size fits all' approach that we are trying to remedy the housing crisis with, is instead the 'one size fits few' and the problem will be exacerbated each year until the issue of suitability within the houses that are being built is addressed.

Figure 7: Identical houses under construction in Auckland

Trends in the size of houses that New Zealand is building have also changed over the past 40 years. In 1976 the average size of a new house was 121m². By 2011 this size had expanded to 220m² (Dudding, 2010). In Auckland the average size further balloons to a whopping 230m² (Johnson et al., 2018, p. 24). While in recent years the average size of new homes had decreased to

180m², the large sizes are a stark contrast to the number of occupants living in these homes (Stats NZ, 2020d). In 2018 the average number of people per household was 2.6, a slight drop from an average of 2.7 people in 2013 (Stats NZ, 2020c). As the trend suggests, New Zealand's average household size is predicted to fall to 2.4 people by 2031 meaning that we are building more rooms for fewer people (Dudding, 2010). Not only this, but a large percentage of our current stock is occupied by sole occupants as a result of the country's aging population. As family sizes reduce, median ages increase, along with the demand for housing. Leonard Hong, of the New Zealand Initiative summarises this problem perfectly with the following statement:

"When the typical group of a hundred people consists of 20 couples, each with two young kids, and ten retired couples, those hundred people fall into 30 households. Thirty homes might be needed. When the hundred are instead 15 couples with two kids each and 20 retired couples, 35 homes may be needed" (Hong, 2021).

As our population continues to age, this naturally occurring phenomena further adds to the housing shortage. As of 2013, 23% of New Zealand's housing stock was occupied by a single occupant meaning that the two-, three- or four-bedroom homes that are out there are off limits to the hundreds of families who would better suit them. This is what is called the 'empty nest' syndrome, proving that New Zealand needs to prepare for its changing demographics in the coming years (Jeram, 2014, p. 2).

2.1 Housing and Maori and Pacific People

New Zealand's issues around housing disproportionately affect Maori and Pacific people. Home ownership in New Zealand has been in decline since it peaked in the early 1990s and the national average sits at 64.5% as of 2018 (Stats NZ, 2020b, p. 28). Maori and Pacific people especially have been hit the hardest, with ownership rates declining steeply during this time. As of 2013 only 35% of Maori and 24% of Pacific people own their own home (Stats NZ, 2016, p. 7).

A large percentage of Maori and Pacific people are settled in the urban areas of Auckland, particularly the South which is dominated with state housing settlements. Houses in these areas were built in the post-war boom of the late 1940s and the uniformity of design and the emergence of low income families created 'ghetto' communities (Ministry for Culture and Heritage, 2014). The ramifications of this era of state housing are still prevalent in the area today with many of these houses still standing. The size of these houses is also reflective of

This image has not been reproduced due to Copyright

Figure 8: Low quality state houses

the time they were built in with their size falling well below the average for the modern New Zealand home. The suburb of Manurewa in the south of Auckland contains an average home size of 152m² (Stats NZ, 2020d).

Homes of this size are indicative of the lower quality of life often reported by those living in them. This is due in part to household crowding. Nearly 6% of New Zealand's households are crowded, with rates highest among Maori and Pacific people (Stats NZ, 2020b, p. 97). Almost 1 in 9 people lived in a crowded household with the highest rates in the South Auckland areas of Mangere, Otahuhu, Otara and Papatoetoe (Stats NZ, 2020c). A correlation can be drawn between household size in these areas and house size as the reason for the overcrowding. Household sizes in South Auckland on average were larger than the national average with the highest being 4.0 people per household in Mangere and Otahuhu (Stats NZ, 2014). Another reason for the crowding has been the rise in the multi-family household. In 2018, 19.5% of Pacific peoples and 11.4% of Maori lived in a household with two or more families (Stats NZ, 2020b, p. 128). While the majority of New Zealanders rated their house as suitable, people living in crowded housing were found to have the opposite opinion. 65,540 households said that they required one additional bedroom and 24,620 households believed that they required two extra bedrooms.

2.2 Housing and the Aging Population

New Zealanders have a special connection to housing, especially the elderly who own their own home and have forged that connection over many years. Home ownership has held steady at around 86% for those aged 65 and over in recent years (Johnson et al., 2018, p. 41). Many of these people share a strong desire to remain living independently in their own homes for the rest of their lives under the concept of "Ageing in place". Ageing in place encourages and assists older people to remain in their own homes, in order to enhance their sense of independence and self-reliance (Davey, 2006, p. 2). Ageing in place can be difficult when trying to live out an elderly life in a home which is not suited to its elderly occupants. As many of those over the age of 65 have expressed some concern that their current house would not be suitable to live out the rest of their days.

One of these concerns is related to house size. Studies in Australia which have relevance to New Zealand show that among houses owned by elderly couples, 82% were living in homes with at least 3 bedrooms (Jeram, 2014, p. 7). This is the most common type of house and one that older people may have raised a family in, making the decision to leave even more difficult. Sometimes however the decision to leave or downsize is prevented by a lack of suitable alternatives. In particular it has been argued that the under supply of smaller housing options effectively prevents owners from downsizing at all (Jeram, 2014, p. 7). As far back as the 2006 the number of one and two-bedroom dwellings fell by 4.8%, the biggest decline out of any number of dwelling sizes from last census at this time (New Zealand Department of Building and Housing, 2010, p. 46). Data available today from the recent 2018 census indicates this number has declined even more, adding further demand for dwellings of this size (Stats NZ, 2020b, p. 20).

The second of these concerns was related to maintenance of the home. These concerns tended to come from people who were still living in original family homes that were becoming less suitable for ageing in place. Judith Davey, a researcher for the New Zealand Institute for Research on Ageing interviewed a select number of elderly people in the community who thought their houses and sections were too large (Davey, 2006, p. 7). Around half of the participants did not see any problems with themselves being able to undertake renovations as they were used to doing much of the work themselves but many were aware that they were beginning to experience limitations on the work that they could and could not do due to their increasing frailty with age.

64.8%

Home ownership in New Zealand in 2013

Average household size in New Zealand in 2013

2.7

↓9%

Decline in home ownership since 1991

Sole occupant household aged 45 years or older

79.9%

24%

The percentage of home owners who move to a more suitable home

Maori experience crowded conditions in households in New Zealand

1 / 5

↓20%

Decline in Maori home ownership between 1986 and 2013

Pacific people are living in a crowded household

4 / 10

23.5%

Percentage of sole occupant households in New Zealand

2.3 Key Learnings

As mentioned at the start of this research, New Zealand's proposed solution to the housing crisis, of simply building more houses and believing that the problem will sort itself out is not the way to address this issue. As households in New Zealand have gotten smaller, their compositions have also changed, and yet our approach to building houses has remained the same. While it is important to build fast and keep building, this change must come to the forefront of the industry and occur sooner rather than later to prepare us for the inevitable changes in our population's demographics. If not, we could see future generations locked out of housing for good, and current generations with no suitable alternatives apart from the houses they currently reside in. Statistics New Zealand's 'Housing in Aotearoa: 2020' report which has been a key source of information in this chapter, concludes with this idea too.

"Whilst the classic Kiwi three-bedroom, stand-alone home may remain a staple for a while, the New Zealand homes of the future will likely need to change. It is not just about the numbers but the suitability of housing to meet growing and changing demand that is of key importance" (Stats NZ, 2020b, p. 130).

This research has shown that problems exist along every inch of the spectrum, with all issues highlighted in this chapter of equal importance to the one which came before. While there are many areas which require attention, they can be broken down into 3 key areas that need to be addressed.

- Creating the ability for people to build small for what they are able to afford or need to begin with when building their first home.
- Creating the opportunity for people to expand their home if needed based on a growing family unit or an improved financial situation.
- Making sure occupants to remain comfortable in their homes by allowing for the necessary changes that come with growing families and aging in place.

Our current process of designing and building houses does not consider these factors when constructing new homes and instead leaves us stuck somewhere around the middle where new homes are built always around the idea that they will be occupied by a family. New Zealand architect Tony Watkins describes this process as an “arrival” to a finished product rather than a “journey” (Watkins, 2009, p. 16). Watkins believes that we go about designing houses the wrong way, “expecting the newly married couple to know how many bedrooms they will need or if grandma will fall ill and need to be close by” (Watkins, 2009, p. 52). New Zealanders are expected to make a courageous attempt to look 30 years into the future when building their homes. A change to the build process to allow for incremental construction and the ability to change would grant New Zealanders the ability to make the decision for themselves on when they need to expand or grow their homes.

The Build Method

3.0 Traditional Construction Method

3.1 Traditional Construction Method Analysis

3.2 The Mini Wall

3.3 Conclusion

3.0 Traditional Construction Method

New Zealand's current construction method sees houses built out of light timber frame. This method of construction sees individual pieces of timber, sawn to the desired length and then nailed together onsite to create the main structure of the dwelling (Isaacs, 2010, p. 119). For the most part of the last century this method has gone unchanged as New Zealand had the available resources to produce large amount of timber frame relatively quickly and cheaply leading to it becoming the dominant method of building for the construction of new houses for New Zealand's growing population (Isaacs, 2010, p. 119). As of today it is estimated that up to 90% of homes are constructed using light timber framing (Rosevear & Curtis, 2015, p. 5).

Figure 10: Ballon frame construction (left) and platform frame (right). Two examples of light timber frame construction in New Zealand

While light timber framing is still our primary building method, its issues become apparent when wanting to build a large number of houses in a short span of time. A BRANZ study report estimated that to build a 120m² home onsite using the traditional methods it can take 14 weeks (Burgess et al., 2013, p. 25). This estimate of course doesn't factor in New Zealand's weather which plays a significant role in prolonging construction times as well as the fact that the growing size of New Zealand houses means that construction times are also longer than this estimate. The current method also uses materials and structural components which are static. This way of building does not factor in change as we build houses with the intent of the structure lasting as long as possible. Any change that does occur is then usually permanent and designed to blend in with the rest of the original structure. To analyse whether it is possible to build flexible homes using our current construction method, a small segment of wall has been constructed to test its flexibility and adaptive potential.

Figure 11: NZS3604 timber framing

3.1 The Builder

A large part of this research involves testing and analysing the results of building and fabricating. To undertake this research, the author has taken the role of the “builder”. This role has created the opportunity for the author to have a “hands on” approach when designing, and building — something that the architect of today rarely has the chance to do. The author’s building skills could be described as amateur level, having had experience with DIY and a familiarity with basic principles of construction. This amateur level of expertise allows for greater insight into the complexities of the current build process and suggests that a build method that aims to promote flexibility should be simpler so that changes to the physical fabric of the home can be easily undertaken.

3.2 Traditional Construction Method Analysis

Mini Wall:

To investigate the traditional construction method a segment of wall was constructed following the guidelines outlined in NZS3604 for timber frame construction. The wall measures 1.2 m x 1.2 m and is constructed out of standard 90x45 timber framing which is nailed together. A centre stud with dwangs either side creates a standard stud spacing of 600mm. It is wrapped in building paper and clad in weatherboards to mimic a plain lapped style cladding. Inside the wall are fixtures such as a water pipe and an electrical wire simulating the items which would be found inside the walls of all homes. Lastly the interior is lined with 10mm GIB® board.

Figure 12: Exterior cladding and internal component of the mini wall.

Figure 13: The Builder

Figure 14: Mini Wall Construction Sequence

Figure 15: Attaching a dwang to the studs with a nail gun

Figure 16: Nailing the weather boards to the cavity battens

Flexibility Task:

The author was tasked with creating a partition at the midway point of the wall. The purpose of this exercise was to test the difficulty of the task and to see whether light timber framing in its current form was flexible and able to change to a given scenario.

Flexibility Test:

The demolition of the interior lining came first. The GIB® lining would have to be removed to create a new 'Internal T Intersection' for the new studs. The GIB® material was fragile and crumbled easily when being removed from the wall. Additional factors such as plaster and fill in the joins were not considered on this model. The interior of the wall featured a single stud. The middle stud and dwangs either side would need to be removed for the new double stud placement. The addition of a water pipe and an electrical cable would make this removal extremely difficult, and, in the end, it was decided to remove the cable and pipe by cutting them and replacing them later. The middle stud and dwangs were removed with some forceful demolition. The use of nails made this task quite difficult and protruding nails that were left sticking out had to be cut flush so that the new dwangs could be installed (Fig: 19). New timber was cut to size and nailed in place. New cable and a new water pipe were also installed during this time before the interior lining was replaced on the inside.

Figure 17: Demolition of internal lining

Figure 18: Removal of internal services

Figure 19: Nails protruding from the bottom plate after the centre stud was forcefully removed

Figure 20: Demoliton and alteration sequence

Results:

While the task was able to be completed, there were some key issues that would need to be addressed going forward. Material choice became a prime concern. The use of GIB® board for the interior lining was unable to be reused once it had been forcefully removed from the wall. As a result, all new material was used to reline the wall. Permanent fixings such as nails also severely impacted the ability to modify the wall. The use of adhesives to fix interior linings to the studs would also have had a significant impact had they been used here too. The biggest obstacle encountered was the existence of services in the wall such as the electrical wire and the water pipe. No modifications were able to be undertaken without the time-consuming removal of these fixtures. These services are also critical fixtures, meaning their replacement was compulsory, further adding to the difficulty of the task. If the wall was to revert back to its original status, then all of these issues would need to be addressed again.

3.2 Conclusion

The mini wall test offered a clear insight into the difficulty of adapting conventional structures to changing needs. It is evident that the current build process is one that is not suitable for creating flexible houses and a new construction methodology must be explored. Material and structural testing analysis will become a key component of the research going forward to determine a new method for constructing houses. Permanent fixings will need to be eliminated or at the very least kept to a minimum as these are one of the biggest factors which restrict change. Lastly, there must be a separation of structure and services. Services are key to the building but provide the biggest hurdle when trying to change. Designing a solution which encompasses these three issues will be critical to developing flexible housing.

Prefab, Modular & Digital Fabrication

4.0 Preface

4.1 Prefabrication Background

4.2 Prefabrication as a Solution

4.3 Role of the Joint/Connection

4.4 Modular Construction

4.0 Preface

Initial design research, investigating New Zealand's primary build method, deemed that this mode of traditional construction does not lend itself to principles of flexible housing. This chapter will provide a brief background into prefabrication and how alternative methods of construction involving prefabrication and digital fabrication can be utilised in the construction of flexible housing. An analysis of jointing methodologies and modular construction is also undertaken to determine the role that these aspects play in relation to flexible housing.

4.1 Prefabrication Background

Prefabrication is a method of construction where elements of a building, ranging in scale from components to a complete building, are manufactured offsite. These elements are then transported to the building site and assembled on prepared foundations (Serratts, 2012, p. i). It is a well-established practice of building in New Zealand. In 2013 it is estimated that 32% of New Zealand homes incorporated some form of prefabrication (Moradibistouni et al., 2018, p. 137). Because prefabrication refers to anything constructed offsite this figure also includes the many homes which feature pre-nailed frames and trusses which are then assembled onsite this elevates this number significantly. Discounting for these inclusions, real figures show that only 2% of buildings have their elements completely prefabricated (Moradibistouni & Gjerde, n.d., p. 428).

4.2 Prefabrication as a Solution

At present, New Zealand is facing a large structural timber shortage (Pearse, 2021). Accelerated demand for timber caused by New Zealand's booming construction sector and Carter Holt Harvey's recent decision to cut supply to retailers Mitre 10, ITM and Bunnings Warehouse could force the construction industry to explore alternative material and fabrication methods to meet demand. It is here that prefabrication and digital fabrication methods could bridge this gap between a shortage in desired materials, and the demand for more houses.

CNC (Computer Numerical Control) technology unlocks the opportunity to use typical construction materials in new ways, and as a result it is changing the way architecture in New Zealand is being constructed. CNC has gradually started to compete with traditional fabrication delivery methods by providing high precision, greater variety, faster manufacture, lower costs and safer options of assembly (Denhardt, 2016). The result of this has seen plywood used extensively for its CNC manufacture capabilities, creating structural members from the fabricated pieces, proving its worth not just as a cheap, sheet bracing but as a dependable, light, flexible and durable digital building material.

4.3 Role of the Joint/Connection

On the most basic level, the joint is the interface on which building elements are assembled in order to make them continuous or form a unit of parts (Escaleira et al., 2019, p. 2). The joint itself is the most critical component that could aid itself to flexible housing. Konrad Wachsmann in his book, 'The Turning Point of Building', believes that the design and adoption of a particular joint depends not only on the technical considerations of that joint but also the nature of the problem that the joint is trying to solve (Wachsmann, 1961, p. 76).

Assuming the most basic arrangement of a grid, building elements in this arrangement can only be placed alongside or at right angles to each other. A noteworthy discovery is that these types of connections not only occur in a horizontal arrangement (plan) but also in a vertical (section). This results in only four possible types of connections (Wachsmann, 1961, p. 76).

- Two-way connections
- Three-way connections
- Four-way connections
- Two-way connections forming a right angle

Wachsmann's theory on the design of joints and connections also takes into consideration whether the intention is to build with elements "which will be permanently fused together after erection; or with a system capable of being demounted just as easily as it was assembled" (Wachsmann, 1961, p. 82). As this research has a clear focus on flexibility and being able to alter and make changes to the physical fabric of the building, the latter has been established. The condition of flexibility will therefore have a decisive influence on the design of such a connection (Wachsmann, 1961, p. 82).

He states that assembly processes of the building systems itself are critical to the design of the joint and that they must be clearly thought out (Wachsmann, 1961, p. 84). These particular systems must take care to ensure that there is room left to insert the last key piece in the same way that all other parts were inserted. A complex jointing mechanism which requires elements to be installed in a certain direction could contribute to these problems and should be avoided. Lastly the undermining factors which determine the usefulness of the connection is its thermal quality, permeability, anti-condensation and acoustical properties. These need to be taken into careful consideration and implemented in the design of such a connection. (Wachsmann, 1961, p. 84).

Figure 22: The five fundamental ways in which surfaces can be related at a joint. They are identical with the way possible relationships between building elements, both in the horizontal and the vertical

4.4 Modular Construction

There is an assumption that the more prefabricated a building is the more closed it becomes (Smith, 2010, p. 124). This is in fact the opposite as many modular systems are designed with the purpose of being manipulated, added to, and subtracted over the course of their lifetime (Smith, 2010, p. 124). Modular construction therefore lends itself to the principles of flexible housing.

A module is a standardised unit of construction that is designed for ease of assembly (Smith, 2010, p. 161). The module is of key importance as it dictates the positioning and size of building elements as well as their placement for use within the given constraints of the system (Smith, 2010, p. 125). Mentioned previously, Wachsmann, a pioneer of modular design and construction believed that the deciding factors on size should be made after analysing the relationships between some or all of the following categories (Wachsmann, 1961, p. 55):

- **Material Module**
- Performance Module
- Geometry Module
- Handling Module
- **Structural Module**
- Element Module
- **Joint Module**
- Component Module
- Tolerance Module
- Installation Module
- Fixture Module
- **Planning Module**

To be concise, only the categories in bold were discovered to have relevance to this research and they have been elaborated on further in this chapter.

Material Module

The material module is the outcome of raw material sizes and materials which have been processed into industry adopted, predetermined sizes (Wachsmann, 1961, p. 60). The widespread use of sheet material which comes in standard widths and heights can correspond to a given module size.

Structural Module

A structural module determines the relationship between structural elements which carry load, and filler elements (Wachsmann, 1961, p. 61). Importantly, structural modules dictate the position of fixed and hinged joints connecting structural members, critically deciding which members are static and must not be moved and which members are dynamic and can aid in flexible construction (Wachsmann, 1961, p. 62).

Joint Module

The joint module has a direct relationship to the structural module and determines the position of every point of direct connection between structural and filler elements (Wachsmann, 1961, p. 66). The joint module in some cases performs not only as a means of fixing one element to another but also to transmit stresses from the loading of one structural element to the next. This may result in the accumulation of many joints in high stress areas disrupting modular coordination (Wachsmann, 1961, p. 66). The joints themselves should be distributed in a geometrically proportional manner ensuring symmetry on that module axis.

Prefab & Flexibility

- 5.0 Preface
- 5.1 Industrialised Building System
- 5.2 Packaged House
- 5.3 Critical Reflection

5.0 Preface

The following precedents were selected based on their unique and innovative architectural construction methodologies and how they support and amplify the rationale of this thesis. These precedents are the Industrialised Building System and the Packaged House. The following part of this chapter explores the history of these systems and their prefabricated system and connection designs.

Figure 24: Logo for the Industrialised Building System

Figure 25: Logo for the General Panel Company

5.1 Industrialised Building System

Architects: Roger Hay & Ivan Juriss

Location: New Zealand

Date: 1970-1980

System Type: Panel and Designed Joint

Background:

Industrialised Building System or IBS for short was the brainchild of Palmerston North property developer Keith Clark and brought to life by Architects Roger Hay and Ivan Juriss. Hay was frustrated at the idea of transporting prebuilt houses over long distances and decided a new approach to building and transportation was required (Hay, 2012, p. 26). The solution came from America in the form of the 'mobile home' — an odd choice considering it had no connection with the accepted concept of building in New Zealand. Associated with producing instant slums and with no ties to conventional housing due to their unusual aesthetic, the concept was a hard sell. Initially, architect Ivan Juriss was reluctant to take up the challenge of designing a 'better' version for the New Zealand market, and decided that the New Zealand concept had to break ties with its American counterpart's 'mobile concept' (Hay, 2012, p. 27).

Figure 27: The American mobile home on which the IBS concept was based

System & Connection:

The first Juriss image for the new concept reduced the idea down to a prefabricated modular sandwich wall, ceiling and floor system that could be assembled into modules rather than being towed to site as mobile home were (Hay, 2012, p. 28). It was in the planning that Juriss made the most significant breakthrough, realising that a standard unit known as a 'single wide' could be extended to a 'double wide' by duplicating new modules alongside the existing ones. Further lateral expansions could also be created through a small "link unit" to move beyond the 'double wide' structure (Hay, 2012, p. 29). It was at this moment that flexibility became a keynote of the IBS approach to building as one that would separate from the appearance of a mobile home (Hay, 1974).

This image has not been reproduced due to Copyright

Figure 28: IBS expansion floor plans

The first hurdle to overcome to create the intended flexibility of the system was the development of a wall panel jointing system and a rationalised range of panels which allowed for the elimination of the double wall between adjoining units (Hay, 2012, p. 29). Doing this also enabled the mass production of kitset wall components that could be interchanged and used in a variety of different builds. The IBS panel that was developed was not to unlike the rudimentary SIPs panel used today with a light weight foam core sheathed in timber and asbestos based sheet materials.

Figure 29: IBS Wall Panel

Figure 30: Panel Joint

The jointing system moved through several iterations before settling on an accepted solution. IBS's ability to be a flexible building system was advertised as a "major design innovation" and was a key feature (Hay, 1974). The ease of modification was made possible by treating panels as singular elements meaning that adjacent panels would not be affected by the removal or replacement of another panel (Hay, 1974). This meant the system permitted full interchangeability of components without compromising the overall structure. This idea was applied to the joint itself which connected the roof, wall and floor sections through three different types of connectors depending on the junction. Simple steel plate connectors on the outside edge of the panels were bolted together to form the connection with facia and skirting covers screwing on to cover the joint.

Figure 31: IBS Module expansion

Figure 32: Sketch of the IBS prototype home

Result:

The goal of the team at IBS was to show that the system really worked and so three prototype houses were constructed out of the IBS research and development factory in Avondale, Auckland (Hay, 2012, p. 31). At the pinnacle of the building and development programme, the IBS team undertook an intensive appraisal and testing of materials and components, the likes that had never been seen before in New Zealand or any part of the world for that matter on a conceptual building project. The completed houses were transported down the road to a staging site where the public and investors would have the chance to see the IBS System at work first hand.

Figure 33: The first IBS prototype house in Avondale, Auckland

Ultimately IBS began its demise once investors formed an opinion on the roofline of the IBS prototype house. To them, "it didn't look like a real house" and they believed that the public would feel the same way (Hay, 2012, p. 33). New Zealanders weren't accustomed to the low pitched roof of the prototype IBS homes and so the association with the American mobile home stuck. In a desperate attempt to win over investors Hay and Juriss completely redesigned the system and in the process abandoned the prefabricated wall system and the concept of the expanding house (Hay, 2012, p. 33). So much of what made the IBS system revolutionary and unique was lost in his process and Juriss soon lost interest and as money began to run dry the project was abandoned. IBS was an idea ahead of its time and could have drastically changed the way houses in New Zealand were built.

5.2 Packaged House & General Panel Company

Architects: Konrad Wachsmann & Walter Gropius

Location: United States of America

Date: 1941-1952

System Type: Panel and Designed Joint

Background:

The Packaged House/General Panel System was not to unlike that of IBS albeit developed 30 years prior. Developed by Konrad Wachsmann and Walter Gropius between the early 1940s and 1950s the project began as a wartime proposal to create industrialised building components for prefabricated housing post World War II (Martinez, 2019).

The idea began while Wachsmann was in exile to France at the start of the second world war. On arrival to the United States, Walter Gropius provided Wachsmann with the financial and intellectual resources to continue the project (Bergdol & Christensen, 2008, p. 80). Wachsmann chose not to design any house models as the intended purpose of the system was to have no ideal arrangement. Instead he developed a system of ten different types of panels forming what would become horizontal and vertical components of a building (Bergdol & Christensen, 2008, p. 80). The panel system alone was not enough to gain a patent but instead the unique “wedge connector” which joined the panels together was deemed the inventive and noteworthy element of the system (Bergdol & Christensen, 2008, p. 80).

This image has not been reproduced due to Copyright

Figure 35: An early scale model from Konrad Wachsmann on what he envisioned for the Packaged House

Figure 34: (Left) Konrad Wachsmann & Walter Gropius along side a stack of Packaged House panels

System & Connection:

The four-way metal connector which became commonly known as the “Wedge” was the primary means of connecting wall panels to one another in the Packaged House. Made from four unique steel pieces these pieces were attached to outer edges of the timber framed panels and slotted together in specific order at the junctions between panels. The system was complex but allowed panels to be joined from any primary axis without the need for nails, screws or other permanent fixtures (Tower et al., 2003, p. 20). The wedge also provided connection between floor and ceiling panels proving its versatility. As a result the wedge allowed for rapid demountability (Herbert, 1984, p. 257). This accelerated rate of assembly and disassembly meant that one of the first prototypes built took five unskilled workers only nine hours to assemble the finished structure (von Zimmerman, 2012).

Figure 36: Wedge Connector.

Figure 37: Position of the wedge connector parts in the wooden panel frames.

Figure 38: Wedge Connector in locked position.

This image has not been reproduced due to Copyright

Figure 39: Stack of Packaged House panels with wedge connectors. Panels also contain electrical installations.

Result:

It was through Gropius's involvement that the Packaged House System was given architectural meaning incorporating Wachmann's theoretical framework and the concepts of change, unity, variety, flexibility, growth and change (Herbert, 1984, p. 259). With Wachmann being intensely focused on the detail of the system it was Gropius who gave the Packaged House its first architectural form with a set of drawings showing possible house designs that could be generated from the system (Herbert, 1984, p. 259). It wasn't until 1942 when the 'General Panel Corporation was formed out of an old aircraft hanger in California that production looked like it might start (Imperiale, 2012, p. 42). By the end of the war in 1945 the Packaged House had still not gone into production and it took a further two years for Wachmann to design the production and assembly line for the system which was ready by mid-1947. During that period Wachmann and Gropius took it upon themselves to finally build two test houses in Queens, New York. The system proved successful and Wachmann and Gropius drafted plans to build 3000 houses a year as soon as the production line was ready (Herbert, 1984, p. 279).

This image has not been reproduced due to Copyright

Figure 40: Axonometric drawing of a proposed design for the Packaged House System

Like IBS, the Packaged House System started to falter around the point before mass production could really start. The theory Wachmann envisaged for the Packaged House was a universal set of components that allowed for the generation of an almost unlimited number of universal designs (Herbert, 1984, p. 293). The goal was to originally market this kit of parts rather than complete houses to demonstrate the systems flexibility. Unfortunately building regulations and FHA (Federal Housing Administration) requirements forced General Panel Company to abandon these plans. By this time the war and its after affects were well and truly passed and the demand for post war had subsided. Through 1948 and 1949 the General Panel Company began to struggle financially as the total number of houses produced and sold did not exceed the 200 mark (Herbert, 1984, p. 304). Colin Davies, author of the Prefabricated Home believes that the ultimate reason for the failure of the Packaged House were the actions and decisions of its creator. Wachsmann was obsessed with the system and could not stop "improving" it (Davies, 2005, p. 23). As a result the Packaged House and General Panel Company were late to the game and the demand for post war housing was filled by over 70 other companies who produced more than 200,000 prefabricated homes (Davies, 2005, p. 23).

This image has not been reproduced due to Copyright

Figure 41: Packaged House Panels

5.3 Critical Refelction

This analysis of key precedents in this chapter has shown that flexible housing is by no means a new concept and if given the chance to be developed properly, could have great success. The discovery of the Industrialised Building System (IBS) designed by Roger Hay and Ivan Juriss gives this research significant historical grounding in New Zealand and shows that the concept of flexible housing has a connection to history of schemes which have been investigated as a solution to problems in the housing industry.

A common theme among both precedents is evident in the use of a complex jointing system used to connect rather rudimentary panels. In both cases this complex jointing system was a significant part in the downfall of both IBS and the Packaged House. It is clear that the difficulties associated in terms of both fabricating and assembling this connector were the main reasons. On these grounds, a primary focus of the design phase will become the simplification of such a joint.

The second such issue that was observed was one of form. Unknowingly IBS and the Packaged House both used the same style of roof, leading to problems around aesthetic and negative perceptions of the resultant designs. Replications of such designs that were seen in these two precedents will need to be avoided. This chapter has capped off in-depth research and provided critical insight on where this research could progress into the initial design phase. It has also identified two critical issues that were prominent factors in the failure of previous flexible housing initiatives. A focus on these issues as well as integration of key learnings from the construction method analysis and prefabrication and modular design chapters will be used going forward in the next chapter.

flexible

flex · i · ble

characterised by a ready capability to adapt to new, different or changing requirements

System Concept Design

- 6.0 Preface
- 6.1 Methodology
- 6.2 Modernising IBS
- 6.3 Analysing IBS
- 6.4 Panel Design
- 6.5 Detailed Panel Connection
- 6.6 Module Form Testing
- 6.7 Module Layout
- 6.8 Foundation and Floor
- 6.9 Revisiting the Module Arrangement
- 6.10 Critical Reflection

6.0 Preface

This chapter builds on the design knowledge acquired through the preliminary research stage in the previous chapters. Analysis of the traditional construction method and flexible solutions in the form of a precedent study has provided a starting point to develop a new flexible system based on the key learnings from this analysis.

A selection of a structural system, based upon strong material, assembly, manufacture, and flexible attributes will become the first design phase. This chapter builds on the ideas and technological aspects of the analysed precedents to iteratively develop a new flexible construction system. Design and testing have been undertaken through the use of scale physical modelling, digital modelling, and material analysis. New making and modelling methods are also explored in this chapter with the introduction of CNC manufacturing to the design led research process.

Development of the joint and prefabricated modular system was not a linear process. The design process of these two things worked in conjunction with the design of a modular organisation system to which the joint and panel could be applied. This process entailed a back-and-forth movement between the two programmes with significant design decisions in one often influencing design decisions in the other.

6.1 Methodology

As the focus of this research looks at flexible housing on both a macro and micro level, a decision has been made to use Pamela Bell's prefab category designations during the design phase of this research to focus on the different areas that will be explored. These categories have industry relevance and are used by Prefab NZ to define the different types and scales of prefabricated construction in New Zealand (Prefab NZ, 2018, p. 8).

These categories are Component, Panel, Module, and Complete Building (Bell, 2009, p. 27). For the sake of this research, Component will be reclassified as joint as it is the smallest scale and a key part of the design led research. The design research phase will move incrementally through each of these categories using design methods at various scales to produce a design outcome. For clarity, each stage of the research will include the following icons to communicate which category is being investigated.

6.2 Modernising IBS

Of the two precedents, the Industrialised Building System showed the most favourable characteristics in terms of its assembly and flexible abilities. The system, however, is also not without its faults, and its historical structural and material composition shows that it would simply not be able to comply with New Zealand's strict modern building standards. The panel features a foam core, which was sheathed in asbestos sheets on either side. For obvious reasons, this would not be acceptable by today's standards. The foam core would also restrict the ability to run services through the panel unless they were integrated prior. The second area of concern is the connector system that joins the panels together. Like its counterpart in the Packaged House, the connection is overly complicated for simply joining panels together. A revised solution should be simple and easy to integrate into the panel without the need for additional and expensive manufacturing of custom components.

6.3 Analysing IBS

While the Industrialised Building System's material and connection assembly attributes were significant restrictions for the system's immediate adoption, IBS's structural modularity and organisation system were noteworthy and prompted some design investigation. A 1:10 scale model was built to analyse the arrangement and relationship of the structural elements.

The scale physical model aimed to provide a physical summary of IBS's structural and organisational system, in which an exceedingly small amount of information was available to analyse. It provided clear insight into the way such a flexible system might be assembled and the ways in which different components would interact with one another.

Observations:

The Industrialised Building System used a joining mechanism for floor and ceiling components consisting of a simple tab which extends from the panel. This is the concept that was used for one of the early prototypes — the one which had the most developed detail from the drawings on which this assembly model was designed. The system has instant modularity utilising a primary 1200mm panel for the main structural component. The system also uses corner posts with a width from corner point to end of 200mm. To keep the 1200mm module, a panel at the end of every finished wall measures shorter at 800mm to keep the module consistent and easy to expand. The tabs on the edges of the panels lined up easily with those on the floor component allowing for quick installation between the floor to wall connection and the wall to ceiling connection. As

Figure 42: Elements of the IBS model

Figure 43: 1:10 scale model of the Industrialised Building System

Figure 44: IBS Model Assembly Sequence

the panels all act independently in the structure, removing one panel did not compromise the structural integrity of the small model.

Figure 45: Tight fit of the panels

Figure 46: Tab joints to the roof at the module corner

Observations:

Designed as a flexible construction system, IBS performs more or less as it should. The systems modularity worked well, exhibiting the potential for an arrangement module and a structural module to coexist. The corner can be a significant draw back in modular systems as it offsets the module grid, but IBS combats this by using shorter panels to adjust for the corner pieces at either end. The metal tabs allow for the system to be lined up easily with floor and ceiling components to make sure that they are in the correct positions. The addition of bolt holes, evenly spaced along the sides of the Ribsel floor component means that the walls do not have to be assembled in a specific direction. The greatest advantage of the system is its ability to remove walls without compromising the overall structure as the walls act independently of each other. This was portrayed exceptionally well by the model and added a real sense of reality to the concept of flexible housing. The act of physically making and altering the structure gave tangible form to the system and realised its strengths and weaknesses.

6.4 Panel Design

This first concept design phase will investigate the construction of a modular panel system, specifically looking into material constraints and panel to panel connections allowing for change and disassembly. This concept stage uses the Industrialised Building System's modular panel system as base to build upon.

Overview:

The design of the panel looked to emulate that of IBS, albeit by using modern material and fabrication methods. The design looked to take advantage of CNC manufacturing capabilities by using 17mm sheets of 2400mm x 1200mm plywood to create a structural frame known as a 'cassette'. These cassettes form a modular 'bed-frame' like structure. Machine cut vertical uprights and horizontal cross members use a friction fit 30-degree dovetail joint to hold the components together. Dovetail joints were chosen for their unique but effective geometry which was effective at holding the components together. While the dovetails still rely on friction to hold them in place, their shape acts as a naturally occurring fail safe ensuring that the component that they are holding in place cannot be removed. The dovetails have been arranged in such a way that they restrict other components from falling out of place.

A detachable internal sheet lining is attached via the Fastmount clip system to ensure that it is removeable. A detachable internal lining means that access is provided to the bolts and nuts which connect multiple panels together through evenly spaced holes in the uprights. A simple bolt connection permits rapid assembly and flexibility.

The module size is dictated by raw material size, in reference to Konrad Wachsmann's theory on module design. The size of the cassette is optimised to suit standard sheet material sizes to minimise wastage during production. The width of the cross section of the cassette measures 140mm. This becomes the structural module size of the cassette and has several advantages. This width provides a relationship to a standard size of timber framing, ensuring it could be integrated with traditional frame construction if it needed to be. The large width of the cassette also ensures good thermal performance of the walls, allowing for a large amount of insulation and reduced thermal bridging because of the slender uprights on either side of the cassette compared to the usual thickness of standard timber frame.

Overview:

This panel completed the aim of modernising IBS, using modern materials and methods of fabrication. Jointing geometry and assembly sequencing techniques fulfil a key design objective of eliminating permanent fixings from the structure. Further integration of finishing elements such as weather proofing, internal lining and external cladding will need to be explored before Panel 3.0 can be deemed a suitable system to create flexible housing.

The use of 17mm plywood allows for the creation of panels up to 2700mm by using the longest available sheet size. While formal arrangement of the panels has not yet been explored, the reliance on this sole material may lead to aesthetic issues that plagued the Industrialised Building System due to its low-pitched roof.

Figure 47: Front and rear of the proposed panel

6.5 Detailed Panel Connection

Application of architectural elements such as waterproofing, external cladding and internal lining is key to refining the designed connection between the panels. Analysis of the traditional build method in Chapter 3 highlighted the issues with the current method of internal lining and external cladding and the limitations and restrictions these elements impose on flexible design. A selection of a new method must not only address protection from the external elements but also must be capable of rapid change. These two requirements often don't go hand in hand with joints meant to aid in flexibility, contributing to issues such as water penetration if not designed and sealed correctly. IBS and the Packaged House suffered similar issues because of a complex connection.

Each panel is wrapped in building paper to create a waterproof barrier. On top of this are horizontal cavity battens and a vertical shiplap weatherboard. A small gap is left on either side of the panel so the join can be taped with flashing tape once the panels are bolted together from the inside. After the join has been taped, a closing panel is slotted into place to seal the join. The internal lining is comprised of a HardieGroove™ 7mm panel, secured in place using a FastMount™ clip, predrilled into the horizontal members of the panel.

To disassemble or alter the arrangement of the panels the process is followed in reverse order, with the flashing tape being cut down the join to release the panels once they have been unbolted.

Figure 48: The join between two panels

Figure 49: The process of connecting the panels modelled at 1:10 scale

6.6 Module Form Testing

Primary material selection during the panel design phase created concerns about the possible design aesthetic of a house designed using the specified panel system. This section looks at the spatial arrangement of the panels and the architectural form they produce as a result.

6.6.1 Module Form 1.0

The design of Module 1.0 involved the use of a 2400mm panel and a 2700mm panel. These were arranged 4800mm apart to create a space double the width of the smallest height. This width would also allow for standard sheet material to be used when development of a floor cassette took place.

It became immediately clear that the sole use of plywood created significant limitations for the system leading to notable aesthetic issues. If a line were to be drawn between the two panels simulating a mono pitch roof, the pitch of this roof would be no more than 3.5 degrees. This is the aesthetic issue that also plagued houses built using the Industrialised Building System. Increasing the pitch by reducing the module size was considered to resolve this issue, however reducing the module size would reduce the liveable space within the overall module.

Figure 50: Poor overall form caused by the limited panel height

6.6.2 Increasing Panel Size

To fix the aesthetic issues caused by the low pitch roof an increase in panel size was proposed. This would mean that a new material would need to be used in place of plywood which only had a maximum length of 2700mm.

Oriented Strand Board (OSB) was chosen as its replacement. Similar to plywood, OSB is a sheet material with a range of standard sizes. It is an engineered material with wood strands running in opposing directions on different layers to give it structural strength (IBS - Sustainable Building Products, 2021). OSB's maximum sheet size is 3600mm which will add the much-needed height to increase the pitch between the smallest and largest panels.

While OSB can reach these new heights needed to mitigate these aesthetic issues, plywood cannot, which creates a significant problem when trying to create structural components which are meant to support a panel of this height. To combat this issue, vertical component members will be "doubled up" with the addition of a vertical support member being bolted in behind the primary vertical members. Not only will this allow for plywood to continue being used as the structural component material but will also provide extra structural rigidity to the vertical members.

The OSB would also meet building code requirements unlike the OSB when used a panel face. Fixing of cavity battens and cladding requires a minimum thickness of 20mm. With the OSB this can now be achieved as unlike traditional framing, there are no studs or dwangs to screw into.

Figure 51: New range in panel sizes. 2400mm and 3600mm panel sizes shown

6.6.3 Module Form 2.0

The design of Module 2.0 used the same arrangement as Module 1.0. Unlike the previous iteration, the higher pitch roof produced a stronger impression of a house creating a pitch between the two panels of 14 degrees.

It was also here that a major discovery relating to the proportions of the module in section was made. At even 1200mm intervals along the width of the module, the height of the proposed roof matched evenly with standard sheet sizes and incrementally increased by 300mm at each interval. Figure 52 shows the even proportions of this module size with the corresponding widths and heights. This discovery would optimise the efficient use of sheet material when developing angled panels later.

Figure 52: Even proportions of the concept module section

6.7 Module Layout

While the overall form of the module has been designed primarily in section, the layout and arrangement of the panels has not been explored. This design phase looks at the implementation of Industrialised Building System's module organisation system.

6.7.1 IBS Arrangement

A key takeaway from the Industrialised Building System precedent was its clear use of a module organisation system. While IBS's panel sizes were dictated by material size module, it used a different module for its system organisation. This organisation was dictated by a dedicated corner piece with a width of 200mm. This arrangement offsets the standard 1200mm panel from the module start point by 200mm and includes a new smaller 800mm panel to ensure the organisational module also used a 1200mm width, albeit offset. To use this organisational system with the developed panel, three new panel options will be developed.

Figure 53: IBS module arrangement. Note the offset of 200mm due to the 200mm corner piece

6.7.2 New Panel Elements

Three new types of panel were designed in order to use the IBS module organisation system. These were an external corner panel, an internal corner panel and a series of angled panels. The panels were designed using the same constraints and learnings based off the design of the original panel, incorporating the use of OSB as a critical material.

External Corner Panel:

The external panel measures 200mm square from corner to corner. The panel aims to share as many components as possible with that of a standard panel, however it is only true in the case of the uprights as every other piece had to be specially designed for the panel. While many of the components share the same purpose as a standard panel, an extra component had to be added in the form of a support piece known as the 'filler' between the panel face and the horizontal dwang for much needed support for these components at the rear of the panel.

Internal Corner Panel:

The internal corner panel followed the same basic design as the external corner, albeit in reverse. The internal corner also added a 'filler piece' as the horizontal dwangs on this panel were longer than those of the external corner and were at greater risk of structural failure without the additional support.

Figure 54: Internal corner panel

Angled Panel (Left & Right:

The angled panel follows the same design as the standard panel. The sloped top makes use of a dovetail connection between the top plate and the upright virtually impossible by virtue of the ill-fitting geometry of the two pieces. A finger jointing method is used here instead. The cassette upright extension method used in the design of the standard 3600mm panel is also used here.

Figure 55: Sloped panel

6.7.3 Module Form 3.0

The design of Module 3.0 used four different types of panels. The original 2400mm and 3600mm panels created external walls. Two external corner panels measuring 200 mm in width were placed either side of the module connecting to the corresponding existing panels. The angled portion between was filled with new angled panels. Each of these measured 1200mm in width the tallest end panel reduced to 800mm to complete the module.

6.7.4 Module Issues

It became clear immediately that this module arrangement has significant issues. The primary complication focused on the issue of geometry problems posed by the new corner piece.

While the new corner piece created the first lateral panel connection, the corner is immensely restrictive and prevents easy modularity of the panel system. Cause for concern surrounds the connection to the of the corner to the 2400mm and 3600mm panels. These will be referred to respectively as the 'bottom angle connection' and the 'top angle connection'. The connections involve a significant change in direction as the angled panels at these points run perpendicular to the standard flat top panels. At this connection, the corner panel is expected too somehow join two panels which have vastly different geometry. Part of this problem is caused by the limitations in the design of the corner panel, as the side which would be present on the angled portion of the module has remained flat. This is due to constraints created by the panel material and its fabrication method.

The integration of the corner into this area simply does not work with the proposed mono pitch roof. The overall size of the corners offsets the module layout from the panel module and causes confusion between the panel module and the organisational module. The corner creates substantial problems in a critical area that will need to be resolved.

The significant panel offset also has negative implications for the modularity relationship between the horizontal modular layout and the vertical module layout. The corner offset results in different heights at 1200mm intervals than what was originally proposed disrupting the effect the original module size was meant to have.

Figure 56: Difficult joinery created by the corner pieces in most evident at the top of the panel

6.7.5 Panel Issues

Small scale fabrication of these new components was also undertaken to assess their potential use. Unlike the standard panels, sequencing and jointing of the corners was far more complicated. This resulted in poorly thought-out dovetail arrangement and the need for extra support in the form of a filler plate in behind each of the horizontal dwangs so that they had something to hold them in place. Without the filler plates in behind these dwangs could easily snap off or be removed of excessive force were applied to them. This would make it difficult to attach the internal lining to these pieces. The filler plates complicated sequencing as well and some pieces had to be forced into place at funny angles suggesting that the sequencing was not possible in the first place.

Figure 57: Assembly of an internal and external corner module

Figure 58: Issues with the dovetail. This top piece is able to be removed here

Figure 59: Internal and External corner assembly

Figure 60: Internal corner and standard panels

Figure 61: The mismatched elements at the corner, caused by the corner panel

Figure 62: Complex corner components

6.7.6 Critical Reflection

Poor modular performance and fabrication and assembly issues with the designated corner panels suggest that the Industrialised Building System's organisational module may not be suitable to be used for the proposed system. As a result, the decision has been made to develop an organisational system better suited to the limitations of the proposed system in its current form rather than use one of a critical precedent. Developing the system further to understand its constraints and capabilities will assist in module organisation at a later design phase.

6.8 Foundation and Floor

Foundations are the most permanent element of a house and are the most restrictive factor when trying to design for flexibility (Till & Schneider, 2007, p. 196). This is particularly the case when using concrete foundations. This design phase focuses on the selection of a foundation and floor system. It is here where the first significant connection other than a panel-to-panel joint is investigated with the first panel to floor connection concept is developed.

Development of a designed connection for a panel to floor joint would require the design of flooring and foundation system. The Industrialised Building System used a specifically designed flooring system known as a Ribsel Panel while the Packaged House used a homogenous system where wall panels could also function as floor panels. This provides two possible options to explore. Early design work on the panel does not suggest that it could be used as a homogenous system as it only has a maximum height of 3600mm, and the module width has been decided at 4800mm meaning that it has the inability to be used as a continuous floor span. It was at this point that the decision to use an already established flooring system was used. Developing a new system seemed aimless when a proven system could be adapted for use.

6.8.1 Foundation & Floor Selection

Pryda Floor Cassettes:

Pryda Floor Cassettes were chosen to be used as an established structural floor system. The system utilises prefabrication to construct the cassettes offsite before they are transported to site ready for installation (Pryda, 2016). The trusses that are used as the primary structural component use metal webs for diagonal bracing which allows plenty of space for the easy integration of services under the floor.

The Pryda Cassettes are lightweight and preinstalled lifting devices through the holes intended for panels mean that a small crane or HIAB can lift the cassettes into position, completing a working floor in a few short hours.

Figure 63: Pryda floor cassette

Surefoot Foundation:

The use of a Surefoot concrete free footing system was chosen as the primary foundation structure. Surefoot utilises metal plates with micro piles driven through them at different angles to create a footing which is building code compliant and can be used on any soil type. As opposed to concrete, the Surefoot system is highly flexible being able to be installed just about anywhere and with the potential to be removed and reused if a structure is to be altered or removed.

The foundations installation is highly efficient taking as little as 10 minutes to install with basic equipment. This system was recommended to be specially used with the Pryda Floor Cassette System meaning that these two systems are proven to work together successfully.

Figure 64: Surefoot foundation with micro piles

6.8.2 Detailed Panel to Floor Connection

The proposed connection between the floor and the panel involved treating the components as separate entities the entire time. This is an issue that needs to be resolved so that they can be bought together as one to form the base connection of building but still be able to be separated when alterations are made to the building.

To combat this problem, the first iteration of this connection suggests splitting the building paper and the external cladding and between the panel and the bearer on which the floor cassette sits. Building paper would then extend past the bottom of the cladding on the panel and be able to be horizontally taped to the building paper on the bearer before the panel is completely lowered into place and bolted into the floor cassette. A metal flashing would run from behind the cladding on the panel, out over the cladding on the floor cassette deflecting water outside of the cavity.

Figure 65: Separation of the cladding

6.8.3 The Mini Module

To evaluate the proposed assembly and connection method for the panel to floor connection, a 1:10 scale model of the module was built. This model included features such as the cladding and building paper to critically analyse whether the designed connection would work.

Figure 66: Components of the Mini Module

Figure 67: IBS Model Assembly Sequence

6.8.4 Floor to Panel Connection Issues

The construction and assembly of this model demonstrated significant problems with proposed method and proved the difficulty of the intended design. Firstly, splitting the cladding and building paper in order to separate the panel and floor components was a disastrous idea. Not only is the join in the building paper difficult to do but horizontal taping could also lead to moisture penetration issues if water was to get int behind the cavity. Secondly, the proposed metal flashing meant to deflect water from inside the cavity to outside and cover the join between the two elements is very fragile. During transportation or installation this piece could be crushed or bent rendering it useless. Installing it on the panel while it is being lifted into place would also add significant time to the assembly process.

Overall, this assembly method created significant problems for module and would not be an applicable solution.

6.8.5 Other issues

In the analysis of the Mini Module, further problems were discovered with some of the designed elements. While a roof to panel connection has not yet been designed the place holder roof used in the mini module highlighted a problem with using Panel 3.0. The top of panel 3.0 is the last remaining piece to go when assembling to panel meaning it is also the only piece without a "fail safe". Connecting the roof to such a piece would not be a visible option as it could disconnection itself easily from the panel. Therefore, a redesign of the panel is required along with further investigation into how the wall and roof may connect. This will be explored later in further design phases.

Figure 68: New dovetail joint arrangement at the top of the panel

Figure 69: The flashing separating the cladding on the floor cassette from the panel could be damaged during transport

6.9 Revisting the Module Arrangement

The resultant design issues created by the corner forced a redesign of the module arrangement. This problem particularly effected the module layout in plan view and concerned the location of the walls. A new strategy involving a set of rules and constraints would be used to dictate a new module layout dictated by the panels and their limitations.

6.9.1 Improvements to the Module Layout

The original module layout only focuses on organisation in one primary axis, yet the module size had been dictated along an axis with no such module organisation. Panels in this section were left with one needing to be shorter to fit the space at the end. To allow for consistent panel widths along each axis, a rule was employed called the "outside the line rule". Exterior panels at the edges of the module would be placed "outside the line" and the module would measure 4800mm from the inside edge of the panels allowing for even placement of four 1200mm panels along the angled axis. This meant that the floor cassettes would be extended 140mm at either end to account for this added length.

It is to be noted that this rule only applied to standard panels. Angled Panels followed a rule known as "inside the line" and these would be placed inside the module almost like a capping piece at either end. Changes to the design of the panels in the form of holes on the panel face and dwangs would allow for panels to now be bolted to the face or rear on either side of the panel.

6.10 Critical Reflection

Evaluation of the concept design phase revealed some interesting findings.

Firstly, it has become clear that the concept of flexible housing is much larger and entails far more study than anticipated. Flexible housing is not just a case of designing a prefabricated panelised system and a designed connection and there are far more things that need to be considered.

Secondly, while IBS proved during the initial research phase, to have significant potential as a flexible construction system, the attributes which made it a successful and unique concept have not had the desired effect to modernise the system. From here on out it is clear that the Industrialised Building System has served its purpose, suggesting major improvements are needed to the system to make it work.

This page has been intentionally left blank

Developed System Design

- 7.0 Preface
- 7.1 Panel Design
- 7.2 Roof Design
- 7.3 Window Integration
- 7.4 Linear Expansion
- 7.5 Lateral Expansion
- 7.6 Critical Reflection

7.0 Preface

Chapter 7 builds on the key learnings from the conceptual design phase. This chapter uses a similar design methodology to test and evaluate the designed concepts. This chapter has a clearer focus on built elements which make the system resemble something closer to a house. The method on which a house can be flexible and change to required scenarios is also looked at here.

7.1 Panel Design

As a result of the changes to the module arrangement layout, the panel design has changed again, this time to its dimensions and the top of the panel. As the module arrangement of the standard panels now has them placed outside of the module arrangement line known as "outside the line" this has led to a change in the make up of the panel. The internal height of the small 2400mm panel remains 2400mm on the interior but on the exterior, this slopes down to 2365mm. This is due to the shortening of the panel so that a sloped 35mm top plate can be added. The pitch of the roof not only allowed for even increases in sloped panel size but lead to a key finding in the roof's relation to the top of the panel. The sloped pitch of the roof matched perfectly with a 140x35mm top plate. When this top plate was sliced in half diagonally it matches the pitch of the roof allowing for perfect contact.

This also creates a situation where panels can sit on either side of the modular arrangement line and still meet the roof evenly by adding a 140x35 mm top plate underneath the sloped top plate. This is known as a stacker and helps the panels reach this height.

Inadvertently, this module arrangement and its precise dimensions and layout have created what could be called the "golden ratio" of system arrangement.

Changes have also been made to the exterior cladding for the panel. Replaces the vertical shiplap style of weatherboard is instead a board and batten arrangement. It was decided that trying to fit a shiplap board in between the space between two panels would have been too difficult and so a simpler board and batten cover will be used instead.

Figure 70: New sloped top plate at the top of the panel

Figure 71: New panel structure including the 140x35mm sloped top plate

Figure 72: Panel placement with the use of an added stacker to the top of the panel

Figure 73: Panel placement with the use of just the angled top plate

7.2 Roof Design

The design of a roof encountered similar problems to the design of a floor system. Unlike the floor, this problem could not be supplemented with an existing system and a solution had to be design instead.

A key problem was the fact that a panelised system like the one used to create the walls would not work as a roof. It had already been established that plywood was not long enough to reach lengths over 2700mm and OSB could only reach 3600mm. The proposed concept, instead saw the adoption of LVL rafters to span the maximum gap between panels of 4800mm. These LVL rafters then saw plywood cassettes situated between the rafters forming the internal structure of the roof. These cassettes were designed using the same design methods as the panels and featured dovetail friction jointing. These cassettes matched up with the width of the sloped top of the panels meaning that only 3 different types of cassettes had to be created. A midspan cassette, an outer span cassette (slightly longer so it could sit on top of the sloped top plate) and an eave cassette.

Figure 74: Panel placement with the use of just the angled top plate

7.3 Window Integration

Windows are often one of the last built elements to be put in place before a house is considered watertight on a traditional build. This adds considerable time to a build if there are delays. Therefore, this system proposes having windows installed into the panels before they are delivered to site for onsite assembly. This requires having a hole cut in the middle of the panel for the windows to be placed.

Figure 75: Panel with hole for window

Additional components are needed for the uprights and top and bottom places for the windows to rest on. This involves a slotting piece that slots into the two custom uprights and runs the width of the panel, not just the base of the window. These components have the same basic shape but will need to be altered each time a different size window is placed in the panel so that they slot correctly into place.

Figure 76: New components to hold window in place

Figure 77: Closeup of slotted window components

Limitations in this concept mean that windows may only be the width of a panel. This design could be restrictive and accommodating larger windows requires a different solution.

To accommodate larger windows, two or more panels are treated as one large panel. A continuous plywood box beam is then bolted to the upright of these panels on either side with additional uprights below the beam to support it. This group of panels is then treated as one entity and can be bolted into place like all other panels.

Figure 78: Double panel window with plywood box beam

Small scale prototyping of these two types of window assemblies was undertaken. The slotted joinery for the top and bottom plates worked exceptionally well and had to be hammered into place to force it to fit. This was encouraging as a dovetail joint was not possible to use in this area.

Figure 79: Slotted upright and cross member of a standard single panel window

Figure 80: Slotted upright and support uprights for plywood box beam

7.4 Linear Expansion

Testing the process of linear expansion involved taking all these designed elements and putting them together in the form of a complete module. Linear expansion involved the process of expanding in the same direction as the original module layout. This proved extremely easy and required just simply adding more panels, floor cassettes and roof cassettes to the original module.

7.5 Lateral Expansion

While linear expansion was quite easy, lateral expansion proved a lot more difficult. Lateral expansion was inherently made more difficult due to the build elements on the panels such as cladding meaning that panels could not be backed onto one another. One possible solution could be to remove the cladding off these panels entirely but that would slow the process of expansion and defeat the purpose of prefabricating the panels in the first place.

The solution to this problem came in the form of a 'link module' which was a critical concept used in the Industrialised Building System to allow that system to expand. The link module extends from the side of the house perpendicular from the original module arrangement. From here, a brand-new module can be arranged.

7.6 Critical Reflection

At this stage it has been decided to conclude the conceptual and development stage of the design led research process. Further testing and evaluation of the system is required but this can only be done once the system and all its parts have been fully understood. Testing of the systems flexible abilities will be undertaken once the constraints of the system have been fully realised during the detail design phase.

This page has been intentionally left blank

M8RX System[©]

- 8.0 Preface
- 8.1 Introduction to the M8RX Building System
- 8.2 Components
- 8.3 Panels and Cassettes
- 8.4 Floor
- 8.5 Roof
- 8.6 Fabrication and Assembly Process
- 8.7 Integration of Services
- 8.8 Transport and Onsite Assembly
- 8.9 Panel to Panel Joint
- 8.10 Panel to Floor Joint
- 8.11 Panel to Roof Joint
- 8.12 Critical Reflection

Figure 81: The M8RX Model

8.0 Preface

This chapter moves on from the concept and developmental stage of the design led research process. During this process, a prefabricated panelised system and designed connection has been developed through various means of design exploration from digital modelling to scale physical modelling and small-scale prototyping. The system and connection have reached a point where continued conceptual design seems frivolous without testing and analysing whole system in greater detail. This chapter details the components and panels of the system as a whole and explains how they may work as a flexible housing system.

matrix

ma · trix

a rectangular array of quantities or expressions in rows and columns that is treated as a single entity and manipulated according to particular rules

an organisational structure in which two or more lines of command, responsibility or communication may run through the same individual

"matrix structures are said to offer greater flexibility"

8.1 Introduction to the M8RX Building System

The M8RX Flexible Construction System is the result of rigorous design and evaluation during the concept stage. The concept traces its origins to the Industrialised Building System of the 1970s which very nearly took off as a flexible housing system. The M8RX Flexible Construction system is a modular system that can facilitate change to the physical fabric of the house — something that would not be possible using a traditional construction method. The goal of the M8RX system is not to just be bluntly utilitarian for the end user, but to also provide positive environmental, social, and human health impacts which were key motivators for flexible housing.

The name M8RX derives from its mathematical definition which is “a rectangular array of quantities in rows that is treated as a single entity and manipulated according to particular rules” (Oxford English Dictionary, 2021). The definition felt very fitting to describe the designed system because of its rectangular arrangement and the constraints that govern how the system is used. The 8 signifies the number of panels of each panel type.

8.2 Components

The M8RX component system consists of 80 unique components which, when assembled form the panels for the system. An additional 14 components are used for the roof cassettes. The components are manufactured from two different types of sheet material, 17mm plywood for the primary structural members and 20mm OSB for the panel faces. Plywood is the primary material used with 86% of the overall system using this sole material.

Each component has its own distinctive name and code, dividing them into sub-groups based upon their purpose within the overall M8RX system. Components are often interchangeable meaning that they can be shared between different panels and cassettes, reducing the number of pieces in the overall system. The addition of windows and doors to standard panels only adds an additional two components known as ‘dynamic components’ to the component set. These special components are meant to change based on the custom opening that is designed into that specific panel, but their overall shape and size remains the same. This reduces the need for custom complex components even though openings may range in size.

8.3 Panels and Cassettes

The 94 unique components of the M8RX System are then able to be assembled into 16 different panel types. 8 standard panels, 8 sloped panels and 3 roof cassettes. The system does not feature any permanent fixtures and relies solely on dovetail friction joints and stringent assembly sequencing to hold itself together.

Like the components, the panels have their own distinct name and code for easy identification throughout the complete system.

The panels have been designed especially for their use with the M8RX organisation system and the placement of the first position in its starting position indicates where others may fit on the grid around it.

M8RX

Panels & Cassettes

Figure 82: Colation of M8RX Flexible Construction system panels

1

2400x 1200 mm
Standard Panel
P24

Figure 83: 2400 x 1200 M8RX Panel

2

2700 x 1200 mm
Standard Panel
P27

Figure 84: 2700 x 1200 Standard M8RX Panel

3

2700 x 1200 mm + FS
Standard Panel + Flat Stacker
P27FS

Figure 85: 3000 x 1200 M8RX Panel

4

3000 x 1200 mm
Standard Panel
P30

Figure 86: 3000 x 1200 Standard M8RX Panel

5

3000 x 1200 mm + FS
Standard Panel + Flat Stacker
P30FS

Figure 87: 3000 x 1200 M8RX Panel

6

3300 x 1200 mm
Standard Panel
P33

Figure 88: 3300 x 1200 M8RX Panel

7

3300 x 1200 mm + FS
Standard Panel + Flat Stacker
P33FS

Figure 89: 3300 x 1200 M8RX Panel

8

3600 x 1200 mm
Standard Panel
P36

Figure 90: 3600 x 1200 M8RX Panel

1

2700 x 1200 mm
Left Slope Panel
LSP27

Figure 91: 2700 x 1200 Left Slope M8RX Panel

2

3000 x 1200 mm
Left Slope Panel
LSP30

Figure 92: 3000 x 1200 Left Slope M8RX Panel

3

3300 x 1200 mm
Left Slope Panel
LSP33

Figure 93: 3300 x 1200 Left Slope M8RX Panel

4

3600 x 1200 mm
Left Slope Panel
LSP36

Figure 94: 3600 x 1200 Left Slope M8RX Panel

1

2700 x 1200 mm
Right Slope Panel
RSP27

Figure 95: 2700 x 1200 Right Slope M8RX Panel

2

3000 x 1200 mm
Right Slope Panel
RSP30

Figure 96: 3000 x 1200 Right Slope M8RX Panel

3

3300 x 1200 mm
Right Slope Panel
RSP33

Figure 97: 3300 x 1200 Right Slope M8RX Panel

4

3600 x 1200 mm
Right Slope Panel
RSP36

Figure 98: 3600 x 1200 Right Slope M8RX Panel

8.4 Floor

The floor for the M8RX system utilises the design and structure of a well-established prefabricated truss system in the form of the Pryda Floor Cassette System. The cassettes for the M8RX system follow the same design principles as Pryda's original floor cassette, but with provisions for the M8RX grid ensuring that panels can be arranged evenly over the floor area in their designated spaces.

The floor cassette comes in four options, ranging from a full-size length of 4800mm down to the smallest size of 1200mm, providing a range of base sizes to build on.

Below the floor, the Surefoot Foundation System holds the floor cassettes above ground level providing a sturdy foundation to build upon that can be used on any soil type in New Zealand. This allows the M8RX Flexible Construction system to be built just about anywhere.

Figure 99: 4 types of Pryda floor cassettes, adjusted to fit the M8RX model

8.5 Roof

The roof for the M8RX system is highly efficient using only three different types of cassettes. These three cassettes consist of an eave, a midspan and an outer span and can be flipped so that they can be used at both the top and bottom of the roof span. These cassettes sit between two LVL rafters to span the distance between the two outer panels on which they primarily rest on. The purpose of these cassettes allows insulation to be placed in between the cassettes and have the internal lining installed before the roof is assembled onsite. A small piece of internal lining at each end of the roof structure can be removed to allow access to the bolts for onsite assembly. This allows the bolts to be accessed from the interior of the house and eliminates the need for scaffolding during installation or if the roof was to be removed for alteration.

The roof is clad in Espan® 340 evenly spaced down the centre of the roof structure. A small space is left at either end for a custom profile of Espan® to fill this joint. This is known as the cover piece and is installed once the entire roof has been completely fitted.

Figure 100: The 3 different types of roof cassette

Figure 101: LVL Rafters and the roof cassettes

8.6 Fabrication & Assembly Process

Prefabrication of the panels and components has been utilised from the outset. The logic behind this relates to the inherent benefits that prefabrication offers, specifically relating to the reduced time needed for onsite assembly. The components are fabricated, assembled, and have their additional architectural elements added offsite before they are transported.

The fabrication and assembly process of the panels and cassettes follow six critical steps.

Firstly, raw material would arrive at the manufacturing plant in the form of 17mm plywood and 20mm OSB. These sheets would then be positioned on the CNC machine before the CAM file with the cutting information would be loaded. As the M8RX system utilises standard components, these could easily be organised in a cutting file depending on the type of panel that is being fabricated. This would allow for rapid mass production of the system. Custom panels such as those with openings require specially designed components which may slow down the manufacturing process.

It is likely in a real-world, mass manufacturing scenario that two CNC machines would be utilised, one cutting the sheets of OSB, while the other cuts the plywood components.

Once the components have been cut, they are removed from their original sheet material and assembled according to the designed sequencing order. The M8RX system utilises the same sequencing order for consistency and to avoid confusion during the assembly process.

Once the panels are assembled, installation of the building paper takes place before cavity battens and cladding are added over the top. It is at this point that the panels are ready to be taken to site for onsite assembly.

8.7 Integration of Services

As shown in the Mini wall test during the initial design led research phase, services are some of the most restrictive elements when designing with change in mind. The M8RX Flexible Construction system has been developed in such a way to prevent this from being an issue.

The use of the Pryda floor cassette allows open and unrestrained access for services to run underneath the floor. From here they can then run to designated panels with electrical services built in. This negates the need for wiring to run the length of an entire wall and through several panels. This allows each panel to remain a singular entity and can be removed if necessary, allowing the system to remain flexible.

8.8 Transport & Onsite Assembly

Transporting the panels and cassettes to site without damage became a primary concern for the design of the M8RX system. With panels being prefabricated off site, to completion, protecting the cladding overhang on the panel would be necessary as this design element was critical for the important floor to panel connection. Simply leaving the cladding overhang exposed could risk damage during transport especially when many panels are stacked on top of one another. To avoid this from happening, a basic transport frame was designed to attach to the bottom of the panel for the overhang to rest on. The frame is constructed out of standard 140mm x 45 mm timber frame perfectly fitting the dimensions of the base width of the panel. The bolts which attach the frame to the panel would be unbolted during assembly but remain in position when lowered into contact with the floor cassette. These very bolts could then be used to bolt the panel to the floor, removing the need for specialist fittings and saving on fixtures. The same process would be followed for the cladding and cavity battens at the rear. The transport frame would become reusable and could be returned to be used on future panels.

Figure 102: Panel with transport frame attached

Figure 103: Crane hoisting panel into place with transport frame attached

8.9 Panel to Panel Joint

The panel-to-panel joint is the most basic connection in the M8RX Flexible Construction System. The goal of this joint was to simplify the existing historical flexible connections, as these had an overly complicated joint for joining panels together. This in turn made expansion a difficult task. This joint treats panels as individual elements, meaning that panel elements do not overlap with other panels making the connection between them difficult. A simple butt joint is utilised here so that panels meet flush with one another.

The panels are connected with basic M10 bolts with washers either side to distribute the load around these holes. This joint can be assembled with basic tools such as a wrench or an impact driver. The joint's primary area of focus is on the exterior of the panel. Here flashing tape seals the gap between the two panels so that moisture, air, and noise can't penetrate through this area. Cavity battens are then screwed to the panel face across this taped area before cladding in the form of vertical board and battens are fastened over the top, creating a weatherproof barrier. This is the only action that is required onsite to finish the joint between the two panels.

8.10 Panel to Floor Joint

The panel to floor joint is the first major connection between two different system elements. Like the panel-to-panel connection, M10 bolts are used to fix the panel to the Pryda floor cassette. Because a nut and washer would be impossible to reach because of the overhanging cladding, a T-Nut insert is used on the underside of the floor cassette instead. As a result, tightening the bolt fastens the T-Nut tighter to the bottom of the floor cassette, creating a strong hold between the two elements. The overhanging cladding and cavity batten are then screwed into the floor joist with overhanging building paper in behind.

8.11 Panel to Roof Joint

The panel to roof connection is the second major connection between two different system elements and is arguably one of the most complicated. The outer plywood roof cassettes sitting between the LVL rafters contact the wedge top plate of the standard panel external walls. The roof cassettes are then bolted through the end of the base plywood component of the cassette and down into the wedge top plate. The bolt can be accessed from below inside the panel and a nut is tightened to finish this connection. Additional roof ties can be added to connect the LVL rafter to the panel upright if necessary.

8.12 Critical Reflection

The M8RX system has been developed to a high level of detail which has meant that the system has been critiqued and evaluated in equally high detail. Exploring areas such as onsite assembly and offsite fabrication has added another layer to the level of design research undertaken during this systems development. This level of detail and critical thinking around such issues lend a sense of realism and pragmatism to the system. This has been important as a key goal and the start of this research was to be deliberately pragmatic in the research approach.

Focusing on these areas and not just on the prefabricated system and connection has created a greater understanding of how the system may be used, assembled, and fabricated without having built such a system before. These findings have created an avenue to explore in the next chapter where a full-scale prototype of the system will be constructed. Evaluating these findings from the real build prototype will be a critical form of design feedback, against the performance of the system.

Fabrication & Assembly

- 9.0 Preface
- 9.1 The Prototype
- 9.2 Fabrication
- 9.3 Fabrication Issues
- 9.4 Panel Component Assembly
- 9.5 Panel Component Assembly Issues
- 9.6 Critical Reflection

Figure 104: Undertaking a tool change on the CNC Machine

9.0 Preface

The Fabrication and Assembly chapter involves the design and construction of a 1:1 M8RX construction system prototype. The intended purpose of the 1:1 prototype is to explore the designed connection and the fabrication and assembly of the M8RX panel in greater detail apply knowledge gained from the small-scale assembly tests and models. The application of New Zealand Building Standard E2 is also able to be incorporated in further detail with the use of industry specific weatherproofing materials.

9.1 The Prototype

A corner segment of the M8RX system was chosen to best showcase the systems flexible assembly. This involved the fabrication of 3 panels to demonstrate two different types of joints. Two standard 2400mm x 1200mm panels form a simple panel to panel connection, with a 2700mm x 1200mm right slope panel, illustrating the more complex corner join. These panels also demonstrate the different types of panel assembly methods, from standard assembly to extension assembly.

Figure 105: Render of the full scale assembly prototype

Figure 106: CNC Machine completing the pre-cut elements

Figure 107: CNC Machine completing the external profiles

9.2 Fabrication

Prior to Fabrication, the M8RX system components that were being used for this prototype build had to be converted into digital files that the CNC machine would be able to understand. It was here that the inefficiencies of the design process became apparent as SketchUp had been used as the software of choice for modelling all parts of the M8RX system. This involved taking the model apart piece by piece in Sketchup and arranging the pieces manually on a 2400mm x 1200mm rectangle that would form the cutting pattern. From here, the file was exported to Rhino to arrange these lines onto different cutting layers depending on the tool being used. This slowed the process significantly but the use of a similar process during the 1:2 scale panel fabrication meant that the process was well rehearsed and understood for the fabrication of the full-scale prototype.

Figure 108: The 3 different router bits used for cutting

Figure 109: Undertaking a tool change manually

The process of cutting the pieces also became an arduous process as it involved the use of 3 different drill bits to make the required cuts. Firstly, a 6mm flat mill cutter would cut out corner holes in any point along the tool path that included an internal corner. This is due to a CNC Machines inability to cut a perfect 90-degree corner due to the roundness of the tool. Drilling a 6mm hole in each of these internal corners would ensure that the components would slot together correctly. Once this was completed, a tool change was required, switching to a 30-degree dovetail cutter. This process of changing tools

Figure 110: Closeup of the number of element layers cut before the external profiles.

required the machine to be zeroed manually on the Z-axis each time. It would be discovered later that this would become a significant issue in the fabrication process (See 9.3 Fabrication Issues).

Once this layer had then been cut, the tool was once again changed to a 9mm compression cutter. The machine was set to complete three, near even plunges (6mm + 6mm + 5mm). This cutter was used to cut the bolt holes and the external profiles which were left till last to ensure that none of the pieces would move on the table assuring maximum accuracy. When this layer had completed

Figure 111: Plywood sheet removed from the machine

Figure 112: Tab to be sanded in preparation for assembly

cutting the sheet was removed from the table and the components were cut from the sheet using a saw to remove their tabs which had kept them in place. A small sand to remove the remainder of these tabs was completed and the components were ready to be assembled.

When left to run by itself the CNC machine was able to cut each sheet to completion in about one and a half hours. The final cutting layer, which involved the cutting of the external profiles of the components sometimes took up to half the total cutting time. The process of changing each tool added significant time to the overall cutting process and could be negated with the use of a more modern machine that has an automatic tool change.

9.3 Fabrication Issues

While the fabrication process ran smoothly, there were a few notable issues. Due to the fabrication process requiring 3 tool changes, this meant that the machine had to be zeroed on the Z-Axis each time a layer with the new tool was to be cut. This occurred manually and involved the operator “eyeballing” the point at which the drill bit contacted the surface of the plywood. While this was not an issue for the standard 6mm and 9mm drill bits, it proved a significant problem for the 30-degree V cutter. Positioning this too low meant that the cutter would then cut too far through the plywood resulting in a wider dovetail joint. This meant that the female dovetail joint did not provide a firm, friction fit with its male counterpart and the joint would slip out proceeding to compromise the rigidity of the panel when assembled. After multiple attempts to decrease the size of the dovetail by zeroing the cutter above the plywood, too no luck, it was discovered that the issue was instead caused by material thickness. The plywood used for the M8RX components which was advertised as 17mm was in fact 16.5mm and ranged in size between these two measurements over the whole sheet. This problem was rectified by changing the depth of the cut in the CAM software to account for the different thicknesses.

The second issue also related to the use of the V cutter but this time when cutting the panel face from a sheet of OSB. OSB is a highly dense and processed material, and it became apparent while cutting one dovetail that this material puts the V cutter under great stress. Extreme heat generated because of the V cutter's contact with the OSB meant that the shaft of one V cutters disintegrated while cutting through the OSB. The materials high density and larger thickness compared to the usual plywood is believed to have caused this failure. It was the only failure of this type seen throughout the entire fabrication process although scorch marks were visible on both the OSB and the flutes of the dovetail cutter at the end of the fabrication process.

Figure 114: Broken V cutter embedded in the OSB

Figure 115: Scorch marks on the new V cutter after use

Figure 116: Remaining pieces of the broken V Cutter

Figure 117: Adjustments in Rhino CAM

Figure 118: Inaccuracies in the depth of the material

Figure 119: Loose fitting panel component

Figure 122: Panel assembly sequence

9.4 Panel Component Assembly

M8RX panel assembly began once that fabrication stage was over. The components underwent small preparation beforehand, involving sanding to remove the leftover tabs. Assembly of the M8RX panels was simple and could easily be achieved with unskilled labour and basic tools following the sequencing method established during the half scale panel assembly tests. It is important to note that careful attention had to be paid to the installation direction of some components. For example, it was easy to confuse the Left Cassette Upright with the Right Cassette Upright. This led to installing the cassette uprights backwards on one occasion and it wasn't until the last component was to be installed that the mistake was realised and had to be rectified by disassembling the entire cassette.

Figure 123: Connecting a cassette upright to a dwang and top plate assembly

Complete assembly of each panel took around 30 minutes. This involved the assembly of the M8RX components and the cutting and stapling of building paper to cover the panel.

Once this was complete the panels were ready for cladding installation. Cavity battens were predrilled and screwed down at 480mm centres. The first layer of cladding boards is then spaced out using a specially designed tool to allow for efficient and accurate spacing. These boards are then predrilled and screwed in place before the final layers of battens is installed using the same method. Given the high amount of accuracy and care required when undertaking this process, it took longer than expected at around an hour.

Figure 124: Inserting the final component, the bottom plate

Figure 125: Completed dovetail jointing assembly with bolt hole for panel connection

Figure 126: Fastmount being attached to the dwangs

Figure 127: Stapling the corner of the building paper

1 | Panel + Building paper

2 | Panel + Building paper
+ Cavity battens

3 | Panel + Building paper
+ Cavity battens
+ Cladding

Figure 128: Construction sequence for building external weather barrier installation

Figure 129: Screwing in the cavity battens

Figure 130: Using the cladding spacer to install the boards evenly

Figure 131: Pre-drilling screw holes

Figure 132: Using the cladding spacer to install the boards evenly

9.5 Panel Component Assembly Issues

When assembled the basic panel weighed around 50kg. This weight allowed for easy manoeuvrability with two people at either end. Adding the cavity battens and exterior cladding added considerable weight to the panel. While the panel was still able to be manoeuvred by two people it was noticeably more difficult. This contributed to some clumsy handling of the panel when moving it around and damaged the corners of the building paper. For added protection, flashing tape was added around the sharp corner edges to reduce wear and tear.

Initial installation of the cavity battens onto the OSB panel face uncovered some issues. In similar ways to the disintegration of the V cutter, several screws snapped while screwing on the cavity battens. Failure of these screws was believed to be due to over torqueing the screws but upon looking back on the issues caused by the OSB during the fabrication process, this problem was put down to the density of the material. The decision to predrill holes for installation of the cavity battens was made in an attempt to avoid screws snapping in the future.

Figure 133: Flashing tape for added corner protection

9.6 Critical Reflection

Building the full-scale prototype tested the real-life build potential of the M8RX Flexible Construction System. Limited time meant that the final system assembly was not able to be completed in time by the submission of this thesis. Analysis of the small-scale prototypes and digital modelling of the prototype indicated that the designed connection would indeed work, however this was yet to be testing. Final system assembly will occur after the completion of this thesis to understand this process thoroughly and bring the fabrication and assembly process of this thesis to completion.

This page has been intentionally left blank

M8RX House

- 10.0 Preface
- 10.1 Client Selection
- 10.2 The Client
- 10.3 The Build
- 10.4 Linear Expansion
- 10.5 Lateral Expansion
- 10.6 Critical Reflection

10.0 Preface

In Chapter 9, the fabrication and assembly process of the M8RX system was analysed and evaluated. After deeming the system's ability to be constructed a success, further analysis was needed to demonstrate how the system might expand and grow against a set of design requirements. The following chapter therefore explores the way that the M8RX Flexible Construction System could be used in the design, construction, and alteration of a house. A basic house dubbed the 'M8RX House' has been designed and digitally modelled to assess and evaluate the M8RX system's flexible potential and its ability to alter the physical fabric of the house. The findings and resultant design outcomes will become the deciding factor as to whether the M8RX Flexible Construction System has real potential to be used in the construction of flexible houses.

10.1 Client Selection

In order to design a house, a brief would need to be formed to specify the clients and the requirements that the house would need to fulfil. This would create a starting point for the flexible house to begin its original built state, and then be changed and altered according to the various requirements of the brief. In an effort to eliminate bias by using the M8RX Flexible Construction System, it was decided that the client would be created by a third party. This would create an ideal situation where the system would aim to be flexible and change to the client's requirements, rather than forcing the clients to work around the system. By implementing this tactic, the true flexible potential of the system could be understood.

A google document called the client creator was established with a series of questions to fill in. With the participants consisting of predominantly university students and young professionals it was no surprise to have 50% of survey respondents describe their clients as first home buyers. After randomising the survey results, a client to base a design around was selected.

The screenshot shows a web-based survey interface. At the top, a purple header bar contains the text 'Section 1 of 5'. Below this, the main title 'Section 1 - Creating a Client' is displayed in a large, bold font. Under the title, there is a paragraph of introductory text: 'To begin designing, I need clients. It would be of great assistance if you could create personas that I could base designs around. These personas can be entirely fictional, you can base them on yourself or someone you know. Personal details will not be collected and anonymity is guaranteed.' Below this text, a smaller line states: 'Four preset options are given to you to begin with. Pick one and build a client from the given starting point.' The main content area contains a question: '1: What category does your client fall into?'. Below the question, there are four radio button options: '1: Young Home Buyers (Eg: Young Couple)', '2: Family', '3: Elderly Couple', and '4: Sole Occupant'. A red asterisk is visible to the right of the question number. At the bottom of the form, there is a blue vertical bar on the left side.

Figure 134: Screen snip of the 'Creating a Client' participant survey

10.2 The Client

Category: Young Home Buyer

Age: Mid 20s

Future Family Plans: Yes

Special Circumstances: No

Personal Design Preferences: They will be starting a family and would like to make provisions for space to accommodate their growing family.

10.3 The Build

The build of the original house will be known as the first stage. This first stage involves the construction of the house into its first built form. The proposed design is a simple one-bedroom design with a single bathroom and living area with a kitchen. The design of this house sets up the need for expansion in future years due to its small size.

Beyond the scope of this research is the inclusion of bathrooms and kitchens and other specific-use areas. For the design of this test house, First Light Studio's UNIPOD has been introduced to provide key services for the dwelling. The UNIPOD features a dedicated services wall between the bathroom and kitchen housing electrical and water services. This allows the opportunity for the M8RX panels to not have to contain services which allows them to be flexible.

The original build begins with the installation of the Surefoot Foundation system before the floor cassettes are craned into place over the top of this foundation. It is at this point that the UNIPOD is installed as the central services core of the building, forming the kitchen and bathroom backing on to one another.

The internal wall cassettes are installed after this being bolted together one by one. With the external walls providing the primary bracing the interior panel cassettes are constructed solely of plywood. Their lightweight design ensures that they can easily be lifted into place by one person.

The external wall panels are positioned in place and bolted down to the floor and to each other once this has occurred. Some of the larger panels may require a small crane such as a HIAB to put these in place.

Once the panels have been bolted into position the joins are taped and sealed with flashing tape before the remaining cavity battens are installed over the top and the final boards and battens are fixed into place.

The roof cassettes by this stage would have been lifted into place through the use of a small crane. Once in position these can be bolted from the inside of the house removing the need for external scaffolding. The joins on the roof cassettes follow the same procedure as the wall panels where the join is taped and the Espan cover plate is fixed into position over the top.

Once all joints have been sealed and tightened the internal lining can be applied though the use of the Fastmount clip system and the house becomes a water tight liveable structure.

The following series of images demonstrates this process.

Figure 135: First stage of the M8RX House, a one bedroom dwelling

Figure 136: Expansion plan showing stage one

10.4 Linear Expansion

The first expansion involves expansion of the house in the same modular direction. This will occur in preparation for the young couple's first child and will involve the addition of an extra bedroom. Linear expansion is the simplest form of expansion to allow the young couple to increase the size of their home. Like the original build, new foundations are installed at the rear of the house. The expansion adds an additional 3.6m in length to the house and 3 additional floor cassettes are to be placed atop these foundations, which results in an increased footprint of the house. The two rear most floor cassettes are placed in first, allowing room for the existing rear wall to be unbolted and moved back to the new end cassette. This is a key design attribute of the M8RX system which allows panels that have been used in the original build to be moved and used again in another similar part of the house.

Once these panels have been moved, new internal wall cassettes are positioned inside. This creates new partition walls dividing the space and creating the additional bedroom that is needed.

Then new external panels are put in place to fill in the remaining space between the existing panels and the relocated external wall. New roof cassettes are craned into position using the same process as the original build. All gaps in panels are sealed and covered and the process of linear expansion is complete.

The following images demonstrates the process of linear expansion.

Figure 137: Second Stage demonstrating linear expansion

Figure 138: Expansion plan showing the progression into stage two

10.5 Linear Expansion

The first expansion involves expansion of the house in the same modular direction. This will occur in preparation for the young couple's first child and will involve the addition of an extra bedroom. Linear expansion is the simplest form of expansion to allow the young couple to increase the size of their home. Like the original build, new foundations are installed at the rear of the house. The expansion adds an additional 3.6m in length to the house and 3 additional floor cassettes are to be placed atop these foundations, which results in an increased footprint of the house. The two rear most floor cassettes are placed in first, allowing room for the existing rear wall to be unbolted and moved back to the new end cassette. This is a key design attribute of the M8RX system which allows panels that have been used in the original build to be moved and used again in another similar part of the house.

Once these panels have been moved, new internal wall cassettes are positioned inside. This creates new partition walls dividing the space and creating the additional bedroom that is needed.

Then new external panels are put in place to fill in the remaining space between the existing panels and the relocated external wall. New roof cassettes are craned into position using the same process as the original build. All gaps in panels are sealed and covered and the process of linear expansion is complete.

The following images demonstrates the process of linear expansion.

Figure 139: Stage 3 demonstrating lateral expansion

Figure 140: Expansion plan demonstrating lateral expansion

10.6 Critical Reflection

The fabrication of the M8RX construction system in chapter 9 provided a great sense of realism to the system demonstrating that there was potential to build out of such a system. This led to the design of the M8RX test house as way of investigating whether the system had potential to be used in the design and construction and expansion of such flexible house. The M8RX house has demonstrated that the concept of flexible housing may be a closer possibility than what was once thought.

The decision to model in extreme detail with the use of the digital components created the sense of physically building, albeit digitally. Certain clashing elements in the digital model illustrated the need for further refinement of the system specially to do with aspects relating to the external cladding which tended to clash with the roof during the process of lateral expansion.

Critical Reflection

- 11.0 Preface
- 11.1 Process Reflection
- 11.2 Research Limitations
- 11.3 M8RX System Improvements
- 11.4 Future Direction

11.0 Preface

This chapter reflects on the overall design process of this thesis. It covers personal reflection on the design process and the methods used during the design led research phase. Further reflection is carried out on the design outcome as well as thoughts on where the research could lead in the future.

11.1 Process Reflection

As mentioned at the start of the thesis, the intent was to be deliberately pragmatic in the approach to the design led research phase. The use of scale modelling and scale prototyping allowed for hands on learning during this stage and was largely beneficial in the making of design decisions. Such a large amount of concept work and high level of detail would not have been possible without using this method of designing. The act of building and fabricating also added significant understanding of how such a system and connection may work. The aspect of physically making and building lead to better evaluation and analysis of the design outcomes during the concept and developed design phase.

11.2 Research Limitations

The events of 2020 created significant issues at the start of the design led research process. With the intention of physically modelling and prototyping as much as possible, this design method was forced to be re-evaluated. While prototyping was able to get underway after the return to university, the delay in being able to access critical machinery, slowed the design process immensely. Had this not occurred, further development of the system may have been able to have been undertaken and led to a more refined final output.

11.3 M8RX System Improvements

While the M8RX system performed admirably during full scale assembly and during the design of the M8RX house it is by no means a refined system that could be adopted immediately as a flexible construction system. The decision to model in extreme detail with the use of the digital components created the sense of physically building, albeit digitally. Certain clashing elements in the digital model illustrated the need for further refinement of the system specially to do with aspects relating to the external cladding which tended to clash with the roof during the process of lateral expansion. Further design exploration of the modular organisational system needs to be explored too.

Lastly, the M8RX Flexible Construction system would benefit significantly from further design exploration of designed houses. Development of the system only showed so much before it reached a point where it was felt it could be developed no further without further testing. Designing and testing the system in the form of different arrangements of flexible houses would test the system further and evaluate its flexibility.

11.4 Future Direction

After completing the assembly of the prototype, there is no doubt that the next move is to continue fabricating and eventually produce a full-scale flexible house, like the one designed in Chapter 10 to evaluate the true performance of the system. As mentioned above, the system does have some significant limitations and improvements to be made and with further design development and further fabrication, this system's true potential may eventually be realised.

One design technique that was not explored during this thesis was the introduction of parametric design to the development of the system. Using parametric design would have allowed for faster production of digital components and the ability to create a set of rules and constraints so that each different type of panel is designed to the same set of parameters. This would particularly have been of use during the design of panels with openings in them. Parametric design would have sped up the process significantly and allowed for exploration of different parts of the system in greater detail.

This page has been intentionally left blank

Final Remarks

12

12.0 Final Remarks

The purpose of this research was to respond to the question: “How can a designed connection, in combination with a prefabricated building system, be applied to the construction of houses in New Zealand to create flexible homes which can change with the occupant?”

Research into the extent of New Zealand’s housing crisis revealed a significant issue based around suitability. Houses that people once lived in were no longer suitable based on the size of their household in relation to the size of their home. This meant that New Zealanders were sometimes having to choose between living in a cramped home with too many people or having to uproot their families and purchase a new home that was in turn more suitable.

However, research has found that simply building more houses does not curb this problem as it is unlikely to address the changing demographics of the country which is contributing largely to this issue. The focus of this research therefore became how we could potentially build houses which could be more suitable for the occupants which lived in them. Making sure these houses could change and adapt to any given circumstance was the primary focus, and so developing a flexible housing system was critical to analysing if the concept of flexible housing was feasible.

There was careful evaluation of traditional NZ building methods, followed by analysis of a historical New Zealand precedent and the exploration of extensive structural and material analyses. This allowed a base to be created. This base was used to develop a new modular structural system and connection based around the idea of flexibility.

Full scale fabrication and assembly of the system demonstrated that the system’s feasibility as a prototype system has real world potential and could be used in the construction of flexible houses.

This thesis has found that this system can be used in the design and construction of a flexible house that can change with the occupant over the lifetime of the building. New Zealanders can live in a house which is accommodating of their needs, whatever they may be.

The challenge lies in disrupting or disturbing the status quo about what ‘housing’ may mean for New Zealanders. This has profound social, economic, environmental, and human health consequences in the real world. After all, in a country where increasing amounts of valuable agricultural land is being built upon for housing, where land and house values (particularly in Auckland) show

no signs of decreasing, and population and immigration will only increase, flexibility and adaptability of housing may become an over-riding concern. Added to this are New Zealand's changing demographics, where a rapidly ageing population find themselves in housing manifestly unsuitable to their needs, and a young population are economically excluded from ever owning a home.

A house must become a 'living' entity, changing and adapting throughout its 'lifespan', just as we biologically change and adapt with age.

I hope this thesis has demonstrated the viability of a flexible modular construction system within the New Zealand context. My hope would be that this work is a contribution towards market development of such a system.

Bibliography

13

Ardern, J. (2020). Labour keeps housing sector moving. NZ Labour Party. <https://www.labour.org.nz/release-labour-keeps-housing-sector-moving>

Bassett, M., Malpass, L., & New Zealand Initiative (Organisation). (2013). *Priced out: How New Zealand lost its housing affordability*.

Bell, P. (2009). *Kiwi Prefab: Prefabricated Housing in New Zealand: an Historical and Contemporary Overview with Recommendations for the Future* [Victoria University of Wellington]. <http://researcharchive.vuw.ac.nz/handle/10063/1111>

Bergdol, B., & Christensen, P. (2008). *Home Delivery: Fabricating the Modern Dwelling*. Museum of Modern Art.

Burgess, J., Buckett, N., & Page, I. (2013). Prefabrication Impacts in the New Zealand Construction Industry (No. SR279; p. 105). BRANZ.

Davey, J. (2006). "Ageing in place": The views of older homeowners on maintenance, renovation and adaptation. *Social Policy Journal of New Zealand*, 27, 14.

Davies, C. (2005). The Prefabricated Home. In *The Prefabricated Home* (p. 3,6-206,209-216). Reaktion Books Ltd. <https://www.proquest.com/docview/1428331077/abstract/592345DE697047EAPQ/1>

Denhardt, T. (2016). CNC – The New Approach To Building. *Architecture New Zealand*, January 2016(1). </articles/cnc-the-new-approach-to-building/>

Dudding, M. (2010). The supersized homes puzzle. *Stuff*. <https://www.stuff.co.nz/sunday-star-times/features/4045718/The-supersized-homes-puzzle>

Escaleira, C., Amoêda, R., & Cruz, P. J. (2019). Connections and joints in buildings: Revisiting the main concepts on building materials life cycle's circularity. 225, 7. <https://doi.org/10.1088/1755-1315/225/1/012062>

Gibson, A. (2021). REINZ figures: House prices reach new highs as market hits busiest period in 14 years. *NZ Herald*. <https://www.nzherald.co.nz/business/reinz-figures-house-prices-reach-new-highs-as-market-hits-busiest-period-in-14-years/JYRC2JDPZ2NCW4HR2BJOWPMJVU/>

Groak, S. (1992). *The Idea of Building: Thought and Action in the Design and Production of Buildings*. CRC Press LLC. <http://ebookcentral.proquest.com/lib/vuw/detail.action?docID=169734>

Hay, R. (1974). *The Research and Development for Industrialised Building Systems Ltd* (Vol. 1).

Hay, R. (2012). *Out Of Time: IBS, an idea too strange for home* (1983). In *Kiwi Prefab: Cottage to Cutting Edge* (pp. 26–33). Balasoglou Books.

Herbert, G. (1984). *The dream of the factory-made house: Walter Gropius and Konrad Wachsmann*. MIT Press.

Hong, L. (2021). The housing shortage is even worse than you'd thought. The New Zealand Initiative. <https://www.nzinitiative.org.nz//reports-and-media/opinion/the-housing-shortage-is-even-worse-than-you-d-thought/?1>

Imperiale, A. (2012). *An American Wartime Dream: The Packaged House System of Konrad Wachsmann and Walter Gropius*. 5.

Isaacs, N. (2010). Timber framing – rapid and reliable. *Build Magazine*, August/September 2010, 2.

Jeram, J. (2014). Empty nests, crowded houses: Building for an ageing population. The New Zealand Initiative.

Johnson, A., Howden-Chapman, P., Eaquib, S., & Ministry of Business, I. & E. (2018). *A stocktake of New Zealand's housing*.

Martinez, D. D. (2019). Residential Speculation. Architectural experiments and real estate in the formation of postwar American suburbs. Archive ARQ Eure. <https://archives.cl/en/residential-speculation-architectural-experiments-and-real-estate-in-the-formation-of-postwar-american-suburbs/>

Ministry for Culture and Heritage. (2014). State house style—State housing | NZHistory, New Zealand history online. New Zealand History. <https://nzhistory.govt.nz/culture/we-call-it-home/state-house-style>

Moradibistouni, M., & Gjerde, M. (n.d.). *Potential for Prefabrication to Enhance the New Zealand Construction Industry*. 9.

Moradibistouni, M., Vale, B., & Isaacs, N. (2018). *Prefabrication: New Zealand manufacturers of prefabricated buildings and components 2017*. 9.

New Zealand Department of Building and Housing. (2010). *New Zealand Housing Report 2009/2010: Structure, Pressures and Issues*. In *New Zealand housing report structure, pressures and issues*. (p. 103). Dept of Building and

Housing.

Pearse, A. (2021). Housing: Carter Holt Harvey cuts timber supplies to Mitre 10, Bunnings, ITM. NZ Herald. <https://www.nzherald.co.nz/business/housing-carter-holt-harvey-cuts-timber-supplies-to-mitre-10-bunnings-itm/P3T6DQ2PBT4JDZ64AAF26WIRU4/>

Prefab NZ. (2015). Prefab NZ 5 Year Impact Report.

Prefab NZ. (2018). Prefab Good Offsite Guide (p. 37). Prefab NZ.

Rosevear, M., & Curtis, M. (2015). Physical characteristics of new houses 2015 (No. SR367; p. 19).

Serratts, M. (2012). Prefab Houses Designsource (1st. ed.). Harper Design.

Smith, Ryan. E. (2010). Prefab Architecture: A Guide to Modular Design and Construction. John Wiley & Sons.

Stats NZ. (2014). 2013 Census QuickStats about families and households. Stats NZ. <http://archive.stats.govt.nz/Census/2013-census/profile-and-summary-reports/qstats-families-households.aspx>

Stats NZ. (2016). Changes in home-ownership patterns 1986–2013: Focus on Māori and Pacific people. 52.

Stats NZ. (2020a). 46-year high for new home consents. Stats NZ. <https://www.stats.govt.nz/news/46-year-high-for-new-home-consents>

Stats NZ. (2020b). Housing in Aotearoa: 2020 (p. 139).

Stats NZ. (2020c). New data shows 1 in 9 children under the age of five lives in a multi-family household. Stats NZ. <https://www.stats.govt.nz/news/new-data-shows-1-in-9-children-under-the-age-of-five-lives-in-a-multi-family-household>

Stats NZ. (2020d). New homes around 20 percent smaller. Stats NZ. <https://www.stats.govt.nz/news/new-homes-around-20-percent-smaller>

Tower, M., Gropius, W., & Wachsmann, K. (2003). The Packaged House System (1941-1952). *Perspecta*, 34, 20–27.

von Zimmerman, J. (2012). Build it in the morning, move in in the evening. Stylepark. <https://www.stylepark.com/en/news/build-it-in-the-morning-move-in-in-the-evening>

Wachsmann, K. (1961). The turning point of building: Structure and design. Reinhold.

Watkins, T. (2009). The Human House: Sustainable Design. Karaka Bay Press.

Source Illustrations List

14

Figure 3: New Houses under construction in Pokeno. Sourced from: <https://www.waikatodistrict.govt.nz/news/public-notice/article/2019/10/31/community-committee-triennial-meeting>

Figure 5: New Zealand state houses in the 1950's. Sourced from: <https://paulmaunder.com/2017/12/04/fixing-the-housing-crisis/>

Figure 6: New suburb development in Milldale. Sourced from: http://www.closingthegap.org.nz/press-release-25-march-2021-the-governments-response-to-the-current-housing-crisis-in-nz-a-good-start-but-nowhere-near-enough/?utm_source=rss&utm_medium=rss&utm_campaign=press-release-25-march-2021-the-governments-response-to-the-current-housing-crisis-in-nz-a-good-start-but-nowhere-near-enough

Figure 8. Low quality state houses. Sourced from: http://www.closingthegap.org.nz/press-release-25-march-2021-the-governments-response-to-the-current-housing-crisis-in-nz-a-good-start-but-nowhere-near-enough/?utm_source=rss&utm_medium=rss&utm_campaign=press-release-25-march-2021-the-governments-response-to-the-current-housing-crisis-in-nz-a-good-start-but-nowhere-near-enough

Figure 9: Standard timber frame construction: Sourced from: [https://www.beaconpathway.co.nz/images/uploads/Executive_Summary_Wall\(3\)_Measuring_extent_of_thermal_bridging_in_timber_framed_external_walls.pdf](https://www.beaconpathway.co.nz/images/uploads/Executive_Summary_Wall(3)_Measuring_extent_of_thermal_bridging_in_timber_framed_external_walls.pdf)

Figure 10: Balloon frame construction (left) and platform frame (right). Two examples of light timber frame construction in New Zealand. Sourced from: Timber Framing – Rapid and Reliable, Nigel Isaacs

Figure 21: Digital Fabrication using CNC machining. Sourced from: <http://joanna-stabler-tifr.squarespace.com/wikihouse>

Figure 23: Walter Gropius and Konrad Wachsmann inspect the Packaged House during assembly. Sourced from: Home Delivery: Fabricating the Modern Dwelling, Barry Bergdoll & Peter Christensen

Figure 26: (Left) IBS prototype home. Sourced from: Kiwi Prefab, Cottage to Cutting Edge, Pamela Bell

Figure 27: The American mobile home on which the IBS concept was based. Sourced from: Kiwi Prefab, Cottage to Cutting Edge, Pamela Bell

Figure 28: IBS expansion floor plans. Sourced from: Kiwi Prefab, Cottage to Cutting Edge, Pamela Bell

Figure 29: IBS Wall Panel. Sourced from: The Research and Development Programme for Industrialised Building Systems Ltd. Roger Hay Collection. [01/14]. Architecture Archive, University of Auckland Library

Figure 30: IBS Panel Joint. Sourced from: The Research and Development Programme for Industrialised Building Systems Ltd. Roger Hay Collection. [01/14]. Architecture Archive, University of Auckland Library

Figure 31: IBS Module expansion. Sourced from: The Research and Development Programme for Industrialised Building Systems Ltd. Roger Hay Collection. [01/14]. Architecture Archive, University of Auckland Library

Figure 32: Sketch of the IBS prototype home. Sourced from: Kiwi Prefab, Cottage to Cutting Edge, Pamela Bell

Figure 33: The first IBS prototype house in Avondale, Auckland. Sourced from: The Research and Development Programme for Industrialised Building Systems Ltd. Roger Hay Collection. [01/14]. Architecture Archive, University of Auckland Library

Figure 34: (Left) Konrad Wachsmann & Walter Gropius alongside a stack of Packaged House panels. Sourced from: <https://parasitevisions.wordpress.com/2010/09/04/form-finding-techniques-konrad-wachsmann/>

Figure 35: An early scale model from Konrad Wachsmann on what he envisioned for the Packaged House. Sourced from: Home Delivery: Fabricating the Modern Dwelling, Barry Bergdoll & Peter Christensen

Figure 37: Wedge Connector. Sourced from: The Turning Point of Building, Konrad Wachsmann

Figure 38: Position of the wedge connector parts in the wooden panel frames. Sourced from: The Turning Point of Building, Konrad Wachsmann

Figure 39: Wedge connector in locked position. Sourced from: The Turning Point of Building, Konrad Wachsmann

Figure 40: Stack of Packaged House panels with wedge connectors. Panels also contain electrical installations. Sourced from: Home Delivery: Fabricating the Modern Dwelling, Barry Bergdoll & Peter Christensen

Figure 41: Axonometric drawing of a proposed design for the Packaged House System. Sourced from: *The Dream of the Factory-Made House*, Gilbert Herbert

Figure 42: Packaged House panels. Sourced from: *The Turning Point of Building*, Konrad Wachsmann