HOMELESS.

Self-build Housing for Wellington's Transitionally Homeless

Jacob R. Goodger
300322658

A 120 - point thesis submitted to the Victoria University of Wellington in partial fulfilment of the requirements for the degree of Masters of Architecture (Professional).

Victoria University of Wellington
School of Architecture

2018

HOME~~LESS~~.

Self-build Housing for Wellington's Transitionally Homeless

Jacob R. Goodger
300322658

A 120 - point thesis submitted to the Victoria University of Wellington in partial fulfilment of the requirements for the degree of Masters of Architecture (Professional).

Victoria University of Wellington
School of Architecture

2018

Figure 0.02 (left):
Infographic representation showing
number of transitionally homeless
currently in New Zealand -
<Authors own>.

Abstract

Housing is an important precondition for people to live healthy and prosperous lives. Access to suitable housing is an essential factor in the overall well-being of individuals, families, and communities. Housing suitability and quality has ramifications for physical and mental health, education, employment, social cohesion and intergenerational mobility. These outcomes directly impact the functioning of communities, broader society, and the economy (Ministry of Business Innovation & Employment).

Per capita, New Zealand has one of the highest rates of homelessness in the world. At 1% of the total population, it is estimated that approximately 42,000 New Zealanders are experiencing some form of homelessness. These individuals are either in temporary or insecure accommodation (OECD). Our capital's housing supply is evidentially not meeting demand. Wellington is currently 9312 dwellings short of what is required, resulting in multiple tenants residing in singular rooms, and an increase in homelessness (Ministry of Business, Innovation & Employment). This issue arises when there is an intermediate population deemed 'too rich' for social housing by the Ministry of Social Development screening process. However, due to low current median incomes this group are not able to afford Wellington's rental prices, leaving them with little to no options in securing healthy and stable accommodation. Those fortunate enough to secure tenancy find themselves marginalised by society as they are not in permanent 'homes' but transitional residences on the city fringes.

This thesis explores a novel approach to our capital's housing crisis, with the specific intention of provoking conversation about alternative approaches to the re-housing of New Zealanders most at need. Giving individuals the opportunity to up-skill, combined with the ability to craft their own permanent home will provide the helping hand needed to get them back on their feet and re-introduced into productive society.

Interviews with Wellington's housing providers and those working directly with the homeless have informed the key considerations for providing housing for the transitionally homeless. The literature review highlights the importance of creating and enhancing a sense of belonging through architectural design strategies. Precedent studies are analysed to understand the importance of location, planning, appearance and the materiality of housing units as well as assessing the validity of self-build housing for New Zealand. This research develops a universal design response to affordable housing in Wellington. A non-exclusive approach facilitates residents as a whole rather than focusing on site specifics, thus achieving a more holistic design concept. This model can be implemented in a broader context to ultimately support the provision of quality and affordable housing to those in most need.

The outcomes of this thesis include; a set of design guidelines for those involved in the provision of housing for the transitionally homeless, and a detailed design proposal for a conceptual housing intervention in urban Wellington.

Figure 0.01 (above):
 Sketch illustrating diversity of transitionally homeless population -
 <Authors own>.

Preface

In the five years that I have lived in Wellington, I have observed the lack of healthy and affordable housing in the city. I have never experienced homelessness. I have been fortunate enough to have had the ability to work and support myself with help from both family and friends, in order to keep a roof over my head and food readily available to me. It is hard to fathom that this is a luxury, which is unattainable for so many New Zealanders.

Growing up in rural New Zealand I was, to some degree, sheltered from the concept of homelessness. The sense of home and belonging is something that I have always known and taken for granted. The fact that this is an experience unfamiliar to many New Zealanders resonates in my mind. This uncomfortable resonance has fuelled my passion for architecture, and is one of the key reasons that I pursue it as a profession. I have always been intrigued in the reasons why individuals end up being homeless, yet more so interested in how we as a society are quick to turn a blind eye to this issue, and how limited the support for the homeless population would appear to be. These factors combined with my interest in designing high quality, affordable, yet innovative housing, have led to the theme of this thesis.

Acknowledgements

This thesis is dedicated to those who are actively working for the protection and rehabilitation of the homeless population within New Zealand.

I would like to thank the following people who all played a part in the development of this thesis.

Firstly, to the team at Kuhungunu Whanau Services and Te Whakamura Ai Te Ahi, and especially to Bernice, whose passion and dedication was truly inspiring. Secondly, Karen, Matt and all the staff/volunteers at the Te Puaroha Compassion Soup Kitchen, whose insight and knowledge was extremely beneficial moving forward at an early stage of this project. I have been deeply encouraged to see there are so many people willing to help those that would seem to be the hardest to help, with the aim of restoring independence to fellow New Zealanders. It is obvious that their work is beneficial to so many, and I find this inspirational and commendable.

To both of my Supervisors; Adele Leah and Hans-Christian Wilhelm. Your combined guidance and expert knowledge is something I could not have done without. I hope that this thesis is something you too can be proud of.

Finally, to my parents; Tom and Leanne. I have, and will always know where Home is. My whole life you have provided the support and motivation to push myself further. I cannot thank you both enough for this.

“

A PLACE WHERE I
AM NOT JUDGED,
A PLACE WHERE I
DO NOT HAVE TO
PRETEND,
A PLACE WHERE I
FEEL SECURE,
A PLACE THAT IS MY
BIGGEST BLESSING,
A PLACE THAT I
CALL...

HOME ”

MEARS, 72

V	Abstract
VII	Preface
VIII	Acknowledgements
X	Contents

Chapter One: Introduction & Research Overview

1	1.1 Background
3	1.2 Research Scope
5	1.3 Research Aims & Objectives
7	1.4 Research Methodology
8	1.5 Thesis Structure

Chapter Two: Literature Review

11	2.1 Introduction
12	2.2 Overview of Selected Literature
	2.2.1 <i>Te Mahana: Ending Homelessness in Wellington - A Strategy for 2014 - 2020 (Wellington City Council)</i>
	2.2.2 <i>Homes People Can Afford; How to Improve Housing in New Zealand (Bierre)</i>
	2.2.3 <i>Designing for the Homeless; Architecture that Works (Davies)</i>
	2.2.4 <i>Future Social; Design Ideas, Essays and Discussions on Social Housing for the 'Hardest to House' (University of British Columbia School of Architecture + Landscape Architecture 2012).</i>
14	2.3 Analysis of Selected Literature
	2.3.1 <i>A Sense of Belonging and the Benefits of Community</i>
	2.3.2 <i>Affordability</i>
	2.3.3 <i>Purpose-Built Design</i>
18	2.4 Conclusions
20	2.5 Housing First; Feasibility Study for the Liverpool City Region
23	2.6 Conclusion

Chapter Three: Interview Process

25	3.1 Process
	3.1.1 <i>Te Whakamura Ai Te Ahi</i>
	3.1.2 <i>Compassion Soup Kitchen</i>
30	3.2 Conclusions

Chapter Four: Precedent Study

33	4.1 Introduction
35	4.2 Analysis of Selected Precedents
	4.2.1 <i>Luke Street Transitional Housing Development, Otahuhu, Auckland</i>
	4.2.2 <i>Henderson Transitional Housing Units, West Auckland</i>
	4.2.3 <i>Jagtvej 69 'Vendepunktet', Copenhagen, Denmark</i>

	4.2.4	<i>Transition Centre Apartments, Rambouillet, France</i>
42	4.3	Conclusions
44	4.4	Self-build Case Study
	4.4.1	<i>Extension House Neukolln, Berlin, Germany</i>
	4.4.2	<i>R50 Apartments, Berlin, Germany</i>
50	4.5	Conclusions

Chapter Five: Design Guidelines

53	5.1	Process
56	5.2	Design Brief
57	5.3	Conclusions

Chapter Six: Design Iterations

61	6.1	Process
63		DESIGN ITERATION I: Small Detached House
63	6.2	Design Summary
64	6.3	Massing & Modular Studies
	6.3.1	<i>Massing Study</i>
	6.3.2	<i>Modular Study</i>
68	6.4	Design, Construction & Occupancy Management
70	6.5	Physical Modelling
	6.5.1	<i>Initial Modelling</i>
	6.5.2	<i>Massing Models</i>
	6.5.3	<i>Programme Development</i>
80	6.6	Final Concepts
83	6.7	Energy Efficiency, Green Innovation, & Environmental Quality
85	6.8	Conclusions
87		DESIGN ITERATION II: Self-Build Apartment Housing
87	6.9	Design Summary
88	6.10	Site
	6.10.1	<i>Site Selection</i>
92	6.11	Locality Map
94	6.12	Proximity Map
96	6.13	Site Context & Planning Aspects
97	6.14	Design Coherence
98	6.15	Environmental Response
100	6.16	Form Development
104	6.17	Construction Process
106	6.18	Concept
111	6.19	Conclusions

Chapter Seven: Detailed Design Proposal for Self-Build Apartment Housing

113	7.1 Design Summary
114	7.2 System Framework
120	7.3 Stage One: Structural Shell Completion
126	7.4 Stage Two: Facade & Building Envelope
136	7.5 Stage Three: Intertenancy Configuration + Services & Fixed Utilities
140	7.6 Stage Four: Interior Fit-out
164	7.7 Building Configuration
175	7.8 Exemplar Floorplan Layouts
180	7.9 Building Elevations

Chapter Eight: Conclusions

221	8.1 Overview
222	8.2 Conclusion
	8.2.1 <i>Constraints & Limitations</i>
	8.2.2 <i>Potential Applications of Research</i>
	8.2.3 <i>Future Advancement</i>
	8.2.4 <i>Overall</i>

Works Cited

Bibliography

List of Figures

Appendix One:

232	NZ Housing Continuum
-----	----------------------

Appendix Two:

234	Detailed Organisation Analysis
-----	--------------------------------

Appendix Three:

248	Detailed Precedent Analysis
-----	-----------------------------

Appendix Four:

258	Overview of Wellington Homeless Statistics
-----	--

This page intentionally left blank.

1.

Chapter One: Introduction & Research Overview

1.1 Background

Housing in New Zealand is rapidly becoming one of our country's greatest issues. Research suggests that New Zealand is amidst a housing crisis. According to the 14th annual International Housing Affordability Survey conducted by Demographia there is not a single region of New Zealand that can be considered affordable. The survey indicates that anything above three times the average income is rated unaffordable. New Zealand averages a 5.8 median multiple, classifiable as 'severely unaffordable' with Auckland reaching an astonishing 8.8 (19-21). The complexity of such crisis should not be overstated and can be explained by a multitude of factors, including; more people working and living in urban centres, increasing income inequalities, and a rising housing market (Bierre 41). This shortage of affordable properties in New Zealand's main urban centres is consequently denying many New Zealanders their basic right to adequate housing, forcing them into an undignified position: homelessness (Johnson 38).

Homelessness in New Zealand is an issue that has graduated in more recent years into a common problem for many urban centres. There is no homogeneous typology of issues surrounding homelessness; instead, we see our vast range of problems unique to each individual and situation. A research paper published by New Zealand Parliament states that unaffordable accommodation, poverty, unemployment, mental health issues, addictions, traumatic life events, convictions and imprisonment are all contributing factors to homelessness ("*Homelessness in New Zealand*"). Without a permanent address or place to call home, it is difficult to secure employment and undertake basic tasks such as bathing and washing laundry. The homeless community are denied many basic necessities, opportunities, and choices that most New Zealanders take for granted.

Like any major social, economic or political issue there is not usually a blanket solution or 'easy fix'. Homelessness is no different. It is a socio-economic issue that extends far beyond the context of an architectural intervention. Research suggests that the design of the built environment and aesthetic and design elements can influence health and well-being. Therefore innovative design solutions (when part of a fully developed holistic strategy aimed at addressing homelessness) can aid and support the transition of the homeless back into permanent housing (Ayers 23).

The outcomes of this thesis include developing a novel strategy which will incorporate two design aspects; 1) Design guidelines for those involved in the provision of housing for the transitionally homeless in Wellington; and 2) A detailed design proposal for a conceptual housing intervention for the transitionally homeless.

MORE THAN ***42,000**
NEW ZEALANDERS ARE
ON THE STREETS, IN
EMERGENCY HOUSING
OR IN SUBSTANDARD
SHELTERS

1.2 Research Scope

For the purpose of this research, homelessness has been categorised into three main categories; transitionally homeless, episodically homeless, and the periodically homeless (see figure 1.01). This classification is adopted from Housing First Auckland's simplified form of the New Zealand definition of homelessness established by Statistics NZ (Housing First).

This research will focus on housing for the transitionally homeless. Transitionally homeless are everyday people experiencing extreme financial hardship as a result of redundancy, family breakdowns and/or health issues. As a result, they cannot secure permanent tenancy or a place of their own (see figure 1.01) Transitional homelessness will form the fulcrum of this analysis because there is a notable lack of purpose-built housing available in Wellington for those seeking permanent shelter. Rather than focussing on housing with temporary or restricted durations of time for inhabitation, this research will investigate the ways in which permanent and affordable housing can play a part in the transition from dependence to independence of the users. "For many people, having access to secure and affordable housing as quickly as possible is enough to end their homelessness" (Wellington City Council "*Te Mahana*" 13).

Figure 1.01 (left):
Categorisation of New Zealand Homelessness including percentages - Based on Housing First Model - Auckland, NZ - <Authors own>.

HOW CAN
SELF-BUILD
CONSTRUCTION
CONTRIBUTE
TO PRODUCING
A QUALITY &
AFFORDABLE
HOUSING
SOLUTION FOR
WELLINGTON'S
**TRANSITIONALLY
HOMELESS** ?

1.3 Research Aims & Objectives

The question being presented in this research is; how can self-build construction contribute to producing a quality & affordable housing solution for Wellington's transitionally homeless?

The aims of this research are to; 1) propose a novel approach to the provision of housing for the transitionally homeless in Wellington; and 2) develop and reflect upon a detailed design proposal for a housing scheme in the city.

The strategic objectives of this research are to; 1) discover and explore the key considerations in the provision and design of housing for the transitionally homeless in Wellington. These will be discovered through interviews with the city's housing providers and those working directly with homeless; 2) investigate the importance of the location, planning, appearance and the materiality of housing units through a literature review and analysis of precedent studies; and 3) develop a detailed design proposal for a housing scheme for the transitionally homeless in Wellington. This novel approach will act as a guide for those who wish to pursue or are already involved in the provision of housing for the transitionally homeless in Wellington .

Buildings we create are direct reflections of our culture and history. Any proposal or architectural intervention will have the objectives of exhibiting kiwi values and representing New Zealand society. This thesis proposes to go beyond a temporary housing solution - Instead it will create an expression of modern architecture fitting the context of urban New Zealand. This context requires creating a home environment, and re-establishing a sense of belonging for Wellington's transitionally homeless.

The detailed design proposal will focus on the redevelopment of an inner city site with a combination of residential units and public spaces, thus integrating the transitionally homeless population with the rest of society through engaged social interaction. To address homelessness with this mindset, rather than turn a blind eye, means that the issues are tackled head on, bringing homelessness to the forefront of everyday life. This is a place where the stigma surrounding homelessness can be addressed.

It is envisaged that this research will be of interest to councils, charitable organisations, and urban and architectural designers who are involved in the provision of housing for the transitionally homeless in Wellington. Although this thesis is tailored towards architectural interventions, there is hope that this research will also provide an impetus for changing the culture of homelessness, policy direction and how everyday New Zealander's approach the issue.

1.4 Research Methodology

Before commencing any design or experimentation, it was essential to develop a thorough understanding of homelessness in Wellington. This initial platform of knowledge assisted in delivering an appropriate and realistic design solution.

Four key bodies of knowledge informed the design output of this research (see Figure 1.2). The methods of research undertaken in this thesis include:

- 1) A literature review of principal theorists of homeless housing, existing strategies and considerations of housing design and analysis of an existing Housing First study in the United Kingdom;
- 2) An analysis of precedent studies to understand the importance of location, planning, appearance and the materiality of housing units;
- 3) Meeting with Wellington's housing providers and those working directly with the homeless population in the city was the best way to obtain a foundational understanding. As such, interviews with a number of Wellington based organisations are an important part of the research methodology;
- 4) Identification of vacant sites within the city which are suitably located.

Based on the above research findings a detailed design proposal has been developed.

Figure 1.02 (left):
Research Methodology Diagram. In
order of tasks undertaken -
< Authors own>.

1.5 Thesis Structure

The structure of this thesis follows the timeline of tasks undertaken.

Chapter 1 provides an overview of the current housing situation in New Zealand, specifically urban Wellington. This chapter includes recent statistics of homelessness, a summary of key ideas and the intended research objectives.

Chapter 2 focuses on the review of literature relevant to the provision of homeless housing. This chapter considers ways in which authors and designers have approached important aspects of design such as; strategies for achieving affordable housing, attaining a sense of home, and self-build design techniques relevant to the implementation of a housing scheme in Wellington.

Chapter 3 begins to build the case for successful housing intervention solutions for the transitionally homeless. It includes an analysis of current New Zealand housing precedents as well as international examples. A summary of existing evidence and design techniques provides a basis for the design proposal. It takes into consideration strategies for achieving affordable housing and purpose-built design techniques applicable to a housing scheme in Wellington.

Chapter 4 presents the findings and insights from the interview process conducted with key housing providers and organisations that work directly with homeless in Wellington. These organisations include; Te Whakamura Ai Te Ahi, Kahungunu Whanau Services, and the Compassion Soup Kitchen.

Chapter 5 defines the design guidelines specific for an effective housing intervention in urban Wellington. It reflects upon knowledge and insight gathered from the three main bodies of knowledge; precedent study, literature review, and the interview process.

Chapter 6 outlines the first design experimentation; The small detached home. This chapter focuses predominantly on replicating the feeling of 'home' and how this can be conducted utilising principles of prefabrication, modularisation and affordable design techniques.

Chapter 7 explores a progression of the first design iteration. It uses the same design principles and design guidelines to form a higher density apartment development concept. This is concluded to be a more economical response to housing in urban Wellington.

Chapter 8 continues to develop design iteration II. In this chapter a developed design proposal is presented including; a design summary, breakdown of the operational framework required, information of the complete building framework, and rendered images showing the design implemented on the 133 Taranaki Street site.

This page intentionally left blank.

2.

Chapter Two: Literature Review

2.1 Introduction

The literature review considers the ways that authors and designers have approached important aspects such as; achieving a sense of belonging, strategies for achieving affordable housing, and purpose built design techniques applicable to a housing scheme in Wellington.

Not unlike most architecture, the design of housing often comes under scrutiny for the finished result and the following questions often arise; is it thoughtfully designed, is it purpose built, does it reflect the context of its surroundings in terms of history and culture? Perhaps the biggest obstacle faced with the design and implementation of housing for the homeless is related to cost, and the key questions include; is it affordable, is it an effective use of taxpayer dollars? A common misconception is that housing that is well planned, constructed using quality materials with robust and elegant detailing, specific to site, and designed through a collaborative process will add unnecessary cost. While this may be true in terms of an increased cost upfront, it is possible that cost savings overall are achievable by using a considered design process, and the application of innovative construction techniques and programming. Through this process, it is believed that a more efficient, cost effective and successful housing scheme can be achieved.

Four key pieces of literature relevant to NZ housing, and specific international examples of homeless housing have been analysed for the purpose of; 1) understanding the housing needs of the transitionally homeless in Wellington, and 2) establishing a design strategy to implement a housing scheme. The following texts have been selected for their innovative and meaningful grasp on homelessness, and ways in which homelessness can be addressed through alternative thinking and a schematic approach.

- Te Mahana: Ending Homelessness in Wellington – A Strategy for 2014-2020 (Wellington City Council).
- Homes People Can Afford; How to Improve Housing in New Zealand (Bierre).
- Designing for the Homeless; Architecture that Works (Davies).
- Future Social; Design Ideas, Essays and Discussions on Social Housing for the ‘Hardest to House’, School of Architecture, University of British Columbia (University of British Columbia School of Architecture + Landscape Architecture).

2.2 Overview of Selected Literature

2.2.1 Te Mahana: Ending Homelessness in Wellington - A Strategy for 2014 - 2020 (Wellington City Council)

Te Mahana is a strategy devised by a collective group of government agencies and community organisations, as well as people experiencing homelessness in New Zealand. The strategy highlights the important actions and desired outcomes required for a collaborative approach at preventing the occurrence of homelessness in Wellington. Te Mahana translates to English as ‘warmth’ and literally speaks of the warmth found in a supportive home environment. This strategy has been adopted by a number of agencies and organisations in Wellington and aims to: a) Stop homelessness from happening, b) Deal with it quickly when people become homeless and c) Stop people from becoming homeless again. The Te Mahana concept is extremely relevant to research regarding housing for the transitionally homeless, as a sense of belonging is something that every New Zealander should have, yet so many lack. (Wellington City Council *‘Te Mahana’*).

2.2.2 *Homes People Can Afford; How to Improve Housing in New Zealand (Bierre)*

This book investigates New Zealand’s shortage of affordable housing and offers viable and exciting options that could potentially house New Zealanders in homes they can afford. First published in 2013, it was funded by the New Zealand Centre for Sustainable Cities, and Housing and Health Research programme centred at the University of Otago, Wellington.

2.2.3 *Designing for the Homeless; Architecture that Works (Davies)*

Sam Davies is an American architect who has worked mainly with affordable housing schemes in the San Francisco Bay area. Davies has also been involved with the homeless housing movement across the United States. This book acts as a set of guidelines for architects, public policy makers, and housing activists and offers design solutions and recommendations to help solve the housing affordability crisis in the United States. Although homelessness is something with unique causes and issues to each country, there is a lot that can be learnt from Davies’ research and expertise in the area of housing for the homeless. Design can create a sense of belonging for people who may have few social connections.

2.2.4 *Future Social; Design Ideas, Essays and Discussions on Social Housing for the 'Hardest to House' (University of British Columbia School of Architecture + Landscape Architecture 2012).*

Vancouver is a city struggling with the on-going issue of homelessness, and 'Future Social' is a collaborative project of graduate students, and guest experts brought in during a seminar in 2006 seeking to generate innovative design ideas for supportive housing that meaningfully contributes to the problem of homelessness. This is a useful resource as it includes both collaborative research into homelessness as well as the conceptual designs that were developed.

2.3 Analysis of Selected Literature

2.3.1 A Sense of Belonging and the Benefits of Community

Many of Wellington's homeless have been marginalised, challenged with external circumstances leading to a life of homelessness. Housing is a basic human right, and most will agree that all people are entitled to feel physically, emotionally and psychologically secure within a safe environment, knowing their social identity is stable, and can remain so. However, access to adequate housing is not enough on its own, as helping those struggling with homelessness also involves providing easily accessible services to meet the holistic needs of each individual. The fundamental needs of an individual can be summarized effectively by Abraham Maslow's 'Hierarchy of needs' model (see figure 2.01). Maslow's model is a 5-tier pyramid comprising of his motivational theory in psychology of basic human needs. At our most basic level, there is our need for physical survival; this is the first thing that motivates our behaviour. Then there are our physiological needs, and finally self-fulfilment, which is the level we reach when achieving ones full potential. It is this principal that should be aimed for when designing housing for the homeless. This is achievable when adequate housing and social support is readily available, and when one can aspire to follow ones passion as a contributing member of modern society.

"It is quite true that man lives by bread alone — when there is no bread. But what happens to man's desires when there is plenty of bread and when his belly is chronically filled? At once other (and "higher") needs emerge and these, rather than physiological hungers, dominate the organism. And when these in turn are satisfied, again new (and still "higher") needs emerge and so on. This is what we mean by saying that the basic human needs are organized into a hierarchy of relative prepotency" (Maslow 375).

The concept of Te Mahana is one that speaks of the warmth experienced within a supportive home environment and is a concept which closely correlates with the concept of home and the ideas explored by Maslow.

“Home is associated with personal identity, family, relationships, a role in the community, privacy and security, and the possession of personal property. Homelessness or the lack of home affects all these areas of an individual’s life” (Davies 19).

The collaborative approach of the Te Mahana strategy identifies homelessness as being preventable, by reducing poverty and increasing household incomes, as well as increasing the availability of affordable houses for those at most risk. It delves more into the aspect of home or belonging that can only truly be achieved through sensory feeling, it does not just come from receiving access to adequate housing, it is more than just about having a place to live. It is about people living well, having interactive social links and regular access to supportive services.

To be successful, housing for the transitionally homeless should be located close to services and support. In order for housing to be effective, design strategies will need to encourage a sense of belonging and sensory feeling. These ideas are further explored and discussed in chapter five of this thesis; Design Guidelines.

2.3.2 Affordability

Sarah Bierre in ‘Homes People Can Afford’, suggests that the fundamental factors resulting in the apparent increase of homelessness in New Zealand, is the unavailability and unaffordability of quality housing. The private property market, due to more profitable margins at the upper end, has always underprovided quality affordable housing. Population growth has also played a leading role in the shortage of affordable housing. New Zealand house prices spiked significantly between 2002 and 2005 as the population grew predominantly in urban centres. Increasing by roughly 53% (31), this sudden rise in house price had a detrimental effect on first-time homebuyers whilst also having a knock on effect resulting in the increase of rental prices; further decreasing housing affordability for the average New Zealander.

“Recent studies in the US have shown that building supportive housing for the homeless pays for itself through the reduction in services required. Creating buildings does entail costs but it is clear that thoughtful architecture is a major part of the solution.” (University of British Columbia School of Architecture).

It could be thought that the best possible way to achieve affordable housing is to understand the initial cost limitations, and compromise on amenities, sizing, and quality standards from the outset. However, Davies argues in 'Designing for the Homeless', that public housing should be the polar opposite of such a mindset, as "...affordable housing should be indistinguishable from nearby housing so that the residents will not be stigmatised, and will feel like part of the surrounding community" (Davies 43). Based on this research, 'designing down' in terms of quality is not considered a suitable option, but rather exemplary design is explored in this thesis.

New Zealand housing unaffordability is largely attributed to small scale building with labour intensive stick build construction, as well as high cost of compliance requirements by governing bodies. Bierre in 'Homes People can Afford' suggests that one way in which the New Zealand government can respond to this issue, is to develop and promote a move to more modular building scheme. Utilising a variety of standard building components will make assembly on site far less labour intensive and greatly reduce construction cost overall. Using the techniques suggested by Bierre would also allow issues around gaining consent to be greatly reduced as using a more standardised modular building system designed to comply with relevant standards would allow the process to run efficiently. The text also explores ways in which building material supply costs could be reduced if the government used its large buying power to negotiate competitive material cost from suppliers in order to front for an affordable housing strategy for New Zealanders.

Modular building solutions are further explored and discussed later in this thesis.

2.3.3 Purpose-Built Design

Architecture, at its most basic level is the process in which space and shelter are created to accommodate human activity; both form and function. However, when designing for the homeless, arguably the most important consideration for the designer is the question of how to restore a sense of belonging and dignity to the occupants of the housing. 'Future Social' is an examination of how both architects and architecture students alike have approached the challenge of designing both facilities and housing for homeless. The text highlights why purpose designing facilities which are specific to context such as site, history, and culture, is a way in which to create effective housing that people enjoy, facilitating their transition from homelessness to permanent housing.

Current examples of housing for the homeless in New Zealand appear to be lacking in thoughtfulness compared to overseas precedents, which indicates that the approach in New Zealand needs to be addressed (see Chapter 3.0 Precedent Studies). Housing for the homeless should be celebrated architecturally, to encourage a reduction in the stigma surrounding homelessness, and recreate a community that is aware of this issue and can help to resolve it. Housing for the homeless in Wellington needs to meet the needs of the homeless, yet the immediate neighbours and members of the surrounding

community deserve well-designed and attractively built forms that enhance the existing landscape. Davies explains that for the homeless to be able to reintegrate back into the community, external input and buy-in from the surrounding community is essential. This reiterates the fact that any architectural intervention should not compromise the context of the community, or the quality of the built environment.

Examples of housing for the homeless found in New Zealand (and examples of social housing) typically incorporate units significantly smaller than the majority of market housing, presumably because of budgetary constraints. These units are often perceived negatively due to their small size, however this perception is only due to the designs failing to utilise strategies that enhance the uniqueness and attractiveness of smaller spaces. This issue can be addressed by utilising strategies such as planimetric and sectional offsets, and variegated modular systems, which maximise the potential of small home living.

Housing for the homeless should not be restricted to a single typology, as the homeless are not a homogeneous population, with a wide variety and range of people from different cultures and backgrounds experiencing homelessness. Successful housing could be apartments, detached units, or collective dwellings, which could be designed using modular design. Many could view modular design as being too uniform and impersonal, however, by offering a series of adaptable and different unit types, which are designed to suit the profile of the occupants, units would be able to be personalised, and thus enhance the inhabitant's sense of belonging. "The inhabitant must feel, to some degree, that it is their right to take over the space. In other words, the architecture must grant permission to for its over taking." (Davies 44)

“

THE INHABITANT
MUST FEEL, TO
SOME DEGREE,
THAT IT IS THEIR
RIGHT TO TAKE
OVER THE SPACE.

”

DAVIES 44

2.4 Conclusions

Previous examples of homeless design and theories surrounding it can provide great insight and understanding. Applying these principals cohesively with innovative design exploration through this research will encourage the formation of an informed, effective and achievable solution to the housing of Wellington's transitionally homeless.

Key findings from the literature analysis are illustrated in Figure 1.3.

- Modular Design – Efficiency in Construction Time and Cost
- Variety within Uniformity – Easily Personalised Space
- Cross Programming – Well Utilised and Functional Spaces
- Exemplary Design Quality – Elegant Detailing
- Thoughtful Planning – Transitional Spaces
- Energy Efficiency – Natural Lighting and Ventilation

Modular design can potentially offer quality construction and efficiencies in terms of time and cost. It is considered that variety within the uniformity of the modular design will allow occupants to personalise the space, enhancing their sense of belonging. Cross programming (the overlapping of multiple activities or programmes into one space) will create spaces that are well utilised, practical and space efficient. Exemplary design quality will raise self-esteem, whilst elegant and robust detailing will help create housing that enhances the existing built environment. Thoughtful planning will create smooth transitions between private, semi-private and public spaces, blurring the boundaries between internal and external spaces. Housing which is energy efficient, highly insulated with natural lighting and ventilation, can only contribute to the health and wellbeing of the occupants, whilst reducing running costs.

Figure 2.02:
Key findings from Literature Review -
<Authors own>.

2.5 Housing First: Feasibility Study for the Liverpool City Region

This section analyses a Housing First feasibility study for implementation in Liverpool City Region (LCR) conducted by Crisis a charity organisation based in London who care for the homeless. This research was considered for the purpose of; 1) understanding what Housing first is, 2) what they seek to achieve, 3) ways in which this model can be implemented, and 4) to inform detailed guidelines and a design proposal or the implementation of an effective housing facility for the transitionally homeless in urban Wellington.

Tracking the progression of research, which was initially to investigate ways in which purpose-built transitional facilities could assist with the housing of homeless in Wellington. I have since concluded that this model is not the most effective approach. Transitional housing is a model which in recent years been something New Zealand housing providers are moving away from. This was reinforced throughout the interview process, as it was shared view from all organisations I spoke with that; there should be no such thing as transitional housing. People want a place they can call their own, to work through issues at their own pace rather than have a time limit on their transition from dependence to independence. Housing First is a housing model which offers an alternative solution, to make permanent housing the priority and to work through the problems/ issues of the individuals at their own pace.

“Housing First is a system of support for homeless people with high and complex needs which is designed to deliver a sustainable exit from homelessness by helping them to access an independent tenancy as quickly as possible and providing the support they need for as long as they need to sustain this tenancy.” (Housing First 4).

Housing First is an organisation with the intention of ending homelessness. Primarily focussing on providing permanent residency to clients with the most complex issues – moving these people from dependence to independence.

Housing and social support typically comes hand in hand when providing shelter for homeless, however in most cases the transitionally homeless may not need such support. As a result, these people end up in supportive housing purely because of a lack of housing rather than their need for supportive services. Housing First’s default approach is to get homeless into permanent and independent residences as quickly as possible, circumventing requirements of compulsory stays in supportive, temporary facilities. Support is offered if necessary once tenancies are secured, for as long as required depending on the individual needs and requirements.

This Housing First feasibility study was intended to detail and give a sense of how such model might work if implemented in the Liverpool City Region. Based on 7 key principles the study presents a vision of how such model can work from existing evidence and how it could work if implemented in the LCR. These principals are as follows;

- 1) People have a right to a home;
- 2) Flexible support is provided for as long as it is needed;
- 3) Housing and support is separated;
- 4) Individuals have choice and control;
- 5) An active engagement approach is used ;
- 6) The service is based on people's strengths, goals, and aspirations;
- 7) A harm reduction approach is used

I understand and agree with all of these principles apart from number 3; Housing and support should be separated. Bernice Te Ahuru stated during our interview that “we are unbreakable when we stand together as one... housing and supportive services need to go hand in hand”. Te Ahuru, a highly established member of Te Whakamara, is convinced that housing and the support service provided needs to work in collaboration with cohesive buy-in from a range of services such as the Wellington Council, support organisations, as well as the local community. A wrap around assistance framework that provides necessary support and assistance when required on a number of levels from social support to financial advice.

Chapter four in the study outlines types of property to be used for Housing First. This section proved very important as it reinforces how vital it is for housing to be integrated or blended into communities rather than sacrificing design quality in order to reduce build cost. If housing stands out or does not fit the context of its surroundings, then this will in-turn marginalise these people further outside of norms of everyday productive society, this concept also surfaced in both the precedent study and interview process. The interviews suggested that if a housing intervention didn't feel like home then people would simply choose not to live there. The precedent study outlined the existing transitional facilities in Auckland, these were not in any way designed for an individual – rather a blanket solution that is proving to be in-effective at re-establishing independence for the most in need.

“Even if it was just 2 houses here and blend them in with the other houses, so they're not pointing and saying ‘oh that's the estate where the people off the street live’ do you get what I'm saying?” (Housing First 60).

It was established through the Housing First LCR feasibility study that what is required to successfully deploy the Housing First Model is a carefully planned and managed multi-phased approach. In order to achieve such an outcome, it is suggested to come down to detailed implementation and planning emerging from input of a wide collective including; local authorities, select landlords, or those who represent them, people with first hand lived experience and criminal justice professionals. This dialogue of input is used to inform an assistance framework led by a team leader(see figure 2.03 below). Four housing support workers are then initiated to work directly with and support 20 people into permanent tenancy. Facilitating with everything from general well-being to work assistance and training these support workers are to be on call 24/7. This project structure seems to be very well considered in the fact that it provides assistance from project initiation right through to project completion – this in itself is such an important aspect as it is the supportive assistance that we can offer that will truly make the difference between offering ‘Homes’ before housing. Places where people can feel comfortable to be themselves yet supported enough in their transition to independence.

Figure 2.03 (left):
Diagram showing outline of Housing
First Assistance Framework -
<Authors own>.

2.6 Conclusion

In this section I have analysed existing evidence as to how a solution such as the Housing Firsts' model of housing can play a crucial role in resolving the issue of permanent housing for Wellingtons transitionally homeless. The provision of permanent tenancies at an early stage apposed to transitionally or temporary facilities means we bypass having to provide social support for people who simply may not require it. In some cases, all it may take to get these people back on their feet is a permanent place to call home. Although Housing First aims are focussed at clients with high and complex needs such as the chronically homeless, implementation of similar strategies I predict that this will have a great effect on the housing of transitionally homeless and their journey to independence. By providing an effective assistance framework alongside the housing process will allow a smoother transition into permanent tenancies. It was suggested throughout the interview process that there is an excess of help and assistance already in place, with a large amount of volunteer staff ready and willing to help, there is no reason for which an effective an affordable system cannot be developed. This framework is explored further throughout this research.

“

BY PUTTING
SOMEONE WHERE
THEY FEEL SAFE &
SECURE ALLOWS
THEM TO ADDRESS
THEIR OTHER
ISSUES.

”

HOLLAND

3.

Chapter Three: Interview Process

3.1 Process

The desired outcome of this research is to propose a housing concept that is both practical and realistic. In order to achieve this existing statistics and information regarding homelessness in Wellington needs to be absorbed. It is vital respond to the knowledge and insights of the people that work directly with the homeless population. It was unrealistic to reach out and talk to the homeless population directly, as this would only be accessing a small percentage of a very large and diverse population and the time limitations of this research would not allow for this. It therefore seemed much more beneficial for to approach housing providers in Wellington, and organisations that work directly with homeless as their experience, outreach and resources extend far beyond what could be achieved through this thesis alone.

The initial steps taken were to select and analyse organisations or housing providers that were thought to be best suited to support research into the re-housing of Wellington's homeless (see appendix 02). Six organisations were contacted for the purposes of conducting interviews in order to find out general information regarding homelessness and housing in Wellington, and the involvement of each organisation;

- The Wellington Night Shelter
- The Wellington Homeless Women's Trust
- The Salvation Army – Transitional Housing
- Dwell Housing Trust
- The Compassion Soup Kitchen
- Te Whakamura Ai Te Ahi (Kahungunu Whanau Services)

However due to unavailability, limited resources or individual representatives not believing that their organisation would be of any assistance, only two organisations opted to be interviewed; Bernice Te Ahuru a representative from Te Whakamura Ai Te Ahi, and Kahungunu Whanau Services, and Karen Holland who currently manages the Compassion Soup Kitchen.

3.1.1 *Te Whakamura Ai Te Ahi*

Bernice Te Ahuru is the team leader of Te Whakamura Ai Te Ahi and is also a representative of the Kuhungunu Whanau Services. At the Downtown Community Ministry office she talked about her experience working with homeless in Wellington, and her thoughts around housing. Ali Hamlin-Paenga (CEO of Ngati Kahungunu ki Poneke Community Services) also sit in for this interview. Both representatives have proven backgrounds in the protection and rehabilitation of homeless and offered valuable knowledge and advice. A key point of discussion arose surrounding the current definitions of homelessness in New Zealand, and the fact that homelessness cannot easily, or simply be categorised because of the complex issues and circumstances experienced by each individual. This led into discussions that a time based housing strategy was not considered not be beneficial as every resident is unique and may require more (or less) time dependant on their individual circumstances. “There should be no such thing as transitional housing... Housing First’s model is one way to approach (homelessness), it is not the only way” (Te Ahuru)

Bernice Te Ahuru stated that; “It is not about the house, it is the unique issues that need addressing” which highlights the importance of a wraparound service that could work cohesively with a housing scheme in Wellington. The provision of adequate housing and resources, for some people will allow them to build the skills and knowledge in order for them to make their own decisions in terms of housing, when they are ready, and on their own terms.

“

THERE SHOULD BE
NO SUCH THING AS
TRANSITIONAL
HOUSING . . .

”

TE AHURU

3.1.2 *Compassion Soup Kitchen*

For this interview; A conversation was held with Karen Holland and Matt Petrie; Manager of the Compassion Soup Kitchen, and Purposeful Activity Project Leader, respectively. Much of the discussed content correlated closely with that of the Te Whakamura interview. Firstly, the theme of 'home' was one that reoccurred, that without a sense of purpose or belonging, it is hard to call somewhere home. "Some (homeless) may have shelter, but not a 'home'" (Holland).

Reintroduced was the idea that a 'Transition' period of housing will not give most effective result as yes, some residents may require six months, yet others may require six years. However, by providing somewhere that is suitable for whatever amount of time is required will allows individuals to work through their problems and make decisions which are best for them "By putting someone where they feel safe and secure enables them to address their other issues" (Holland)

One topic that correlated strongly with the theme of this research was that of quality. Both Karen and Matt shared the understanding that, for any intervention, there could be no substitution for quality design. This goes for both materiality and for the design itself "Housing has to be quality, it has to be safe, has to be warm, and it has to have clear aims on whom the housing would benefit and who it would not" (Holland).

“

SOME (HOMELESS)
MAY HAVE SHELTER,
BUT NOT A 'HOME'.

HOLLAND

”

3.2 Conclusions

Information obtained through the interviews was both relevant and insightful, providing a strong direction for which the design process which followed.

Initially this research proposed a housing scheme following the model of ‘Transitional Housing’, which has already been adopted in some cases in New Zealand. However, following the interviews, it was concluded that this model should not be followed due to the problems with current ‘Transitional housing’ model. The fact that transitional housing forces the homeless population into a single box, rather than recognising the diverse needs of this population. It was suggested that there should be no fixed time-period on a housing solution, as no two cases are ever the same. Instead a very different approach is needed – one that responds to the needs, and wants of the diverse population of homeless in Wellington. A housing implementation that is close to local amenities and services yet also provides wrap around social support in order for the most effective re-integration of homeless into permanent housing.

The interview process proved extremely beneficial in the early stages of this research, where the idea of homeless housing was beginning to appear unachievable for all of its complexities. However, after gaining insight from passionate people proved to be a vital step as it informed more holistic and applicable research.

Key findings from the interview process are illustrated in figure 3.03 (see opposite).

- Sense of Belonging – ‘Home’ before housing
- Wraparound Process – Coordinated support system
- Collaborative Approach – Community, Local Authority, Police, Health Care etc.
- Careful Siting – Well connected to services and amenities
- Quality of design – Exemplary design quality

Creating and enhancing an individual’s sense of belonging is considered to be of high importance, and therefore any design should seek to create a homely and welcoming environment. Careful siting is another high priority, as it is important for inhabitants to be located close to services and amenities. A collaborative approach is considered to be essential. To have the support of the local community, local authority, police and other agencies is invaluable, thus providing a coordinated wraparound support system. The importance of design quality should not be underestimated, as the place that a person inhabits can shape a person, thus affecting the way that they perceive themselves, and enhancing (or damaging) their levels of self-respect.

Figure 3.03:
Key findings from Interview Process -
<Authors own>.

Chapter Four: Precedent Study

4.1 Introduction

The analysis of the precedents considers strategies for achieving affordable housing and purpose built design techniques applicable to a housing scheme in Wellington.

Homelessness is an international issue and although certain countries can claim comparatively lower rates of homelessness, it is a matter that appears to exist in regions all across the globe (Institute of Global Homelessness). The Human Settlement Programme initiated by the United Nations estimates that 1.1 billion people live in inadequate housing, and although it is a statistic difficult to gauge research suggests that more than 100 million people worldwide have no housing at all (United Nations).

The purpose of transitional housings is to provide a temporary yet suitable place of residence allowing residents to develop the skills necessary to become independent and return to productive society (Holtschneider). Although transitional housing is a relatively new concept in terms of the New Zealand's housing continuum, it is by no means a new concept internationally. This is reflected through New Zealand's examples of transitional housing in particular on Luke Street, Otahuhu, Auckland, and Henderson, Auckland. Unfortunately, when analysed compared to examples such as the 'Transition Centre', France or 'Vendepunktet', Denmark, the New Zealand examples appear deficient, illustrating a lack of quality design and purpose-built function.

Four precedent studies have been analysed for the purpose of understanding the housing needs of the transitionally homeless, and establishing a design strategy to implement a housing scheme. Two national and two international precedents were selected for the different approaches taken, these are:

- Luke Street Transitional Housing Development, Otahuhu, Auckland
- Henderson Transitional Housing Units, West Auckland
- Jagtvej 69 'Vendepunktet', Copenhagen, Denmark
- Transition Centre Apartments, Rambouillet, France

4.2 Analysis of Selected Precedents

4.2.1 *Luke Street Transitional Housing Development, Otahuhu, Auckland*

The Luke Street transitional housing development is New Zealand's first purpose-built emergency housing model, constructed under the Government's \$303.6 million emergency housing fund announced by Hon Amy Adams Minister of Social Housing in 2016 (Adams). As part of the 2016 budget, \$41.1 million was allocated to provide approximately 3000 houses over a four-year period in contract partnerships with selected emergency housing providers (Ministry of Social Development). Construction was completed on the Luke Street development in early 2017; 27 two-bedroom, 7 three-bedroom, and 17 four-bedroom transitional homes were built on site, "...warm and dry and as good quality as any permanent home" (Housing New Zealand 1). The houses are intended to accommodate families for around 12 to 14 weeks or until permanent accommodation is secured. Whilst living on site, families receive social support from three organisations contracted through the Ministry of Social Development; Monte Cecilia, the Salvation Army, and Vision West.

The Luke Street development demonstrates a copy and paste style layout rather than a purpose built transitional housing facility - each typology of housing whether it be 2, or 4 bedroom is an almost exact replica of the building adjacent, minus a coloured section above the building's entrance. This construction method referred to by the now former Minister of Social Housing, and Associate Minister of Housing Paula Bennett as, "fast 'stick build'", building proves to be beneficial as of the quick turn around in construction times the homes can be built at a relatively cost effective rate. Whilst this method may prove beneficial in terms of overall cost and construction time, there is minimal attention paid to establishing a sense of belonging through architectural design. The overall site layout focuses more on these design considerations as there is a clear separation of public and private zoning. The addition of recreational green spaces and landscaping contributes to this affect and creates a pleasant and safe feeling environment, important for a transitional housing facility.

Figure 4.01 (left):
Example of transitional housing at
Luke Street, Otahuhu, Auckland.

4.2.2 Henderson Transitional Housing Units, West Auckland

One of the New Zealand Governments latest solutions to the housing crisis was the introduction of transportable housing units in Henderson, West Auckland (see fig 4.02). Nine 28m², one-bedroom housing units suitable for single occupiers have been built on a land package leased from the Ministry of Education on Great North Road with construction deemed to be finished by mid-February 2018. These completely self-contained units come fully insulated, double glazed and fitted with carpet – complete with a kitchen, bathroom and furnishings each unit is warm, dry and perfectly functional. In common with the housing development on Luke Street, residents of the Henderson project will receive a range of supportive services from the contracted provider Vision West. It is expected that residents will be housed in the units for up to 12 weeks unless circumstances arise requiring them to stay longer until permanent housing is found.

Surrounding residents of the Henderson area interviewed by Stuff NZ representatives have described the units as ugly, christening them ‘prison cells’ or ‘slave units’ (Fairfax Media Ltd.). The unit design itself reflects no consideration to user or surrounding environment. The context of site and the tenuous circumstances of the users has been overshadowed by the New Zealand Governments chosen hierarchy of time and cost over design and functional purpose-built typologies. There is little information on offer regarding the design and thought process behind the single unit concepts however architectural renders of the site show the transitional units which appear to have only one window and one door laid out on site in a geometric order. Apart from the surrounding landscape of trees and planting it does indeed look somewhat of prison style accommodation.

Figure 4.02 (right):
Example of “Prison Cell” transitional
housing, Henderson, West Auckland.

4.2.3 Jagtvej 69 ‘Vendepunktet’, Copenhagen, Denmark

Jagtvej 69 - Vendepunktet is a privately funded housing scheme merging temporary homeless accommodation and urban gardens in the heart of Copenhagen, Denmark. The project design commissioned to WE Architecture, Erik Juul, and UBA Studio was initiated in 2017 and is currently in concept phase with an on-going status (WE Architecture).

The name ‘Vendepunktet’ translates as; ‘the turning point’, and in this case means exactly that, a temporary and purpose-built residence for the homeless people of Copenhagen aiding their transition back into productive society. A major design contribution for the Vendepunktet building was to have a positive visual contribution for the surrounding neighbourhoods around the Jagtvej 69 area. By providing a visual statement or landmark of architecture within a community the design group intends that this will raise awareness of homelessness and the issues surrounding it theoretically attracting people to the area for both residency and volunteering (Rinaldi 2017). Confronted with the spatial limitations of an urban land package, the building expresses a seamless integration of trees and planting with modular design in order to maximise land use. Both horizontal and vertical axis have been engaged, either with modular units or urban gardens. This effective design feature allows privacy for individual dwellings when manipulated correctly however enhance social interaction with peers. Figure 4.03 (left) shows the configuration of the housing scheme and ways in which units have been extruded to create an intricate interior space and effective zoning of private and public spaces.

Figure 4.03 (left):
Artistic impression of WE Architecture Housing Scheme - Jagtvej 69 ‘Vendepunktet’.

4.2.4 Transition Centre Apartments, Rambouillet, France

The Transition Centre designed by Benjamin Fluery (see fig 4.04) functions as a relay house accompanying the reintegration of vulnerable and isolated homeless during their return to normal social life and participation in effective society. The \$ 3.2 million (NZ) building consists of 19 apartments with studio units, multi-bedroom rooms, independent emergency rooms, and an individual residence for an on-site social worker. Effective site layout results with the set-square building design utilising solar. Orientation of dwelling rooms are predominantly south facing ensuring that they maximum exposure to light, having a positive therapeutic effect on residents (ArchDaily). The north façade houses the bathrooms, landings and technical rooms used for social services etc. The landings are an innovative solution subtly promoting social connection and interaction of residents as they are encouraged using architectural design technique to network with fellow users.

The positioning of the building on the site allows the central garden area to be framed as the centre of the facility and a private space to be enjoyed by resident's (archello). The central garden and recreational area is an essential part of the Transition Centre as it creates a collective activity for residents to be able to be part of and contribute towards. Fruit and vegetables harvested on site are shared amongst all living on site and members of the neighbourhood to enhance social inclusion with outside the outside community.

The Transition Centre, designed to address homelessness in France, is a leading example of purpose built transitional housing; attention to detail and design consideration for homeless goes far beyond examples found in New Zealand. Fluery was successful with his stance on purpose built transitional housing; the project displays a pinnacle of homeless housing and defines considerations and techniques vital to establishing effective transitional housing in any part of the world. Additionally, the project also boasts an advanced approach to sustainable design, labelled 'Housing and Environment profile A' because of buildings strength in terms of solar power use, over 50% of the energy used within the project is generated using photovoltaic systems greatly reducing the environmental footprint of the complex. "Bioclimatic and environmental responsibilities are placed upon residents to invigorate a sense of community and give them a role to maintain and return to social life" (Singhal).

Figure 4.04 (right):
Transition Centre Apartments
Rambouillet, France.

4.3 Conclusions

New Zealand would appear to have a lack of effective purpose built transitional housing. Examples illustrate a lack of architectural design presence, and little reflection of site, history and culture. The precedent studies highlight many issues and flaws with existing examples of housing for the homeless in New Zealand, whose emphasis would appear to be directed towards quantity of housing built and construction cost. However, international examples express many positive features, which will be important to consider in the design of a housing scheme in urban Wellington.

Key findings from the analysis of precedent studies are illustrated in figure 4.05 (see opposite);

- Highlight Homelessness – Exemplary Design
- Encourage Social Interaction – Engage the Community
- Personalise Space – Encourage a Sense of Identity
- Thoughtful Siting – Clearly Defined Public/Private Spaces
- Respond to the Environment – Orientation and Site Specifics

Instead of hiding the issue of homelessness, it is considered important to highlight the issue through exemplary architectural design. Quality design and the strategic location of housing will raise awareness within society and encourage community support. The integration of recreational areas such as planting, green spaces and exercise areas with built environment beneficial to social interaction. Community gardens allow residents to feel pride in work whilst encouraging a communal activity. Consideration of pedestrian flow is important for any urban site, especially for demographics of residents as being able to afford a vehicle may not be an immediate priority. Spaces which can be personalised, by individuals or families are important for establishing a sense of personal identity. Thoughtful siting and the positioning of the building footprint is important in clearly communicating boundaries between public and private space. This allows residents to feel safe and comfortable in their own space, yet they are not removed from society. Having a mix of communal and private areas encourages social interaction, yet allows residents to have personal space. Environmental factors such as renewable energy usage, orientation of building on site, solar gain, and views are important to consider. All contribute to lowering the environmental impact of the building, whilst also improving and enhancing the quality of living conditions.

Figure 4.05:
Key findings from Precedent Analysis
- <Authors own>.

4.4 Self-build Case Study

To gain an enhanced understanding of effective homeless housing precedents this research had to extend beyond the means of existing examples of homeless housing, and into various methods of how different approaches of affordable design and construction methods have been achieved. This is what led to the development of a Self-Build model. Self-build is a concept in which the client resumes responsibility for some (or all, in some cases) of the construction process, thus resulting in a reduced overall build cost as paid labour is replaced with the clients own. This example has the potential to prove effective in terms of housing the transitionally homeless population; as for what they may lack in economical means, they have an abundance of time and possess the willingness and drive to achieve permanent housing in a comfortable and self-driven housing project.

Self-build construction caters for those who may not be able to afford housing on the current open market. By clients managing the building work internally construction and overall buildings costs are driven down. New Zealanders pride themselves on 'Kiwi Ingenuity' and have subsequently adopted a 'Do it yourself' attitude towards building. DIY is a common pastime, and to take part in the crafting or building of their own 'Home' is something held in high regard for many Kiwi's. The idea of self-build housing is an appealing model as it fits within this philosophy. Although building is currently restricted by governing bodies and local authority in terms of building regulations and codes, if the acceptable solutions were somewhat simplified for the average New Zealander it could then allow for the self-build or DIY mindset to flourish - in turn allowing many more people to achieve an affordable housing solution that is crafted for, and built by one's self.

Two further precedent studies have been analysed for the purpose of understanding techniques of supplying affordable housing through a self-build construction model. This will strengthen an understanding of affordable housing techniques and will contribute towards establishing a design strategy for the implementation of a housing facility for the transitionally homeless population of Wellington.

Two European examples were selected for their innovative approaches to self-build design and because both examples could potentially be effective in New Zealand, these are:

- Extension House Neukolln, Berlin, Germany
- R50 Apartments, Berlin, Germany

The analysis of these precedents considers strategies for achieving affordable housing, and self-build design techniques applicable to a housing scheme in Wellington.

This page intentionally left blank.

4.4.1 *Extension House Neukolln, Berlin, Germany*

The Extension House designed by Praeger Richter Architects is a 24-unit apartment block that aims to deliver spatially generous living spaces at cost comparable rates to social housing. They achieve this by offering a range of apartment types from ‘standard’ apartments to ‘takeover shells’ for self development which results in the property, depending on skill, and economical means of the clients can be achieved relatively cheap, also completely unique to the individual.

By having the apartment floor plans completely exempt from the structural shell of the building allows there to be broad freedom with the interior fit outs. Clients therefore have free reign over the spatial manipulation of the floor plan without having to worry about complying to building standards or governing requirements.

This particular model is able to provide a one-bedroom sized apartment for \$344.21 per square metre (approx.), including set plumbing and electrical connections, and some internal partition walls. In comparison to the cost of building in New Zealand which is around \$2-2500 per square metre (considered the economical or standard level of carpentry) this is dramatically lower (Building Guide “*A Budget Breakdown*” 2). Although this figure does include standard labour costs, if this is removed then account for client contribution costs to the Extension House apartment figure it would still appear to be comparatively cheaper. This low cost is achievable by the initial steps taken by the project developer – the building envelope is built with all the necessary infrastructure and interfaces: including structural requirements, electrical, plumbing, and circulation. Clients are then able to enter the property inexpensively with the opportunity for future developments and improvements as they see fit. The initial construction stages undertaken by the developer to provide the building shell can be simple and standardised allowing for a high level of prefabrication and modularity which resulted in the planning and construction time being reduced by about 12 months when compared to similar apartment projects in Europe. The freedom of design and ability of expansion for clients results in a completely unique and personalised space essentially influenced by the resident’s style, space requirements and construction ability. The development offers a basic structure that can basically taken over by the resident, providing a completely unique and personalisable space at a fraction of the cost of standard residential building rates.

Figure 4.05 (right):
Extension House, Berlin, Germany -
Shell completion.

Figure 4.06 (right):
Extension House, Berlin, Germany -
Inhabited Apartment.

4.4.2 R50 Apartments, Berlin, Germany

R50 Apartments designed by Heide & Von Beckerath is a joint building venture consisting of 6 floors of either mix use activities or apartment spaces. Built in compliance to minimum design standards the building was designed to meet the ambitions or requirements of the owners to live in both collective yet affordable housing. Project developers aimed to provide a robust, yet modest structure with carefully designed details and connections to ensure that the project had a simplified construction style.

Apartment layouts are dictated by extensive participation and self directed design of the individual users, however a common standard of fixtures and fittings were developed in collaboration with the building venture to establish a theme or certain aesthetic that would be maintained throughout the project without limiting unique design expression of the residents. Design collaboration and mutual agreement directs programming of shared areas such as roof terrace and community spaces. R50 offers a simplified model of self build housing, it ensures that the spaces can be utilised and essentially built with unskilled labour which in turns allows the residents to establish themselves in an affordable and purpose built housing.

Figure 4.07 (left):
R50 Apartments, Berlin, Germany.

4.5 Conclusions

For many in New Zealand, the concept of building a new home seems unachievable, and currently to those experiencing a level of homelessness it can be. However, these self-build precedents discussed earlier outline potential ways and design considerations for which affordable ways of housing can be achieved, utilising both innovative design planning and construction strategies as well as catering for the 'DIY' mindset.

Offering a simplified yet bare building shell with the basic infrastructure completed is an effective solution to affordable housing if the residents are ready and willing to drive their own housing project. The transitionally homeless population could potentially benefit significantly by a Self-Build model; as found through this research; although they lack the economical means to secure permanent housing, they possess the time and motivation to secure a 'home'. A fully personalised and self-built apartment will possess the features of such – Establishing a sense of belonging back into the residents, as they will have the freedom to craft and build at their own leisure depending on their financial and physical ability. By having collective input for communal areas such as gardens and rooftop terraces encourages social interaction and a sense of pride in establishing a quality and most of all, affordable place to reside.

This page intentionally left blank.

Chapter Five: Design Guidelines

5.1 Process

Outlined in this chapter is a thoughtfully considered set of holistic guidelines, together with design ideas as to how the guidelines could be implemented in a successful housing scheme.

Literature review, analysis of both national and international precedents and an the interview process has ostensibly defined a broad range of strategies and guidelines that will be the foundations of this project; paying respect to the difficulties involved when designing for the homeless as well as responding to the natural environment with passive design strategies.

DESIGN GUIDELINES.

5.2 Design Brief

The design guidelines have been carefully considered and refined in order to establish a design brief that can be reflected upon throughout the design process. The design brief is as follows;

Client Responsive – Flexible & Adaptable

Housing for the transitionally homeless needs to be able to adapt according to the individual needs of each resident and the social conventions relevant to such housing. The building form and functional purpose needs to be able to change, catering for the changes or differences of the occupier over time. The importance of spatial flexibility is key in allowing a building to adapt and perform appropriately for the needs of its residents.

Environmentally Responsive

Passive design strategies will be employed wherever possible in order to minimise the need for auxiliary mechanical heating, cooling and ventilation techniques. A balanced interior microclimate will be achieved through a collaboration of design construction and material selection in order to provide a sealed building envelope that ensures year-round user comfort.

Low Energy

A proposal of more traditional cooling/heating, and lighting methods will be identified in order to reduce the overall building energy consumption. Adversely it is through artificial means of such that are the primary causes of higher energy usage within any building environment. Again passive design strategies contribute to the lowering of energy use such as natural ventilation, and opportunities to utilise solar gain and natural light. Ideally the design will see a greatly reduced reliance on artificial methods and a return to more traditional and natural design approaches.

Site Responsive

Waste Minimising

Material selection and construction methods are essential elements of this project; decisions regarding both are essential in maintaining an efficient and intelligent design scheme. Thought has to be given to waste created not just on-site but also in material production. The selection of materials will recognise this issue and respond accordingly, selecting (where possible) only those that are most recyclable and renewable. The longevity of design is also considered, it is thought that the design outcome will reflect permanence on site, as well as being easily disassembled and transportable to other locations.

Water Preserving

Water management, both recycling and harvesting are important considerations in this project. It is therefore proposed that water usage will be reduced by at least 50% of the average New Zealand domestic household. Regulated through rainwater collection and purification, as well as greywater recycling the housing proposal will promote water efficiency.

5.3 Conclusions

These guidelines form the starting point for the design explorations in this thesis, and are considered to be a good guide to what housing for the homeless in New Zealand should ideally look like (based on the findings from this particular research).

DEVELOPER/
CHARITY
ORGANISATION

Chapter Six: Design Iterations

6.1 Process

This chapter outlines the order in which the design experimentation phase was carried out, and the details of each. The structure of this section follows the timeline of design iterations undertaken.

Design iteration I outlines a proposal of single, nuclear home's as detached dwellings; focussing on simplified construction techniques and the configuration of small spaces to suite a range of occupants.

Design iteration II forms the basis for how this thesis is configured. This stage investigates a universal design response to housing urban Wellington; a self-build apartment framework aimed at establishing a sense of belonging, or home environment whilst offering a place of permanent residence.

DESIGN ITERATION I: Small Detached House

This experimentation section details a conceptual framework for individual 'home' units. The following typologies have been developed with principles of prefabrication, modular assembly, and environmental response in mind, as well as consideration for transportation and logistics of materials and components.

6.2 Design Summary

Whenever the conversation of 'Home' is discussed one can automatically refers their personal interpretation of what this is; singular detached dwelling with a combination of private/ public space and access to recreational outdoor space, surrounded by family or friends is common conception of NZ housing. This is not the case for every New Zealander, however this research sought to challenge how this feeling of 'Home' could be replicated or enhanced through innovative design.

The issue faced with current housing solutions for the most marginalised or in need, is that there appears to be a lack of purpose-built or affordable options for those seeking permanent shelter in Wellington. 'Transitional' facilities offer shelter; yes, yet the temporality associated with it does not allow people to feel at home. An aspect reinforced through the interview process was that if people do not feel comfortable with provided housing, it is simply not effective in such a vital of transition from dependence to independence. Proposed through design iteration I is a way to simplify the construction process in order to utilise unskilled labour. It seeks to can give people the skills and aid to be able to assist with the build process. Thus, creating a sense a purpose for clients, as they are participating in creating their own space as well as lowering construction and labour cost with the reduction of on-site build time and the amount of skilled labour required.

This proposal suggests intimate communities of housing with the basic elements of domestic living alongside supporting activities of collective living and social interaction with adjacent society. Clusters of detached houses forming communities where communication and interaction become the main structure for the supporting process and transition from dependence to independence.

6.3 Massing & Modular Studies

As a modular and standardised notion of building was identified through the preliminary research as the way forward, it is key to identify and explore a framework for which this concept can be implemented in the context of urban Wellington. As a whole, Wellington boasts huge diversity in terms of its topography and landscape – where it is common to see sites with intricate contouring and existing natural landscapes.

6.3.1 *Massing Study*

The first exercise; a building mass study, ignores site, scale, and building form in order to develop a principle of design that addresses the complexity of urban wellington sites. Focussing predominantly on zoning and massing on site as this is has been identified earlier as such an important part of housing for the most in need; principals of such have been explored throughout. This four series study of; random, scattered, cluster, and restrictive zoning, implements principals and insights from the literature review and cases studies.

i. Cluster Zoning

Image (i) displays an indicative example of how cluster zoning may be configured. An interior communal zone or perimeter is framed by the outer housing units which, in-tern creates a combination of private and semi-private spaces. This is an important feature as it is crucial that residents have private space that they can call their own whilst having space for engaged interaction is vital to re-establishing themselves as productive members of society.

ii. Private Zoning

Iteration (ii) shows a way in which private zoning can be achieved. Although a large open private courtyard is formed at the centre, this layout segregates itself from the public realm. Transitionally homeless are largely everyday people experiencing extreme financial hardship – to marginalises them away from the norms of society would not be effective. A more collaborative approach is needed where residents and the community are engaged on equal terms.

iii. Random Zoning

Image (iii) shows a way in which housing units can be set-out in a random configuration. This example creates a good combination of private/ public zones yet still frames a communal 'cluster'. Each unit is separated from the next which allows for access to outdoor space. Pedestrian flow is restricted however as there is no formal axis of site, this may be confusing to someone not familiar with the site.

iv. Scattered Zoning

Iteration (iv) is an example of scattered zoning which allows every unit to be fully detached and set-out in a formal grid. I feel this example is too repetitive and is hinting towards existing examples of New Zealand transitional housing which this research campaigns against. If every unit looks like the one next to it there is no feeling of individuality. Instead examples of variety need to be seen, exemplary design quality that allows people to be proud to call their house a home.

i.

ii.

iii.

iv.

This exercise showed how iterations may and may not work effectively while incorporating features such as pedestrian flow, public/private zoning, and the integration of public green space. This was an important exercise for me to conduct in order to begin any sort of housing design, as factors like that previously mentioned need to be considered through all stages of the design process.

6.3.2 *Modular Study*

At an early stage of this project it was helpful to begin experimenting with modular forms in order to gain an understanding of the unique spaces and zones created through manipulation of horizontal and vertical components. Still with no reference of site specifics or location this exercise focuses on the interaction of units and the relationships formed as a result.

The following four step timeline - influenced by principles from the literature review and precedent analysis shows an adaptive framework in which a site may be approached with the implementation of a modular housing intervention.

i. Step one shows the acquisition of site and the planning in response to site conditions such as site boundaries, set-backs, and existing trees or infrastructure. Identification of public and private zones which will be designed for accordingly.

ii. Step two introduces the manipulation of building form. With consideration of site conditions and user programme the vertical axis is extruded to form the building response.

iii. Engaging with the horizontal axis, step three defines the building footprint to the specifications and requirements of user.

iv. Step four initiates the removal of modules in order to define unique spaces throughout the extrapolation. This technique introduces private spaces for individual units.

This exercise helped in the process of defining how interactions are formed between units and how relationships begin to form with overlapping and extrusion of modules. To further a base knowledge of this aspect and to give reference to the unique topography faced when building in Wellington contours were introduced in the modelling stage. This helped to see how modular design reacts to differing landscapes.

i.

ii.

iii.

iv.

6.4 Design, Construction & Occupancy Management

Occupancy Management

The transitionally homeless make up an overwhelming 80% of New Zealand's homeless population (The peoples project). This body of homeless are typically not drug addicts, they are not alcoholics, largely dominated by families these are everyday people experiencing extreme financial hardship making it virtually impossible to secure permanent housing. For most categorised as 'Transitionally Homeless' this is often their first encounter with social services, and in most cases all it takes is a helping hand to get back on their feet.

As there is no homogeneous profile of people that fit into this category, an effective housing response will need to respond to, and be successful at permanently housing a wide range of occupant profiles. Throughout this design stage three typologies of housing units have been developed in accordance to a range of design responses; a small, medium, and large unit. Accommodating everyone from single occupants, shared living situations, to large families. The following design principles have been analysed and considered throughout the first design iteration.

Prefabrication & Modularisation

A modular approach to the design and construction is proposed for the structural and architectural elements of this project. This will allow and necessitate a close collaboration with contractors, structural and building service engineers, as well as material and component supply manufacturers. The proposed concept employs modern methods of prefabrication and modularisation in order to reduce the reliance on specialist labour; thus providing employment opportunities for people with a lower skills base. Standardised units and modules are employed throughout the design - minimising waste and allowing for cross construction discipline integration. This modular construction method enables a speedier construction process; saving time, and therefore financial/ resource burden. The entire frame and structural configuration is assembled using a modular conformation, this allows for the units to be demounted from their foundation consequently preserving the terrain. The dismantled components can be transported to an alternative site for reconstruction and an extended lifetime.

Building Form

The environmental and climatic responsiveness of the building are strong contributors to the form and design configuration. Rectangular plans orientate in such a way to minimise over exposure to low angle sun. Extruded eaves allow for the provision of shade to the lateral ends of the building, and protection from solar radiation exposure of the interior spaces. Fully adaptable, open plan interior spaces

allow for flexibility and personalisation of space, as well as incorporation of cross ventilation as the higher roof volumes remain un-obstructed to ensure a healthy and well ventilated interior air quality. Deep patio spaces allow for an extension of the building envelope whilst remaining covered and protected from external conditions. This ensures privacy of external space and utilises space demanded by the configuration of the portal frames. Elevating the building from the ground creates a sectional offset allowing for maximum airflow through building footprint. Minimal ground penetrations safeguard the future development of site and the surrounding landscape allowing for changing demands and use of the land. The building form itself articulates a similarity to New Zealand Vernacular of 'home' by adopting the apex roof aesthetic yet moving away from ordinary building techniques and materials to offer an innovative change/ possible alternative to affordable modular housing in New Zealand that could benefit the housing of many facing homelessness.

Outdoor Space

A series of covered deck areas are consistent features implemented in all typologies. These are effective ways in which integration of outdoor landscape and interior spaces can be achieved. Sheltered from prevailing wind, rain, and sun exposure these 'in-between' spaces offer ambient conditions that deem to extend the building form when utilised correctly. This is an important feature of New Zealand design as cohesion of indoor and outdoor space is a fundamental aspect of our housing ideology.

Transportation & Logistics

To achieve a practical and affordable building system for transitional housing thought needs to attribute to how building materials and components will be sourced, how they will be distributed and transported to various sites around Wellington, and potentially further if designed housing model proves beneficial to the homeless population. The proposed modular housing design will be, in most part prefabricated off site. Thus allowing a more straightforward and less time intensive site build. To further reduce cost due to transport and distribution of materials I have research how the standardised building components can be disassembled and flat- packed in order to fit on the back of a single truck to minimise on road costs and minimise the carbon impact involved with transporting building materials.

6.5 Physical Modelling

6.5.1 Initial Modelling

6.5.2 Massing Models

S.

SMALL SIZE HOUSING.

M.

MEDIUM SIZE HOUSING.

L.

LARGE SIZE HOUSING.

6.5.3 Programme Development

S.

SMALL SIZE HOUSING.

The smallest size housing unit (45 m2) depicts a dramatic reduction of overall size when compared to the average household size in New Zealand. Although small in size, this house design encompasses all the basic necessities and spatial requirements for a comfortable living space. With the structural configuration protruding outside of the building footprint this allows for private outdoor areas which when opened up boasts a much larger entertainment and outdoor living area giving an impression of greater spatial generosity. Embracing an open plan internal layout

implementation of sectional offset determines boundaries between areas. With a +400mm change in floor level from living to bedroom space this creates a physical separation allowing privacy to be established between the bedroom and living areas. An adaptable bedroom space allows for bed size of up to queen making this unit perfect for a single occupant or couple who are looking to down size. Utilising a number of environmentally efficient systems this concept includes a water recycling plan relies on solar energy harvesting for water heating purposes.

- 01. Covered outdoor living area
- 02. Lounge/ Living
- 03. Dining
- 04. Kitchen
- 05. Bedroom +450mm Finished floor level
- 06. Hallway +450mm Finished floor level
- 07. Bathroom
- 08. Main Entrance/ Covered patio
- 09. Services room - Grey and rainwater recycling

M.

MEDIUM SIZE HOUSING.

With the additional of an extra bedroom, the medium sized units is suitable for single occupancy however can house up to 4 full time residents making it compatible for a small family. The large kitchen and living space can also be adapted to suit a temporary sleeping arrangement if additional space was required for guests. With a gross floor area of 55 m². This design option allows for a greater expansion of space and a better separation of private/ shared interior spaces.

An expansive private deck extends from the master bedroom to the living area. This allows for an extension of the

interior living space and privacy from surrounding buildings while experiencing a comfortable outdoor environment.

- 01. Services Room - Grey & Rainwater recycling
- 02. Covered outdoor living area
- 03. Bathroom
- 04. Master Bedroom +300mm finished floor level
- 05. Hallway +450mm finished floor level
- 06. Bedroom 2 +300mm finished floor level
- 07. Main Entrance
- 08. Kitchen/ Dining
- 09. Lounge/ Living

LARGE SIZE HOUSING.

The largest of the three housing typologies asserts a floor area of 75 m². With an adaptable secondary lounge space that is also suitable to be an additional bedroom fitting two single beds or up to one standard queen bed. Ideal for a larger family of up to 4-5 occupants however also suitable for couple or smaller family looking for a bit more

space. Utilising a similar lounge/ living space as the medium unit this can again be adapted to suit guests staying or can be used as an office/ study space.

- 01. Private deck area
- 02. Master bedroom
- 03. Additional storage
- 04. Bathroom
- 05. Bedroom 2/ Office - private lounge +300mm finished floor level
- 06. Hallway +450mm finished floor level
- 07. Services room - Grey & rainwater recycling
- 08. Main Entrance
- 09. Kitchen/ Dining
- 10. Covered outdoor living area
- 11. Living Area
- 12. Lounge

6.7 Energy Efficiency, Green Innovation, & Environmental Quality

Rainwater Harvesting

For all domestic water use purposes, rain water is to be targeted as the primary source - except for that used in the kitchen. This feature is aimed at reducing the use of potable water for the majority of household activities, where recycled grey water should instead be used. Rainwater captured from the apex roof planes will be channelled into storage tanks to be passed through microbiological filtration system then used for domestic purposes such as shower, toilet flushing etc.

Greywater Collection and Recycling

Grey water refers to the water that has been previously used in functions regarding everyday use. I aim to recycle atleast 50% of 'grey water' used from hand basins and showers. The recycled will be passed through a filtration system and stored in a spare tank to be used for irrigation purposes, or washing of home or vehicles etc. This strategy will minimise potable water wastage for activities not requiring such.

Building Orientation & Natural Light

A passive design approach will be taken at every point available to ensure energy efficiency and minimise unrequired energy consumption. Thoughtful building orientation and eave placement will ideally minimise the need for mechanical building services such as; heating/ cooling and ventilation. These factors provide unnecessary running costs that can be reduced by careful and attentive design strategies. A narrow building footprint allows for deeper penetration of natural light and reduces reliance on artificial lighting and heating and its associated running costs.

Natural Ventilation

With the nature of the designed typologies all being of an open plan and simple layout allows for greater control of interior air quality and methods of ventilation. As the structural elements are strictly generated from the exterior shell alone, this allows for free reign over design of interior spaces. As such, any interior walls are only partitions between space which can all be slid back to reveal an open interior layout. This allows for the implemented strategy of cross ventilation. Manual openings at the buildings lateral ends in correlation to prevailing winds ensures that fresh, clean air is readily available yearlong. This enhancement of airflow and the opportunity to regulate it will result in occupiers to have a much more quality and enjoyable interior space – with both optimal air quality and temperature.

Thermal Performance

The simplicity of these housing concepts is what makes them unique – an example of how such a design scheme, catering for the transitionally homeless can be achieved. To adhere with this concept, Structural Insulated Panels (SIPS) were investigated for the buildings thermal envelope. SIPs are said to significantly outperform traditional construction when it comes to maintaining constant interior temperatures, and perceived level of living comfort. US studies have confirmed that SIP's construction is far superior when compared to conventional buildings systems based on heat loss data (Formance 18).

Solar Energy

By installing solar modules as part of the design intent home owners are able to capture some of the abundant energy. Roof panels incorporating photovoltaic cell technology will be incorporated in order to utilise the sun as a natural energy source. The output of which dependant on size, orientation, and sun exposure will determine energy consumption and how reliance on power grid as a main energy provider can be reduced.

6.8 Conclusions

In order to pay homage to the expression, rather the ‘feeling’ of Home this concept encapsulates an interpretation of what home can look like. The simple apex style room encapsulates and celebrates this notion. Examples of permanence were imperative throughout this experimentation phase. Although an affordable solution is required there was to be no sacrifice in design quality. The design outcome controlled cost by emphasizing a low maintenance material palette and simplified construction techniques. Made almost entirely from timber the structural component’s such as large spanning portal frames and SIPs panels ensure the structural rigidity which allow complete interior freedom to be customised by the individual occupants, the generous interior space allows for typical arrangements of generic furniture.

Careful consideration of the structural configuration allows the installation of windows and glazing to cover almost any surface. Cross ventilation, and utilising natural daylighting achieves a comfortable and healthy interior environment. Storage is contained in the open ceiling space between the portal frame rafters. This is achievable by incorporation of portal frames and utilising the full height roof space. Sectional offset repeated through both the floor and roof plans allow for separation of internal space with the need for physical partition walls, maintaining an open plan and adaptable internal floor plan.

Physical modelling of the three sized concepts helped to fully establish and understand the spatial requirements required for the transitionally homeless. The developed house concepts challenge the average house size currently in New Zealand; instead offering a small, yet fully operable home environment.

After carefully considering this design option; a concept which does offer, with some conviction a model in which quality and affordable homes can be constructed and readily supplied for the transitionally homeless. However, in the context of urban Wellington where land is expensive and large sites are simply not present this option does not seem as economically viable. This prompts the need for a higher density housing solution entailing principles and learning outcomes from design iteration I in order to achieve an effective housing scheme solution for application in Wellington.

DESIGN ITERATION II: Self-Build Apartment Housing

6.9 Design Summary

Existing housing typologies catering for the transitionally homeless marginalise residents out on the city fringes. This answer does not offer any advantages in the search for employment or even social interaction. This research proposes that bringing a housing model into the heart of Wellington's urban centre; close to amenities, community services and employment opportunities will be the best way to help those who are hardest to home.

This design experimentation seeks to define a simplistic method of self-build apartment construction so transitionally homeless of low-skill can craft their own quality homes at an affordable rate. Expanding on design outcomes from 'Design Iteration I' principles of prefabrication, modular assembly, unit sizing and environmental responses are developed further in 'Design Iteration II'. Surfacing from the first iteration was the issue of density. Single detached dwellings not being a viable option in a central area such as Wellington for a large scale intervention. This issue of building density is addressed more in-depth in this section to develop a more economically viable housing option in an urban Wellington context.

This chapter was comprehensively developed to establish; 1) an urban Wellington site which would be suitable for implementation of a self-build apartment. This will be done taking into consideration aspects such as size of site and local proximity, 2) a conceptual design response to the selected site including a form development study and an initial outline of the construction framework necessary to complete a housing development as such.

Figure 6.03 (right):
Site image - Frederick Street existing building <Authors own>.

Figure 6.04 (below):
Site Model and Surrounding Buildings. <Authors own>.

6.10 Site

6.10.1 Site Selection

Transitionally Homeless are everyday people experiencing extreme financial hardship making it difficult or sometimes impossible to secure permanent residency. Often too proud to seek help or 'beg' for money, they would rather sleep in their cars or on a friends couch than in the CBD. This is one of the greatest challenges when devising a strategy to address the housing of the transitionally homeless. As for these people the best solution to secure work opportunities and have adequate access to social services is for them to reside close to the city centre and its amenities.

133 Taranaki Street is commercial property currently laying vacant on a prime piece of land in the Wellington Central Building District. This site holds the potential to change the way in which the general public perceive 'homelessness' in general. By implementing a housing scheme right in the middle of town on a busy street such as Taranaki we would thrust the conversation of Homelessness to the forefront of modern society, thus engaging with and encouraging community participation in the journey back to independence. With a well designed and executed housing scheme for 133 Taranaki Street steps can be taken to resolve the issue of homelessness altogether, the central location means the residents are close to food stores, healthcare facilities, social services and employment opportunities not marginalised from society housed on the fringes of our communities.

133 Taranaki Site appears to be the most appropriate site. It would give transitionally homeless the best chance at getting back on their feet and a chance of re-establishing themselves as productive members of society whilst, revitalising a central Wellington site currently lying baron and unused.

FREDERICK STREET

133

Figure 6.05 (left):
Site image - 133 Taranaki Street
footpath <Authors own>

Figure 6.06 (below):
Site image - Frederick Street
footpath <Authors own>

SITE.

133 Taranaki Street
Te Aro
Wellington

- Location of food providers - grocery stores, New World, Countdown etc.
- Location of educational facilities - Schools, tertiary institutes and childcare etc.
- ✕ Locations of healthcare facilities and social service providers such as Ministry of Social Development, Work and income, and the Wellington Hospital.

6.13 Site Context & Planning Aspects

○ 135 - 145 TARANAKI STREET Residential Building 7 Storey.	○ 172 TARANAKI STREET commercial + Residential Building 11 Storey.	○ 166 TARANAKI STREET Commercial Building 2 Storey.
○ 150 - 152 TARANAKI STREET Residential Building Backpacker / Hostel 4 Storey.	○ 123 TARANAKI STREET Residential Building 7 Storey.	○ 57 -79 VIVIAN STREET Commercial Building 3 Storey.

6.14 Design Coherence

This section outlines design considerations relevant to building within the central urban area building zone in Wellington. Advised by the Wellington District Plan (Wellington City Council “*Central Area Urban Design Guide*” 10-15).

i. Siting, Height, Bulk, & Form

Building placement should pay reference to neighbouring buildings. This design will reinforce reoccurring patterns of public space in surrounding area and also create positive open spaces. Siting should not restrict intended activity of site. Access to recreation area at rear of the site ensures residents have communal space away from the public.

ii. Setbacks & Edge Treatment

Building alignment and edge definition mimics surrounding buildings and reinforces local street grids. The setback from Taranaki street conforms with the limited setback scope whilst allowing the building to have a softer image with the addition of planting as the building is approached.

iii. Positive Open Space

Placement on-site achieves a good ratio of building to publicly accessible open space. Active edges surrounding the site and adjacent walking routes are all readily accessible with clear visibility. Location of recreation area at the rear off site ensures optimal levels of sun exposure and shading during necessary times. This outdoor space maintains a high level of natural surveillance ensuring security and comfort of users.

i.

ii.

iii.

6.15 Environmental Response

i. Daylighting

Positioned laterally on site West-East the footprint has been placed to maximise solar gain. Utilising the morning and evening sun. The elongated floor plan allows for a greater sun penetration into the building interior. This deeper reach of natural light and heat allows for a more comfortable year long interior environment.

i.

ii. Natural Ventilation

Utilising the prevailing southerly winds that are a common feature of Wellington; Taranaki Street in particular. Operable windows and vents at the buildings ends allow for incorporation of natural ventilation. This supply and movement of air results in an interior zone with a greater air quality. Building position also mitigates wind exposure to the shared space at the rear of the site.

ii.

iii. Building Ventilation

Building orientation plays a large role in the environmental effectiveness of the proposed apartment building. Intending to minimise the reliance on mechanical services for heating/cooling. All responses have been considered to reduce the overall environmental footprint of the housing scheme.

iii.

iv. Solar/ Water Harvesting

An important aspect of this design is its consideration for energy efficiency and green innovation. Incorporated in this design are a number of passive solutions to lower energy consumption in terms of water use. Making use of the large surface area of the roof terrace rainwater is harvested, reducing the use of potable water for household activities. Recycled grey water will be used for domestic purposes such as flushing toilets etc.

iv.

v. Public/ Private Realm

Access to private outdoor space is a key aspect of this design. This gives a far greater sense of out door space and a 'home' when combined semi-private recreational spaces. Private balconies are incorporated for residents to have space of their own away from others.

v.

vi. Response to Site

Establishment of a public thoroughfare as part of the site development enhances user walkability for residents as well as pedestrians. By freeing up the use of the first floor allows a greater range of use whilst also encouraging pedestrian thoroughfare to pass through rather than going around the site. An increased first story height

vi.

6.16 Form Development

<i>i.</i>	Four small size apartments linear arrangement. Individual access.	<i>ii.</i>	Three medium size modules linear arrangement. Individual access.	<i>iii.</i>	Two large size apartment modules linear arrangement. Central access way.	<i>iv.</i>	Small, medium, large combination linear arrangement. Individual access.
<i>v.</i>	Four small size apartments linear arrangement. Central access way.	<i>vi.</i>	Three medium size modules linear arrangement. Central access. Two adjoining units.	<i>vii.</i>	Two large size apartment modules. Units adjoining with edge access.	<i>viii.</i>	Combination units size with central access separating large unit.
<i>ix.</i>	Four small size units parallel arrangement. Central access running length of floor.	<i>x.</i>	Three medium size modules linear arrangement. Central access. Two adjoining units.	<i>xi.</i>	Two large size apartment modules. Units adjoining with edge access.	<i>xii.</i>	Combination units size with central access separating small unit.
<i>xiii.</i>	Four small size apartments parallel arrangement. Access running length of floor along edge.	<i>xiv.</i>	Three medium size modules linear arrangement. Edge access running width of floor.	<i>xv.</i>	Two medium units with central access. Private space at each edge running width of floor.	<i>xvi.</i>	Small and medium unit adjacent with central access separating large unit.
<i>xvii.</i>	Four small size apartments parallel arrangement. Access running length of floor along edge.	<i>xviii.</i>	Two medium units. Perpendicular arrangement allowing private zoning of each unit.	<i>xix.</i>	Three medium size modules linear arrangement. Edge access running width of floor.	<i>xx.</i>	Small and medium unit adjacent with central access separating large unit.

<i>i.</i>	Two small units one large. Each separated with individual corridor.	<i>ii.</i>	Linear arrangement; Small, medium, small units. Separated by two access routes.	<i>iii.</i>	Four apartment units scatter arrangement. Each unit separated with individual access.	<i>iv.</i>	Small and large apartment unit separated by central access way. Each with own private space on edge.
<i>v.</i>	One medium unit arranged three small apartments. One way access to all four spaces.	<i>vi.</i>	Combination units size with central access separating small unit.	<i>vii.</i>	Two large size apartment modules. Units adjoining with edge access.	<i>viii.</i>	Combination units size with central access separating large unit.
<i>ix.</i>	Four small size units parallel arrangement. Central access running length of floor.	<i>x.</i>	Combination units size with central access separating large unit.	<i>xi.</i>	One small and one medium unit. Perpendicular arrangement allowing private zoning of each.	<i>xii.</i>	Small, large, small units. Central access way separating one small unit.
<i>xiii.</i>	One large and two small units. Stand alone units with individual access.	<i>xiv.</i>	Combination units size with central access separating small unit.	<i>xv.</i>	Three small units. Stacked allowing private space for two units. Shared access.	<i>xvi.</i>	Two large units separated by central access way.
<i>xvii.</i>	Combination arrangement of stand alone units. Shared space between large and medium units.	<i>xviii.</i>	Small, medium, large combination linear arrangement Individual access.	<i>xix.</i>	Three small units with shared communal space.	<i>xx.</i>	Two large units. Alternate arrangement allowing large private zones for each unit.

i. **Circulation**

Core and vertical circulation located in centre of building for access and ease of services/ maintenance.

ii. **Unit Position**

All units positioned ensuring that maximum day lighting and natural light exposure for each.

iii. **Private Zoning**

All units to have individual outdoor balcony or deck area. Improving indoor/ outdoor flow and ventilation. As well as a more pleasurable space to occupy.

i. Small Apartment Unit.

ii. Medium Apartment Unit.

iii. Large Apartment Unit.

6.17 Construction Process

i.

ii.

iii.

i. **Acquire Land Package.**

Optimal site to be identified and selected based upon proximity to local amenities, site conditions and local building restrictions etc. Building location and placement on site to be determined once land package acquired in response to site features.

ii. **Groundworks & Foundations.**

All basic groundworks and infrastructure to be completed at this stage. Including but not limited to connection to water, and service/ utilities etc.

iii. **Precast Shear Wall & Core Elements.**

Precast Shear walls to be delivered and erected on site minimising construction time. These sections to be completed with reinforced connections at each point; floor by floor.

iv.

v.

vi.

***iv.* Structural Columns & Floor System.**

Precast columns for ground floor to be installed. Ground floor to act as the base for the remaining floors. Vertical forces exerted onto the building to be run down through column structure and dispersed through the buildings foundations.

***v.* Extrusion of Core Structural Elements.**

Precast shear walls and central core elements to be extended floor by floor until maximum height reached. This is the first step in each level before establishing post & beam structure.

***vi.* Apartment Floor Construction.**

Each floor from here on to be replicated from the previous. Resulting in a complete structural layout consisting one base level on ground level and four apartment levels above.

6.18 Concept

i.

ii.

iii.

i. **Self-Build Components**

Simple component selection to be designed enabling residents to build and design building interiors with ease.

ii. **Component Selection**

Clients choose what items to build and design interior according to individual preference and requirements

iii. **Output Configuration**

Result is a fully bespoke and self-built home that transitionally homeless can call their own.

S.

SMALL APARTMENT UNIT.

M.

MEDIUM APARTMENT UNIT.

LARGE APARTMENT UNIT.

Figure 6.07 (above):
Potential DIY self-build instruction
manuals <Authors own>.

6.19 Conclusions

‘Home’ should be a place where one has the freedom of choice to manipulate and design accordingly to individuals needs or preference; a place where you are free to be yourself and place to call your own. This thesis strives to prove that this feeling, or notion of ‘home’ can be achieved through self-build design, it is a fundamental aspect of this research and one which will be explored further through chapter 7 ‘Detailed Design’.

There were a number of key learnings from ‘Design Iteration II’ which will be addressed and developed further in the following chapters. Firstly, it became apparent that it may not be necessary to design and develop everything for the apartment interiors. A large component selection was proposed including wall panels, floor sections as well as kitchen components. Essentially this is a proposal of bespoke designed furniture which, for the most part cannot compete cost comparatively to ‘IKEA’ style flat pack furniture. Since affordability is an essential feature of this research though will need to be attributed to what exactly needs to be designed so that residents can build themselves, and what will need to be supplied. Secondly, simplicity is an element that cannot be overstated more. In the first proposal the large selection of components could be refined down to a selection of essential components that will be easily built by residents on site. This means that elements such as the curve corner pieces may have to be removed as these will add unnecessary cost and be more time demanding to construct. The way in which the remaining components will be designed will cohere with standard dimensions and techniques ensuring they are easy to assemble, and can be done so using materials sourced from your local hardware stores such as Mitre10 and Bunnings Warehouse etc. Finally, there needs to be a clear distinction of what the residents will build and what will be left up to the developer and professional contractors. For instance, wet areas such as bathrooms and kitchens require skilled professionals to install and also need inspections to ensure compliance. Areas as such will be developed prior to the resident occupying the apartments.

Figure 7.01 (above):
Artistic Impression of complete
building - <Authors own>.

Chapter Seven: Detailed Design Proposal for Self-Build Apartment Housing

This chapter details the final design proposal for a self-build apartment housing scheme for implementation in Wellington. The suggested outcome affirms the potential for self-build housing aimed at providing affordable and quality *'homes'* for Wellington's transitionally homeless.

7.1 Design Summary

The proposed design outcome of this research offers a novel approach to housing in Wellington city. The self-build design enables the user to be able to craft their own dream home using a viraity of unique design tools and decisions within an inner city apartment complex. The pre-consented apartment shells come ready to be transformed into a range of outcomes suiting those in need of a small studio loft or a larger family home. The apartment range have been creatively designed to establish a quality yet permanent housing solution at an affordable cost through utilisation of New Zealander's DIY DNA.

The architecturally designed apartment contains 12 individual units in a range of sizes. Simplified construction methods allow the user to fully personalise the interior spaces. The individual units come pre-consented and are readily equipped with a broad range of features and fixed services that will enable a faster transition into permanent tenancy, whilst giving residents the satisfaction of crafting their own bespoke home. Located amidst an urban environment the selected sites used for this housing intervention are close to local amenities' giving residents the full experience and ease of inner city living.

7.2 System Framework

This research proposes a multi-staged project timeline for the implementation of a self-build housing scheme in Wellington city. The framework has been developed after consideration of findings from all research bodies with thought also attributed to the most plausible and economical means of construction.

The project framework consists of 4 key stages with differing inputs and outputs at each stage. The overall project is to be initiated by a developer (charity or non-profit organisation such as Housing NZ or the Salvation Army Housing etc.), from here, an operation or administration team will be appointed to oversee the entire project from conception to completion. This team will offer support and guidance to residents at various points throughout the building completion to ensure a smooth transition into permanent tenancy.

The project framework is as follows;

Pre-construction – Planning & Land Acquisition

This preliminary stage involves everything involved with site selection and acquisition. To be run by project administration, Developer funded and run.

01. Stage One: Structural Shell

The first stage to be completed is the structural shell. This will be overseen by the project administration however work to be outsourced to skilled, professional contractors. Work comprising of infrastructure, foundations, building core & circulation, and all structural components. Primary structure comprises of precast shear wall and concrete post & beam design. Hollow core floor slab system substrate with polished concrete screed. All elements where possible to be pre-fabricated off site to minimise construction time and cost.

02. Stage Two: Façade & Thermal Envelope

Stage two oversees the establishing of the building thermal envelope. Selected cladding systems and building substrates installed by professional contractors. Selection and location of glazing, as well as placement of balcony and sun shading as per client specification.

03. Stage Three: Services & Fixed Utilities

Stage three sees the input of wet area modules and installation of underpinning walls. Kitchen and bathroom areas to be fully established in compliance with NZBC and local authority regulations. For ease of access and installation, all services fixtures are directly fixed to building core and corresponding risers. Work to be carried out by professional contractors with client input on selection of fixtures etc.

04. Stage Four: Interior Fit-out

Building is essentially complete at Stage four. Clients can occupy selected pre-consented apartments. Structural and services components have been carried out. Interior fit-out is left up to the resident. Addition of furniture and/or partition walls to be completed by residents as required.

INPUT HIERARCHY

DEVELOPER LED:

Initial stages of construction. Predominantly developer led as skilled labour and professional contractors required to undertake majority of work at this stage.

COLLABORATION:

Stages Two and Three require input from client and potential residents. Although still overseen by the administrative team clients begin to decide on fixtures, positioning of glazing etc.

CLIENT LED:

Construction essentially complete and building ready to be inhabited. Input transfers entirely into the hands of the resident. Developer has no further say in the building output.

04.
STAGE FOUR :
FITOUT

03.
STAGE THREE :
SERVICES + FIXED
UTILITIES

02.
STAGE TWO :
FACADE / THERMAL
ENVELOPE

01.
STAGE ONE :
STRUCTURAL SHELL

OWNERSHIP MODEL

Permanent housing - yet not economically viable in this case. Would only be available to those who can afford market price property; Many Transitionally homeless would not.

Would not resolve issue of permanent housing; Renting is affiliated with time. Will always feel 'temporary'. Tenants without regular incomes would struggle with scheduled payments.

Achieves value of 'Home' through permanent housing. Building Re-instated for next resident once lease ends.

CONSTRUCTION PROCESS

04.

03.

02.

01.

01. **Stage One:** Structural Shell

02. **Stage Two:** Facade + Thermal Envelope

03. **Stage Three:** Services & Fixed Utilities

04. **Stage Four:** Interior Fit-out

7.3 Stage One: Structural Shell Completion

01.

Figure 7.03 (above):
Interior perspective render - Stage
One 'Structural Shell Completion' -
<Authors own>.

Figure 7.04 (above):
Interior perspective render - Stage
One 'Structural Shell Completion' -
<Authors own>.

Figure 7.05 (above):
Interior perspective render - Stage
One 'Structural Shell Completion' -
<Authors own>.

Figure 7.06 (right):
Interior perspective render - Stage
One 'Structural Shell Completion' -
<Authors own>.

7.4 Stage Two: Facade & Building Envelope

02.

Figure 7.07:
Perspective render - Stage Two
'Facade and Thermal Envelope'
West Elevation - <Authors own>

i.

ii.

i. Facade Exemplar One

ii. Facade Exemplar Two

iii.

iv.

iii. Facade Exemplar Three

iv. Facade Exemplar Four

BEAM TO BALCONY CONNECTION
THERMAL BRIDGE DETAIL

DETAIL 1: Selected detail section showing beam to balcony connection using thermal bridging device embedded into concrete facade.

- 01. Floor Screed (polished)
- 02. Hollow Core Floor System
- 03. Hollow Core Fixing Bracket
- 04. Precast Beam
- 05. Precast Beam Housing Notch
- 06. Precast Structural Shear Wall
- 07. Waterproofing Membrane
- 08. Cladding Fixing
- 09. Elastic Seal
- 10. Acoustic Ceiling Insulation
- 11. Lightweight Concrete Facade Panel
- 12. Bitumen Coated Insulation

CONCRETE FACADE SYSTEM THERMAL ENVELOPE DETAIL

DETAIL 2: Selected detail section showing connection between reinforced concrete shear wall and precast concrete facade system. Also shear wall notch where primary beam is secured in place.

- 01. Lightweight Concrete Facade Panel
- 02. Cladding Fixing
- 03. Timber Flooring (Ext.)
- 04. Thermal Bridging System
- 05. Elastic Seal
- 06. Bitumen Coated Insulation
- 07. Waterproofing Membrane
- 08. Precast Column
- 09. Timber Framed Wall (Int.)
- 10. Concrete Screed (Polished Surface)
- 11. Hollow Core Flooring System
- 12. Acoustic Ceiling Insulation
- 13. Precast Beam

Figure 7.08:
Perspective render - Stage Two
'Facade and Thermal Envelope'
East Elevation - <Authors own>

Figure 7.09:
Perspective render - Stage Two
'Facade and Thermal Envelope'
North Elevation - <Authors own>.

7.5 Stage Three: Intertenant Configuration + Services & Fixed Utilities

03.

Figure 7.10:
Interior perspective render - Stage
Three 'Intertency Configuration'
Small Unit - <Authors own>

KITCHEN & BATHROOM MODULES

i.

ii.

i. Bathroom Module

To ensure compliance with local authority building consents and standards a bathroom module will be established prior to resident occupation. Waterproofing inspections may then be carried out for each apartment.

ii. Kitchen Module

To ensure compliance with local authority building consents and standards a kitchen module will be established prior to resident occupation. Waterproofing inspections may then be carried out for each apartment.

INTERTENANCY SEPARATION

NOTE: Two Way FRR – Double Timber Frame with Central Barrier.
Intertenancy walls between adjacent flats are required to be 120/120/120 fire rated and have a minimum acoustic performance of 55 STC.

<p>i. Double Layer Plasterboard</p> <p>10mm Standard plasterboard, fasteners at 300mm centres around perimeter of sheet. Adhesive at 300mm centres to field of sheet.</p>	<p>ii. Insulation</p> <p>(90mm) glass wool insulation minimum R-value of 2.2</p>	<p>iii. Timber Frame</p> <p>90*45mm radial SG8 H1.2 framing timber. Top and bottom plate with studs spaced @600mm centres. Dwang spacing as required.</p>
<p>i. Central Barrier</p> <p>INTEGRA lightweight concrete panel or similar product fixed with proprietary bracket attached from the core panel to framing.</p>		

7.6 Stage Four: Interior Fit-out

04.

Figure 7.11:
Interior perspective render - Stage
Three 'Intertency Configuration'
Medium Unit - <Authors own>.

INTERIOR
COMPONENTS

NOTE: Two Way FRR – Double Timber Frame with Central Barrier.
Intertenancy walls between adjacent flats are required to be 120/120/120 fire rated and have a minimum acoustic performance of 55 STC.

<i>i.</i> Peg Board Wall Components.	<i>ii.</i> Vertical Slatted Timber Partition Components.	<i>iii.</i> Standard Plasterboard or Plywood Lined Wall Components.
<i>iv.</i> Peg Components - Dowel timber cut to required length.	<i>v.</i> Timber Flooring Components.	

FURNISHING

Interior Furnishing

Interior furnishings are to be included at users preference/ expense in order to create an optimal interior space.

600MM WALL
COMPONENTS

<i>i.</i>	600mm * 2700mm 10mm Standard plasterboard lining.	<i>ii.</i>	600mm * 2700mm Timber Slatted wall panel.	<i>iii.</i>	600mm * 2700mm Peg board panel.	<i>iv.</i>	600mm * 2700 opaque poly- carbonate wall panel.
<i>v.</i>	600mm * 2400mm 10mm Standard plasterboard lining.	<i>vi.</i>	600mm * 2400mm Timber Slatted wall panel.	<i>vii.</i>	600mm * 2400mm Peg board wall panel.	<i>viii.</i>	600mm * 2400 opaque poly- carbonate wall panel.

**1200MM WALL
COMPONENTS**

<i>i.</i>	1200mm' 2700mm 10mm Standard plasterboard lining.	<i>ii.</i>	1200mm ' 2700mm Timber Slatted wall panel.	<i>iii.</i>	1200mm '2700mm Peg board panel.	<i>iv.</i>	00mm' 2700 opaque poly- carbonate wall panel.
<i>v.</i>	1200mm' 2400mm 10mm Standard plasterboard lining.	<i>vi.</i>	1200mm ' 2400mm Timber Slatted wall panel.	<i>vii.</i>	1200mm '2400mm Peg board wall panel.	<i>viii.</i>	1200mm' 2400 opaque polycarbonate wall panel.

2400MM WALL
CONSTRUCTION

i.

ii.

i. 1200' 2400mm Frame

90'45mm radial SG8 H12 framing timber. 1200mm top and bottom plate with 3 studs cut at 2310mm spaced @600mm centres. No dwangs required.

ii. 600' 2400mm Frame

90'45mm radial SG8 H12 framing timber. 600mm top and bottom plate with 2 studs cut at 2310mm. No dwangs required.

**2700MM WALL
CONSTRUCTION**

i.

ii.

i. **1200' 2700mm Frame**

90'45mm radial SG8 H1.2 framing timber. 1200mm top and bottom plate with 3 studs cut at 2610mm. Dwang spacing as required.

ii. **600' 2700mm Frame**

90'45mm radial SG8 H1.2 framing timber. 600mm top and bottom plate with 2 studs cut at 2610mm spaced @600mm centres. Dwang spacing as required.

WALL LINING

i.

ii.

i. **600* 2400mm Frame (Lined)**

Refer to (ii) for framing details - 10mm Gypsum plasterboard direct fixed both sides according to manufacturer specifications.

ii. **1200* 2400mm Frame (Lined)**

Refer to (i) for framing details - 10mm Gypsum plasterboard direct fixed both sides according to manufacturer specifications.

**TIMBER SLATTED
PANEL**

i.

ii.

i. **1200* 2400mm Timber Slatted Partition Frame**

90*45mm radial SG8 H1.2 framing timber. 1200mm top and bottom plate. 100mm spacing of 80*25mm timber studs cut at 2310mm.No dwangs required.

ii. **1200* 2700mm Ply Finish**

90*45mm radial SG8 H1.2 framing timber. 1200mm top and bottom plate with 3 studs cut at 2310mm spaced @600mm centres. Dwang spacing as required. Plywood direct fixed to frame.

WALL LINING (FIXING DETAIL)

-
- 01. Construction Grade Adhesive
 - 02. Fixing Screw
 - 03. Selected Wall Lining
 - 04. 100mm Galvanised Nail
 - 05. 150mm Fixing Pattern
 - 06. Selected Wall Lining
 - 07. Timber Frame

**WALL LINING
(PEG-BOARD SYSTEM)**

<p>i. Dowel Pegs</p> <p>Dowel pegs cut in preference to use type. i.e long for desk - shirt for hook etc.</p>	<p>ii. Visual Grade Plywood</p> <p>Nominal thickness visual grade plywood sheet with holes for peg installation. 40mm Dia.</p>	<p>iii. Cavity Batten</p> <p>25' 40mm vertical cavity battens</p>
<p>iv. Plasterboard</p> <p>10mm standard gypsum plasterboard GIB or similar product.</p>	<p>v. Timber Frame</p> <p>90'45mm radial SG8 H1.2 framing timber. 1200mm top and bottom plate with 3 studs cut at 2310mm spaced @600mm centres. No dwangs required.</p>

FLOORING INSTALLATION
CONSTRUCTION & FIXING

-
- 01. Selected Flooring Substrate
 - 02. Screw Fixings
 - 03. Adhesive Along Fixing Pattern
 - 04. 140* 50mm Timber Bearers
 - 05. 100mm Galvanised Nail

WALL COMPONENT INSTALLATION
TOP PLATE CONNECTION

DETAIL 3: Wall fixing to ceiling. Wall insert into profiled steel channel system fixed to hollow core floor slab. 20mm tolerance above top plate allowing for miscalculation. Timber Coving installed once panel is fixed in place.

- 01. Concrete Screed (Polished)
- 02. Hollow Core Flooring System
- 03. Screw Bracket Fixing
- 04. Profiled Steel Track
- 05. Counter-sunk Screw
- 06. Jolt Head Nail
- 07. Selected Wall Insulation
- 08. Selected Wall Lining
- 09. 20mm Tolerance for Insert
- 10. 20mm Timber Coving
- 11. Timber Framed Wall

WALL COMPONENT INSTALLATION **BOTTOM PLATE CONNECTION**

DETAIL 4: Wall fixing to floor. Wall insert into profiled steel channel system fixed to hollow core floor slab. Timber skirting installed once wall panel is fixed in place.

- 01. Selected Wall Lining
- 02. Selected Wall Insulation
- 03. Jolt Head Nail
- 04. Counter-suck Screw
- 05. 20mm Timber Packing
- 06. Concrete Screed (polished)
- 07. Hollow Core Flooring System
- 08. Timber Framed Wall
- 09. 20mm Timber Skirting
- 10. Profiled Steel Track
- 11. Screw Bracket Fixing

Figure 7.12:
Interior perspective render - Stage
Three 'Intertency Configuration'
Small studio unit - <Authors own>.

Figure 7.13:
Interior perspective render - Stage
Three 'Intertency Configuration'
Medium studio unit - <Authors own>.

Figure 7.14:
Interior perspective render - Stage
Three 'Intertency Configuration'
Small studio unit - <Authors own>.

Figure 7.15:
Interior perspective render - Stage
Three 'Intertency Configuration'
Medium studio unit - <Authors own>.

Figure 7.16:
Interior perspective render - Stage
Three 'Intertency Configuration'
Medium studio unit - <Authors own>.

Figure 7.17:
Interior perspective render - Stage
Three 'Intertency Configuration'
Large studio unit - <Authors own>.

Figure 7.18:
Interior perspective render - Stage
Three 'Intertency Configuration'
Large studio unit - <Authors own>.

Figure 7.19:
Interior perspective render - Stage
Three 'Intertency Configuration'
Small studio unit - <Authors own>.

7.7 Building Configuration

This section outlines the complete building configuration for the proposal on 133 Taranaki. Firstly the building use of each floor is described. Secondly, a site plan has been developed taking into consideration neighbouring buildings, outdoor areas and parking requirements for the proposed site. Thirdly, a series of concept floor plans have been developed to show how a finished apartment may be configured to suit a diverse range of residents.

Floor Layout (see opposite)

i. Ground Floor

Communal floor. Semi-open to public. Contains; entrance, lobby, workshop (resident use), meeting rooms (resident use) and access to shared outdoor area.

ii. Levels 1 - 4: Apartment Floors

Residential floors. Each level contains three apartments; One small, medium and large unit. The interior configuration and fit-out is TBC by owner.

iii. Level 5: Rooftop Terrace

Shared rooftop terrace. Greenspace for outdoor recreation. Accessible via central building core. Level 5 green roof and open area for resident relaxation.

iii.

ii.

i.

Siteplan.

- 01. Meeting Room
- 02. Corridor - W.C Access
- 03. W.C
- 04. External Covered Thoroughfare
- 05. Staircase
- 06. Elevator
- 07. Core Access
- 08. Building Services Room
- 09. Electrical Plant Room
- 10. Pedestrian Access (Taranaki St.)
- 11. Main Building Entrance
- 12. Communal Lounge/ Lobby
- 13. Shared Building Workshop
- 14. Entrance/Exit
- 15. Pedestrian Access (Frederick St.)
- 16. Entrance/Exit
- 17. Vehicular Loading Bay
- 18. Courtyard - Seating Area
- 19. Bicycle Parking
- 20. Shared Greenspace
- 21. Vehicular Access
- 22. Parking Space
- 23. Disabled Parking Space
- 24. Vehicular Site Access
- 25. 57 - 79 Vivian Street
- 26. 123 Taranaki Street
- 27. 135-145 Taranaki Street
- 28. Existing Buildings

Floorplan.

The floorplan pictured here (see figure 1.1) displays how the proposed apartments would look at the beginning of stage 04 'Interior Fitout'. Three apartments have been created on each of the four floors; a small **45m²**, a medium **55m²**, and a larger **75m²** space. All major contract works such as structural, electrical and services work has been completed and the apartments have been council consented ready for inhabitation.

An apartment at this point is essentially a blank canvas ready for the clients to take over and turn the empty space into somewhere they can call home.

There is no set time frame on construction at this period. If occupants like the open 'loft' style of the apartments they simply do not have to incorporate any additional features. However, if residents require extra rooms or would like partition walls between spaces they have the choice, and options to do so. Using principles and strategies developed in this research they can easily build components in the shared building workshop and install in their homes at their own leisure and expense.

Example apartment configurations have been developed further in this chapter to show how space can be developed to suit a range of occupancy requirements.

- 01. Adaptable space
- 02. Kitchen Module
- 03. Bathroom Module
- 04. Entrance
- 05. Stairwell
- 06. Elevator
- 07. Vertical Circulation
- 08. Building Services/ Elc.
- 09. Services Riser

S.

SMALL APARTMENT UNIT.

M.

MEDIUM APARTMENT UNIT.

LARGE APARTMENT UNIT.

- 01. Lounge/ Living
- 02. Office/ Study
- 03. Master Bedroom
- 04. Bathroom
- 05. Kitchen
- 06. Dining
- 07. Riser
- 08. Stairwell
- 09. Elevator
- 10. Apartment Entrance
- 11. Services/ Electrical
- 12. Bedroom
- 13. Balcony

Taranaki Street

Frederick Street

0 1 5.0 m

7.8 Exemplar Floorplan Layouts

This section outlines ways of laying out apartment floorplans to suit a wide range of occupants. This style of building can cater for everything from large family units, to small studio loft spaces and everything in-between using principles of spatial separation and sectional offset to achieve zoning and effective spatial configuration.

Although the design concept proposed in this research offers an approach where the clients decide upon (and build) their own personal interiors, for the purposes of this research an entire building has been developed in order to; 1) display what types of apartments can be achieved; 2) different design techniques to achieve such spaces, and 3) what interior components will need to be constructed in order to achieve the desired outcome.

Floorplan Exemplar I

Floorplan iteration (i) pictured here in figure 1.1 (see opposite) has been designed in such a way to achieve a medium sized loft unit suitable for a couple, a small loft unit ideal for a single occupant, and a Large loft unit with two bedrooms designed specifically for a small family (2 parents + 2 Children).

S. Small Loft - 45m²

Small Unit. Single bedroom loft apartment. Privacy not an issue for user as no physical separation between bedroom and living area. Visual separation using 1200mm slatted timber wall component and +300mm elevated floor using floor components. This sectional offset, creates zoning within small interior.

M. Medium Loft - 55m²

Medium Unit. Single bedroom loft apartment with lounge and office space. Privacy not an issue for user as no physical separation between bedroom and living area. Visual separation using 1200mm slatted timber wall component and +300mm elevated floor using floor components. This sectional offset, creates zoning within the small interior.

L. Large Loft - 75m²

Large Unit. Twin bedroom loft apartment with large lounge and living area. Privacy required as separation needed between bedrooms and living spaces. Standard gib clad panels utilised with additional of peg board wall system in childrens bedroom for additional storage.

FLOORPLAN EXEMPLAR TWO.

S. Small Studio

Occupier lives alone. Room for one person + additional space for possible guest(s).

M. Multiple Tenancy Unit

Multiple occupancy (couple). Room for three people to sleep + space for possible guest(s).

L. Family Unit

Multiple occupancy (family). Room for four + people to sleep. Adequate living space.

- 01. Master Bedroom
- 02. Kitchen
- 03. Bathroom/ W.C
- 04. Bedroom
- 05. Lounge/ living
- 06. Dining
- 07. Stairwell
- 08. Elevator
- 09. Services/ Electrical
- 10. Apartment Entrance
- 11. Balcony

FLOORPLAN EXEMPLAR THREE.

S. Couple Suite

Multiple occupancy. Single bedroom suitable for couple.

M. Medium Studio

Multiple occupancy (couple) + young child.

L. Large Studio

Single occupancy. Suitable for single parent and young child with need for extra space.

- 01. Master Bedroom
- 02. Kitchen
- 03. Bathroom/ W.C
- 04. Bedroom
- 05. Lounge/ living
- 06. Dining
- 07. Stairwell
- 08. Elevator
- 09. Services/ Electrical
- 10. Apartment Entrance
- 11. Balcony

IV.

FLOORPLAN EXEMPLAR FOUR.

S. Single Room Small

Single occupancy. Suitable for single parent and child.

M. Single Room Medium

Multiple occupancy (couple). Suitable for couple + Infant/ baby.

L. Double Room Large

Multiple occupancy (Family). Suitable for couple + young child.

- 01. Master Bedroom
- 02. Kitchen
- 03. Bathroom/ W.C
- 04. Bedroom
- 05. Lounge/ living
- 06. Dining
- 07. Stairwell
- 08. Elevator
- 09. Services/ Electrical
- 10. Apartment Entrance
- 11. Balcony

This page intentionally left blank.

7.9 Building Elevations

N.

NORTH ELEVATION.

0 1 5.0m

E.

EAST ELEVATION.

0 1 5.0 m

S.

SOUTH ELEVATION.

0 1 5.0m

W.

WEST ELEVATION.

0 1 5.0m

Aa.

Longitudinal Section A-a.

- 01. Meeting Room
- 02. Disabled WC
- 03. Building services duct
- 04. Building Storage
- 05. Elevator Access
- 06. Electrical/ Service plant room
- 07. Shared lounge/ Atrium
- 08. Pedestrian access to Frederick Street
- 09. Small loft unit
- 10. Large loft unit
- 11. Multiple Tenancy - Home share
- 12. Family Unit
- 13. Medium Studio Unit
- 14. Large Studi
- 15. Single bedroom (medium)
- 16. Double bedroom (large)
- 17. Outdoor green space
- 18. Central access/ building core
- 19. Access to roof terrace

Bb.

Transverse Section B-b.

- 01. Main Building Entrance - Pedestrian Access to footpath
- 02. Atrium
- 03. Access to meeting rooms & Disabled WC
- 04. Shared common space/ reception
- 05. Access to building workshop
- 06. Medium Size loft unit
- 07. Small loft Unit
- 08. Multiple Tenancy Unit
- 09. Small Studio
- 10. Couple Studio
- 11. Medium Studio
- 12. Single Bedroom (Medium)
- 13. Single Bedroom (Small)
- 14. Outdoor roof terrace (Communal access)
- 15. Central access/ building core - to roof terrace
- 16. Workshop vehicular access
- 17. Outdoor green space
- 18. Shared parking space - Guest/ programme staff vehicles
- 19. Site vehicular access
- 20. Indicates location of existing building

Figure 7.20:
Interior perspective render - Stage
One 'Structural Shell Completion'
<Authors own>

Figure 7.21:
Interior perspective render - Stage
One 'Structural Shell Completion' -
<Authors own>

Figure 7.22:
Interior perspective render -
Completed apartment. Lounge con-
figuration in large loft.
<Authors own>.

Figure 7.23:
Interior perspective render -
Completed apartment. Kitchen con-
figuration in Medium loft.
<Authors own>

Figure 7.24:
Interior perspective render -
Completed apartment. Medium loft.
<Authors own>

Figure 7.25:
Interior perspective render -
Completed apartment Bedroom
configuration in small loft.
<Authors own>.

Figure 7.26:
Exterior perspective render - Frederick Street pedestrian entrance.
<Authors own>

Figure 7.27:
Exterior perspective render - Frederick Street pedestrian entrance.
<Authors own>.

Figure 7.06 (right):
Interior perspective render - Stage
One 'Structural Shell Completion' -
<Authors own>

Figure 7.28:
Exterior perspective render - Work-
shop vehicular entrance.
<Authors own>

155
TARANAKI St.

Figure 7.29:
Exterior perspective render
Taranaki Street covered walkway
<Authors own>

Figure 7.30:
Exterior perspective render
Taranaki Street pedestrian entrance.
©Authors own

Figure 7.31:
Exterior perspective render -
West facade balconies
<Author's own>

Figure 7.32:
Exterior perspective render -
South facade mural.
<Authors own>

Figure 7.33:
Exterior perspective render -
View east towards Frederick Street.
<Authors own>.

Figure 7.34:
Exterior perspective render -
West facade mural
<Authors own>

Figure 7.35:
Exterior perspective render -
West facade.
<Authors own>

Chapter Eight: Conclusions

8.1 Overview

Chapter 8 summarises the strategic objectives and future improvements of this research. Firstly, this section outlines the key conclusions determined from design experimentations. Secondly, it will discuss the constraints and limitations experienced throughout. Finally, the potential applications of the research and possible future advancements will be explored.

8.2 Conclusion

New Zealand's current architectural discourse concerns affordable housing - or lack of. This is an issue hastily adding to our growing battle with homelessness which has unmistakably progressed in recent years. Homelessness is evolving into a problem we can no longer neglect. The lack of quality and affordable housing is impacting many Kiwi families and individuals. They are suffering and will continue to do so unless a collective housing solution for the transitionally homeless is developed.

This thesis set out to explore how architecture can play a crucial part in the fight against homelessness. This research provides bespoke spaces that sequentially become homes rather than temporary shelters. The key intention was to develop a universal system of permanent and affordable housing to facilitate the reassertion of independence by society's most vulnerable. This is a novel solution which contrasts the way in which we currently supply housing for New Zealand's transitionally homeless such as temporary or 'transitional' shelters. This novel "DIY" strategy enables residents with a low construction skill level the ability to craft their own home environments in central locations, with materials sourced from local hardware stores. This concept is envisioned to evoke conversation as to how we can deliver action against homelessness through the implementation of self-build housing.

The strategic objectives of this project are to test the validity of a multi-staged apartment complex on a selected site in urban Wellington. The development of this housing model resulted in a unique apartment solution which gives society's most at need a place they can call their own; a home. This thesis employed an integrated methodology which combined regional analysis, precedent case studies and a literature review. This informed a holistic knowledge base which design guidelines reflected upon at each stage of iterations to ensure the design validity.

Design iteration I 'Small Detached House' (see chapter 6) explores the development of small nuclear houses. This section sought to determine what was required in order to replicate the notion of 'Home' through experimentation with sizing, layout, and materiality. Principles of prefabrication, modular assembly and environmental responses were also studied to assess quality and affordability of the units. These tests were successful in developing a number of typologies which cohere with the developed guidelines. However, these typologies would not be suitable for implementation in urban Wellington as the lower density housing requires a much higher land use. This design could be explored further in other New Zealand regions or in Wellington's outer suburbs. This would aid in achieving effective housing for transitionally homeless at a broader scope. Sites with a central location would benefit the transitionally homeless the most as it would be close to local amenities and potential employment opportunities.

Self-build apartment housing is explored through Design Iteration II (chapter 6). This design experimentation sought to define a simplistic method of self-build construction so transitionally homeless of low-skill can craft their own quality homes

at an affordable rate. This section of research was investigated comprehensively to establish; 1) a design concept for an urban site, and 2) a potential operation framework of how such a design could be achieved. This self-build model is an option which appears to have significant potential for application in Wellington. To further assess the feasibility of such a housing model, cost assessments could have been undertaken to determine the validity of this concept compared to market housing rates in Wellington. This would have involved detailed cost assessments for labour at various stages of construction and for materials used. This would have been beneficial because it could prove that a housing intervention like what is being proposed in this research could potentially benefit a number of people in need of housing. It is predicted that with the dramatic reduction of labour cost attributed to the self-build element this would lower overall build cost. Although this claim may be evident it would be asserted further if detailed cost assessments were to be carried out.

8.2.1 Constraints & Limitations

A major constraint faced during the initial research stage was the limited number of organisations available for interview. Several of the organisations contacted for interviews were unavailable due to lack of resources or time constraints. The interviews proved vital sources of information used throughout this research. It would have been beneficial to obtain a broader range of knowledge and insight from a variety of organisations involved with the provision of housing for Wellington's homeless. It would have been informative to hear from Dwell Housing Trust or Salvation Army Housing as these organisations could work as potential developers for the framework developed in this thesis. Both organisations strive to provide quality housing at an affordable rate, therefore a solution relevant to their vision may be an appealing venture to undertake. These organisations are also current providers of housing so their critique and insight would have been beneficial to assess how such a unique intervention would be carried out. It would have been beneficial to discuss with representatives of these organisation on matters regarding material selection, cost assessments, and the operation framework of such a housing system.

Gaining ethics approval was another constraint which delayed the initial progress of this research. In order to commence host interviews, an ethics application and approval was required. Hearing from transitionally homeless first-hand would be valuable in assessing whether or not the developed design was to be viable. For it is these individuals who would occupy and interact with the proposed housing scheme. Outreach to this population was limited to the ethics approval obtained which was to interview organisations only. To successfully understand this population a large group would need to be interviewed; this was not possible in the scope of this project.

8.2.2 Potential Applications of Research

This thesis focussed on the implementation of housing for the transitionally homeless in order to reduce the number of people sleeping in temporary or substandard housing. As this research progressed it became clear that the issue of homelessness extends far beyond the reach of architectural intervention alone. Rather, an integrated approach, building on work such as Housing First's is required to develop an effective housing solution. It is anticipated that the work conducted here will be of interest to councils, charitable organisations and designers involved with the provision of housing for the transitionally homeless. The outcomes of this research have potential to facilitate an innovative housing intervention that contribute to reducing the number of transitionally homeless in Wellington.

Beyond practical applications, this thesis serves as an impetus for changing the culture of homelessness, policy direction and how the public approaches this issue. The stigma plaguing the transitionally homeless community must be uplifted and redefined before any attempt to approach this systemic issue can be addressed. This thesis challenges preconceptions of what it means to be transitionally homeless. It is not necessarily those with drug and alcohol addictions or mental health issues who comprise this particular group of society – rather, it is typical Kiwi's who have run into hardship or have suffered unforeseen circumstances such as redundancy in the current economical situation. This thesis explores what it means to be the opposite of homeless – what it means to have a home, as opposed to home ownership. It causes the reader to reflect upon the concept of home and how it can be achieved by everyone – albeit in different circumstances.

8.2.3 Future Advancement

The next step would be 1:1 scale modelling if this research time frame was to be extended. This would be beneficial to assess; 1) the physical validity of the intervention, 2) the ease of build or carpentry skill required to construct the interior components, and 3) cost efficiency of utilising materials sourced from local hardware stores and simplistic design methods.

This research sought to provide an example of how an effective self-build apartment housing scheme could work in urban Wellington. 133 Taranaki Street was selected and developed as a potential site because of its location and relative size. If time allowed, this thesis would identify and develop a series of sites around Wellington and alternative locations around New Zealand. The potential for a greater national outreach could be evaluated from this development.

It became obvious at various stages of development that this DIY method of apartment living may also be an attractive venture for a wider range of people not just the transitionally homeless or those in immediate need of permanent shelter. The reduction of overall unit price attributed to the self-build fit-out stage could also appeal to first home buyers, small families looking to downsize, or professionals looking for a low maintenance inner city loft.

8.2.4 Overall

This thesis successfully tests the implications of a self-build housing intervention for the transitionally homeless in urban Wellington. This research contributes to the body of knowledge of effective housing for New Zealand's homeless by exploring a greater understanding of quality and affordable design techniques. The establishment of an innovative solution, suitable for a diverse range of family and individual typologies, could contribute to a solution of ending homelessness in New Zealand.

Works Cited

Adams, Amy (Hon): Minister of Social Housing. (2017). "New emergency housing development open". SCOOP Media, New Zealand Government.

Ahuru, Bernice. Te Whakamura Ai Te Ahi. Interview: Victoria University of Wellington - School of Architecture. J. R. Goodger.

ArchDaily (2013). "Transition Centre of 24 housing in Rambouillet / Benjamin Fleury." Retrieved from; <<https://www.archdaily.com/342090/transition-centre-of-24-housing-in-rambouillet-benjamin-fleury>>.

Archello (2013). "Transition Centre - Benjamin Fleury." Retrived from; <<https://archello.com/project/transition-centre>>.

Bierre, Sarah., Howden-Chapman, Philippa., Early, Lisa. (2013). Homes People Can Afford - How to Improve Housing in New Zealand. New Zealand, National Library of New Zealand Cataloguing-in-Publication Data. ISBN: 978-1-927242-25-4.

Blood, Imogen., Copeman, Ian., Goldup, Mark., Pleace, Nicholas., Bretherton, Joanne., Dulson, Shelly. (2017). Housing First Feasibility Study for the Liverpool City Region: Final Report, University of York. Retrieved from; < https://www.crisis.org.uk/media/237545/housing_first_feasibility_study_for_the_liverpool_city_region_2017.pdf>.

Building Guide. (2018) The Cost of Building in New Zealand. (pp. 1).

Davies, Sam. (2004). Designing for the Homeless - Architecture that Works. Berkeley, California, University of California Press Ltd.

Demographia. (2018). 14th Annual Demographia International Housing Affordability Survey: 2018 Rating Middle-income Housing Affordability (pp. 19-21). Retrieved from <http://demographia.com/dhi.pdf>.

Fairfax Media Ltd. (2018) 'Prison cell' emergency housing units will house people for three month. Western Leader

Formance NZ. (2018). Formance Design Guide: The Forever Home. Level 1, 134 Victoria Street Christchurch Central, 8013 Christchurch New Zealand: (pp.18).

Holland, Karen. (2018). Te Puaroha Compassion Soup Kitchen. Interview: Victoria University of Wellington - School of Architecture. J. R. Goodger.

Holt Schneider, Casey. (2015). A part of something: The importance of transitional living programs within a Housing First framework for youth experiencing homelessness. Chicago, IL, United States, University of Illinois, Chicago.

Housing First Auckland. (2018). "Homelessness." What are our definitions of homelessness and ending homelessness?. Retrieved from; <<https://www.housingfirst.co.nz/homelessness>>.

Institute of Global Homelessness (2015). "Why Global?". Retrieved from; <<http://www.ighomelessness.org/about>>.

Johnson, Alan., Howden-Chapman, Philippa., Eaqab, Shamubeel. (2018). A Stocktake of New Zealand's Housing. Ministry of Business Innovation & Employment. (pp. 38)

Mears, Alison. (2012). Seeking Shelter: An investigation into solutions for the homeless. Los Angeles: Skid Row Housing Trust. (pp. 23).

Ministry of Business Innovation & Employment (2017). Briefing for the Incoming Minister of Housing & Urban Development, New Zealand Government: (pp. 5).

Ministry of Social Development (2016). New emergency housing funding model. Emergency Housing, New Zealand Government.

Ministry of Social Development (2017). Transitional Housing Helping to Rebuild Lives. New Zealand Government. Retrieved from; < <https://www.msd.govt.nz/about-msd-and-our-work/work-programmes/social-housing/case-study-rebuilding-lives.html> >.

New Zealand Parliament (2014). Homelessness in New Zealand. New Zealand, Parliamentary Library.

OECD (2017). "As Cities Grow Worldwide, So do the Number of Homeless." Retrieved from; <<https://yaleglobal.yale.edu/content/cities-grow-worldwide-so-do-numbers-homeless>>.

Rinaldi, Marco. (2017). "JAGTVEJ 69 - Vendepunktet by WE Architecture and Erik Juul." A AS Architecture. Retrieved from; <<http://aasarchitecture.com/2017/03/jagtvej-69-vendepunktet-architecture-erik-juul.html>>.

United Nations - Human Rights Council. (2015). Report of the Special Rapporteur on adequate housing as a component of the right to an adequate standard of living, and on the right to non-discrimination in this context.

University of British Columbia School of Architecture + Landscape Architecture (2012). Future Social - Design Ideas, Essays and Discussions on Social Housing for the 'Hardest-to-House', Blue Imprint Ltd.

Wellington City Council (2014). Te Mahana: Ending Homelessness in Wellington - A Strategy for 2014-2020. Wellington, New Zealand (pp. 13).

Wellington City Council (2017). Te Mahana Story. Wellington, New Zealand.

Wellington City Council. (2012). Central Area Urban Design Guide. District Plan. Volume 2: Design Guides: (pp. 10-15).

Bibliography

Ayers, Susan. (2007). *Architecture and Health*. Cambridge Handbook of Psychology, Health and Medicine. Baum, Andrew, Mcnamus, Chris., Newman, Stanton., Wallston, Kenneth., Weinman, John., West, Robert. New York, New York, Cambridge University Press: (pp. 23-26).

Beehive.govt.nz (2016). "More housing on its way for vulnerable families." Retrieved from; <<https://www.beehive.govt.nz/release/more-housing-its-way-vulnerable-families>>.

Boekel, Andrea., Boschetti, Joseph. (2006). *Sustainable French Timber Houses - L’Affaire de Wood*. Victoria, Australia The Images Publishing Group.

Burt, Martha. R. (2006). *Characteristics of Transitional Housing for Homeless Families*. Washington, DC, Department of Housing and Urban Development.

Burt, Martha. R. (2010). *Life After Transitional Housing for Homeless Families*. U.S Department of Housing and Urban Development, Urban Institute - Office of Policy Development and Research.

Community Housing New Zealand (2017). *Affordable Housing Continuum*. C. T. H. C. A. H. v. dec(2). New Zealand, Community Housing Aotearoa Nga Wharerau o Aotearoa.

Davies, Sam. (1995). *The Architecture of Affordable Housing*. Berkeley, California, University of California Press Ltd.

Fleury, Benjamin. (2013). "Maison Relais de 24 Logements en THPE." Retrieved from <<https://benjaminfleury.com/15-habitats/realisations/42-maisonrelais>>.

Graham, John. R., Walsch, Christine. A., Sandalack, Beverly. A. (2008). *Homeless Shelter Design - Considerations for shaping shelters and the Public Realm*. Calgary, Alberta, Detselig Enterprises Ltd.

Harwood, Barbara. B. (1997). *The Healing House: How Living in the Right House Can Heal You Spiritually, Emotionally, and Physically*, Hay House. ISBN: 9781561704279

Homelessness Australia (2017). *A National Homelessness Strategy: why we need it. Strengthening the service response to people who are homeless or at risk of homelessness*, Homelessness Australia - Creating a Framework for Ending Homelessness.

Howell, John. (2017). *Homeless - To all People Hungry and Homeless*. Eastbourne, Wellington, MakaroP Press.

Kidd, Sean., Slesnick, Natasha., Frederick, Tyler., Karabanow, Jeff., Gaetz, Stephen. (2018). *Mental Health & Addiction Interventions for Youth Experiencing Homelessness: Practical Strategies for Front-line Providers*. Toronto, Canada.

Martin, Selena. (2017). *The Nest - A Community for the Homeless*. School of Architecture Wellington, New Zealand, Victoria University of Wellington. Master of Architecture (Professional).

Maslow, Abraham. H. (1943). *A Theory of Human Motivation*, York University, Toronto, Ontario.

New Zealand Government (2017). "Case Study: Transitional housing helping to rebuild lives." from <https://www.msd.govt.nz/about-msd-and-our-work/work-programmes/social-housing/case-study-rebuilding-lives.html>.

Parsell, Cameron., Moutou, Ornella., Lucio, Eduardo., Parkinson, Sharon. (2015). *Supportive Housing to Address Homelessness*, Australian Housing and Urban Research Institute: University of Queensland.

Pleace, Nicholas. (2017). *Housing First: European Observatory on Homelessness*.

Seelig, Michael. Y. (1978). *The Architecture of Self-Help Communities*. New York, New York, Architectural Record Press.

Statistics New Zealand (2009). *New Zealand Definition of Homelessness*. Wellington, New Zealand.

Svensson, Katarina. E. (2015). *Preparing for Life After Homelessness: Transitional Housing for the Homeless*. Faculty of Architecture, University of Maryland. Master of Architecture.

Takahashi, Satoko. (2012). *Finding Hope in Zen: A Design of a Women's Transitional Housing Facility*. Department of Interior Design, University of Manitoba, Winnipeg. Master of Interior Design.

Te Ara Encyclopedia of New Zealand (2007). "Turangawaewae - a place to stand." from <https://teara.govt.nz/en/papatuanuku-the-land/page-5>.

Tilley, Elspeth. (2018) *Te Ha Tangata: A Human Library on Homelessness*. Oyisima-Pirini, A., Pickering, S., Taiapa, R., Williams, S., Rio, M., Swenson, V., Dewes, E., Downs, B., Ifi, J., Sidal, S., Holland, K., Taylor, N., Taite, J., Petrie, M., Fox, E., Tilley, E., Goulter, S. Massey University School of English & Media Studies. ISBN: 9780473422691

Woo, Rolsten., Mangin, John. (2009). *What is Affordable Housing: NYC Edition. Envisioning Development/ Guide No. 1.*

List of Figures

All figures not attributed are author's own.

Figure 2.01

Maslow, H. Abraham. Maslow's Hierarchy of Needs Pyramid. 2018. Image; Mcleod, Saul. <<https://www.simplypsychology.org/maslow-5.jpg>>.

Figure 4.01

Ministry of Social Development. Transitional housing complex at Luke Street. 2017. Photograph; New Zealand Government. <<https://www.msd.govt.nz/documents/about-msd-and-our-work/work-programmes/social-housing/transitional-housing-fact-sheet.pdf>>.

Figure 4.02

NZ Herald. 'Prison Cell' Emergency Housing, West Auckland. Auckland. Photograph; Tristram Clayton. <<https://arc-anglerfish-syd-prod-nzme.s3.amazonaws.com/public/KCQCPW5L4FAVVKKLSVWN7QPLWQ.jpg>>.

Figure 4.03

Juul, Eric. Jagtvej 69 Housing. Copenhagen. Artistic Render; WE Architecture. <https://images.adsttc.com/media/images/58ca/ba1b/e58e/cec1/a900/0269/slideshow/01_we-architecture_front-view.jpg?1489680912>.

Figure 4.04

Fleury, Benjamin. Transition Centre of 24 Housing Rambouillet. France. Photograph; David Boureau. <https://images.adsttc.com/media/images/513a/48e0/b3fc/4b0e/2000/0098/large_jpg/RackMultipart20130308-29360-euwnpx.jpg?1362774208>.

Figure 4.05

Richter, Praeger. Ausbauhaus Neukolln. 2016. Photograph; Praeger Richter Architects. <https://payload.cargocollective.com/1/5/165174/6834960/141027_DSC1614_Aubauhaus_Neukoelln_086_670.jpg>.

Figure 4.06

Richter, Praeger. Ausbauhaus Neukolln. 2016. Photograph; Praeger Richter Architects. <https://payload.cargocollective.com/1/5/165174/6834960/151119_DSC04328_Neukoelln_243_670.jpg>.

Figure 4.07

Heide & Von Beckerath. R50 Apartments. 2013. Photograph; Andrew Alberts. Sourced from Archdaily; < https://www.archdaily.com/593154/r50-nil-cohousing-ifau-und-jesko-fezer-heide-and-von-beckerath/54cb0778e58ece5c5e00030a-portada_r50_aa_dsc7194_1-jpg >.

Image Permission(s);

Street art used for exterior renders

BMD. Rat Pedigree. 2015. Photograph: Norman Heke. bmdisyourfriend.com/outdoors. Wellington. < <https://www.flickr.com/photos/wiredforsound23/23903758086/> >.

BMD. Te Papa Shark Mural. 2013. Photograph. bmdisyourfriend.com. Wellington. <<http://bmdisyourfriend.com/wp-content/uploads/2014/05/tepapa-shark-wall1.jpg>>.

BMD. Rodent Race. 2013. Photograph: Blake Dunlop. bmdisyourfriend.com/indoors. Wellington. < http://bmdisyourfriend.com/wp-content/uploads/2013/11/recentbmd_25.jpg >.

BMD Image permission(s) granted by both BMD members; Andrew J. Steele & Damin (dside) on October 29, 2018.

Harte, Jesse. Son of Tamanuitera. 2015. Photograph: Maryja Garden. instagram.com/maryjasara. Wellington. < <https://www.instagram.com/p/BG6cBt9ydtf/> >.

Image permission(s) granted by original artist; Jesse Harte on February 5, 2019.

Appendix One:

NZ Housing Continuum

01.

T.I. NEW ZEALAND HOUSING CONTINUUM

Form of housing	Characteristics	Residents / form of subsidy
Homeless	Those living either without, or in temporary / makeshift shelter. Living on the street, inhabiting improvised dwellings or those living in vehicles.	Residents are those who have no other options for secure accommodation. No job or income, and may have no family or social connections.
Emergency Housing	Ministry of Social Development deemed that there is no other option for accommodation then emergency accommodation will be sourced for you. Generally, organised as Hostel or Motel type accommodation. Residents can stay for up to 12 weeks, while they seek permanent accommodation.	Those who cannot, or those without the ability to pay for housing. Many have either mental, or physical conditions and/or disabilities. When in MSD emergency housing residents pay no more than 25% of income – however if on a benefit, this amount will be redirected from weekly payments. The remainder subsidised by public funding.
Temporary Housing	Generally, these are motels and hotels, backpacker hostels, boarding houses, or even free accommodation in exchange for working on-site. Often with shared facilities, and furniture / linen may or may not be supplied.	Those seeking accommodation for short period, waiting for emergency or transitional housing. Those without the ability to pay for housing at present time. Combination of public funding and benefit subsidy percentage.
Transitional / Supportive Housing	Transitional housing provides short-term housing for families or individuals who don't have anywhere to live and have an urgent need for a place to stay. Often includes a combination of living arrangements. From single room occupancy to studio units or shared residences. Social services are generally introduced, programs for residents to develop life skills, budgeting advice, and job training.	Those struggling to find a place to live, or unable to pay rent. Assessed by Work and Income as having the greatest priority. People living in transitional housing pay rent of up to 25 per cent of their income, which is in line with income-related rents for social housing. The balance is subsidised to providers by the government.
Social Housing	Social housing is designed specifically for people with lower income, struggling to afford average market rent. Generally multi-story housing units owned by the government in urban areas. Can stay for as long as still eligible.	Those struggling to find a place to live, or unable to pay rent. Amount of rent paid based on resident income, and income of those sharing residence at time of housing offer acceptance.
Rental Housing	Rental properties include any housing that is not owned by occupant. Usually privately owned and operated by individuals or developers. Generally, apartment units, attached dwellings or self-contained units.	Those who can afford market rate of rent yet either choose or cannot afford to buy property. Accommodation supplement provided to those needing help with rent, board, or the with the cost of owning a home. Dependant on annual income + Assets.
Owner Occupied Housing	Single family house or multi family unit.	Those who can pay market price. Often subsidised if resident qualifies for kiwi saver scheme, or additional government funding.

Increased Subsidy

Increased Independence

Appendix Two:

Detailed Organisation Analysis

02.

T.2 HOMELESS ORGANISATIONS

	Population	24/7 Accommodation Service	Male	Female	Families	Bed	Food/Water	Shower Facilities	Laundry Facilities	Clothing	Career Advice	Accommodation Advice	Education Organisation	Design Considerations
Wellington Night Shelter	48													
Wellington Homelss Women's Trust	5													
Salvation Army Transitional Housing	-													
Dwell Housing Trust	n/a													
Te Puaroa - Compassion Soup Kitchen	100													
Te Whakamura Ai te Ahi	n/a													

WELLINGTON NIGHT SHELTER

The Wellington Night Shelter is a Wellington based non-profit organisation that provides emergency accommodation for men experiencing homelessness. The Night Shelter also provides additional support in the form social and health services to ensure the overall health and well-being of all its residents – they are a first point of contact for men often caught in crisis situations, giving them a good night's rest and a chance to start a self-care process.

The Wellington Night Shelter works in partnership with numerous other organisations including; the Capital Coast District Health Board, Suzanne Aubert Compassion Centre, and the St. Vincent de Paul Society.

There are three main typologies of accommodation at the Wellington Night Shelter. Stage 1 is a dormitory style service which include a bed for the night, shower facilities, clothes washing, and a cup of tea – however occasionally food is supplied once it has been donated and made available. Stage 2 is hostel style accommodation where clients generally stay for longer than one night. This is where some social services begin to be introduced to help address the individual issues and needs of clients. Ideally helping them rebuild life skills and prepare them to get back into permanent and secure housing. Stage 3 is on-going social support once clients get back into the community, as the Wellington Night Shelter strive to improve the health and well-being of all their residents.

Unit Types:

- Dormitory Style Units
- Hostel Units

Duration of Stay:

- 1 Night - Dormitory
- 1+ Night(s) - Hostel Accomodation

ACCOMMODATION

SOCIAL
SUPPORT

304 TARANAKI STREET, MT COOK, WELLINGTON 6011

KIRSTY BUGGINS (MANAGER)

PHONE: 04 385 9546

EMAIL: [INFO@WELLINGTONNIGHT
SHELTER@ORG.NZ](mailto:INFO@WELLINGTONNIGHTSHELTER.ORG.NZ)

WELLINGTON HOMELESS WOMEN'S TRUST

The Wellington Homeless Women's Trust is another non-profit, volunteer run organisation that provides accommodation and social support for Women in Wellington City. Women who seek support from the Homeless Women's Trust are generally in vulnerable positions with nowhere to call home. Often from abusive or broken homes, these women need a safe and supportive environment in order to get their lives back in order. Often with children and young families, clients can stay for a period of up to three months.

The women-only accommodation unit is a fully furnished home that can house up to five women at a time. Full kitchen and laundry facilities are supplied as well as social support that help clients reach goals set upon arrival. The three month programme aims to establish confidence and allow women to be more independent, with the goal in getting them back into working society, and permanent housing. The Wellington Homeless Women's Trust has three fundamental goals as part of their strategy; 1) to Sustain – 'Become a charity that is fully funded and self-sustaining throughout all offered help services'; 2) to Grow – 'Provide homeless women in Wellington a wider range of support services and accommodation solutions under one roof.'; 3) to Educate – 'Create more social awareness within our community about homeless and the hidden issues that contribute.'

Unit Types:

- 5 Bedroom fully furnished house

Duration of Stay:

- 3 Month Programme

ACCOMMODATION

SOCIAL
SUPPORT

FOOD +
WATER

PO Box 1784 Wellington

Phone: -

Email: Manager@homeless.org.nz

THE SALVATION ARMY

The Salvation Army of New Zealand offer a wide range of supportive accommodation services for all types of people. Three predominant categories that the Salvation Army cater for are; 1) Transitional housing for those needing immediate shelter while getting their life back on track; 2) Housing for over 55's – an essential service for elderly people with low-income, and; 3) Post Prison Supportive Housing. This services helps those who have been in prison and are having difficulty reintegrating themselves into productive society and finding secure and permanent accommodation. Wellington Salvation Army has three current accommodation facilities; one located in Porirua which is a short term transitional housing for women, children or families, Hutt City emergency housing which provides social support and emergency housing for families, then there is the Wellington City emergency housing for families are supportive accommodation for adults with intellectual disabilities.

The transitional facility located in Porirua is for those people who have been living on the street, in prison or in short term accommodation that's no longer available. They provide a safe and stable base alongside social support services that allow clients to get back on their feet and integrate themselves back into community.

Unit Types:

- (TBC)

Duration of Stay:

- (TBC)

ACCOMMODATION

SOCIAL
SUPPORT

FOOD +
WATER

89 Warspite Avenue, Cannons Creek, Porirua

Phone: 04 389 0594

Email: porirua_cm@nzf.salvationarmy.org.nz

TE PUAROA SOUP KITCHEN

Te Puaroa Compassion Soup Kitchen is a Wellington based organisation - operating for over 116 years. It was founded originally in 1899 by Suzanna Aubert of 'The Congregation of the Daughters of our Lady of Compassion' the Compassion Soup Kitchen is the only New Zealand founded religious congregation. It was identified at the time that Wellington was struggling; employment rates were low and permanent housing was not a luxury not everyone could afford. Home-nursing of the 'Sick Poor' was the first issue that the Compassion tackled in Wellington, however this soon turned into a wide range of services including; childcare and residential care for invalids.

At present, the soup kitchen can serve up to approximately 100 people at any one time, despite the namesake, the soup kitchen also provides 'Family style meals' as they have identified that many people rely on their services to meet their daily recommended food intake. Breakfast is free of charge to any who wishes to come, however because of the higher food quality the dinner is subsidised to \$2 per person.

In addition to food services the Compassion Soup Kitchen also provides computer access to its guests, alongside assistance from volunteers, clients receive help on writing a C.V and cover letters etc. Occasionally guests are also invited to go out fishing on order to catch food that is brought back into the kitchen and prepared for guests.

**SOCIAL
SUPPORT**

**FOOD +
WATER**

132 Tory Street, Te Aro, Wellington 6011

Karen Holland (Manager)

Phone: 04385 9299
027 627 0991

Email: Karen.H@compassion.org.nz

TE WHAKAMURA AI TE AHI

Te Whakamura is a council funded community partnership between Kahungunu Whanau Services and Downtown Community Ministry (DCM). The organisation focusses on supporting those categorised as ‘Chronically Homeless’ – Those who regularly sleep rough or in makeshift shelters.

Te Whakamura Ai te Ahi translates to English ‘To keep the homes fire burning’ – which fits cohesively alongside the Wellington Te Mahana (warmth) Homeless Initiative of ending homelessness in New Zealand. The warmth that both these phrases speak of is the feeling of ‘home’ or sense of belonging is something that can only be found in a homely environment. This is something that everyone should experience, not just a privilege restricted to the wealthy. Te Whakamura combines the strengths of cultural competency, social services, and expertise in working with the chronically homeless in order to address the issue of homelessness in not just Wellington, but New Zealand in general. Their main services include; 1) Street outreach – front line services monitoring activity on the streets where there are concerns of people sleeping rough or on the streets; 2) Case management – the developing of personalised care plans and working with individuals in order to secure sustainable, and healthy living environments; 3) Community involvement – working alongside other agencies and organisations to develop shared solutions for understanding and minimising homelessness in Wellington.

**SOCIAL
SUPPORT**

Level 1-2 Lukes Lane, Te Aro, Wellington 6011

Bernice Te Ahuru (Manager)

Phone: 04 384 6252

Email: bernice@nkkp.org.nz

DWELL HOUSING TRUST

The Dwell housing trust is an organisation aimed at providing a range of appropriate yet quality housing services for New Zealanders with low-income, or physical or mental disabilities. Their overall vision is to see well-housed Wellington communities where people live and flourish in society – this is done through the provision of affordable and quality homes. With emphasis on innovative and sustainable housing designs, Dwell Housing Trust value putting people first, building relationships with residents in order for them to live better and more comfortable lives. An organisation such as Dwell offers better value for money as they have certain leverage over government funding from various public/ private resources. This allows the Dwell Housing Trust to reach out and meet the needs of more New Zealanders in need of permanent housing.

The housing services provided by Dwell Housing Trust include; 1 Supportive housing units, these cater for the accommodation needs of people suffering with psychological illness; 2) group housing for individuals seeking a social living environment; 3) affordable rental housing and; 4) a share home ownership programme supporting first home buyers.

Unit Types:

- Supportive Housing Units

Duration of Stay:

- (TBC)

ACCOMMODATION

Level 5, 173-175 Victoria Street, Wellington 6011

Phone: 04 384 4854

Email: info@dwelling.org.nz

Appendix Three:

Detailed Precedent Analysis

03.

T.3 PRECEDENT STUDY

Case Study

	Location	Building Type	Single Occupancy Units	Communal Units	Facilities - Bathroom/ Laundry	Utilities - Electricity/ Water	Social Support - On-site	Recreational Facilities	Modular - Future Expandable	Prefabrication
Luke Street Housing	Auckland, NZ	Single Family Housing		●	●	●		●		
West Auckland Transitional Units	West Auckland, NZ	Self Contained single unit	●		●	●				●
Vendepunktet - Jagtvej 69	Copenhagen, Denmark	Medium Density Apartments	●	●	●	●	●	●	●	●
Transition Centre	Rambouillet, France	Low Density Apartments	●	●	●	●	●	●		
'Homes for Homeless'	London, UK	Nuclear Pod	●						●	
Homeless Studio	Los Angeles, USA	Self Contained single unit	●						●	
'Homed' Cluster Communities	New York City, NY, USA	Self Contained single unit	●	●	●	●			●	●
ISOSPACE Container Conversions	London, UK	Modular Container Units	●	●	●	●		●	●	●
'Move-on' Flat Pack Homes	London, UK	Studio Flat	●	●	●	●			●	●

LUKE ST. TRANSITIONAL HOUSING

ACCOMMODATION

SOCIAL
SUPPORT

32 - 44 Luke Street, Otahuhu, Auckland

Designer: Housing New Zealand

Units types: 27 - 2 Bedroom Units
7 - 3 Bedroom Units
17 - 4 Bedroom Units

Duration of stay: 12 - 14 Weeks +

HENDERSON TRANSITIONAL HOUSING

ACCOMMODATION

SOCIAL
SUPPORT

32 - 44 Luke Street, Otahuhu, Auckland

Designer: Housing New Zealand

Units types: 27 - 2 Bedroom Units
7 - 3 Bedroom Units
17 - 4 Bedroom Units

Duration of stay: 12 - 14 Weeks +

This page intentionally left blank.

JAGTVEJ 69

VENDEPUNKTET

ACCOMMODATION

SOCIAL
SUPPORT

Jagtvej 69, Copenhagen, Denmark

Designer: WE Architecture

Units types: TBC

Duration of stay: TBC

TRANSITION CENTRE APARTMENTS

ACCOMMODATION

SOCIAL
SUPPORT

FOOD +
WATER

31 Rue De La Prairie, Rambouillet, France

Designer: Benjamin Fleury Architecture

Units types: 19 - Apartment Units

Duration of stay: TBC

Appendix Four:

Overview of Wellington Homeless Statistics

04.

POPULATION OF HOMELESSNESS IN WELLINGTON

ETHNICITY

LIVING SITUATION

AGE